SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FED 10% STATE 0005	RURAL 90% FED 10% STATE 0005	
20200100	EARTH EXCAVATION	CU YD	16612	6302	10310	
20200200	ROCK EXCAVATION	CU YD	200		200	
20400800	FURNISHED EXCAVATION	CU YD	1856	756	1100	
21400100	GRADING AND SHAPING DITCHES	FOOT	72274	19474	52800	
* 25000210	SEEDING, CLASS 2A	ACRE	37	13	24	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3324	1155	2169	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3324	1155	2169	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3324	1155	2169	
* 25100115	MULCH, METHOD 2	ACRE	37	13	24	
* 25100630	EROSION CONTROL BLANKET	SQ YD	42719	4194.4	38524.6	
28000400	PERIMETER EROSION BARRIER	FOOT	18947	1888	17059	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29	7.9	21.1	
40600300	AGGREGATE (PRIME COAT)	TON	139	37.5	101.5	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1699	657	1042	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FED 10% STATE 0005	RURAL 90% FED 10% STATE 0005	
40600990	TEMPORARY RAMP	SQ YD	1722	680	1042	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	12929	3483.7	9445.3	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	307.3	150.2	157.1	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	13746	2095	11651	
44000400	GUTTER REMOVAL	FOOT	27890	10370	17520	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	418	158	260	
44022027	PARTIAL DEPTH REMOVAL 2 1/2"	SQ YD	843	95.1	747.9	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	817	245	572	
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	78	38	40	
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	135	27	108	
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	67		67	
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	55		55	
44201299	DOWEL BARS 1 1/2"	EACH	2254	989	1265	
44213100	PAVEMENT FABRIC	SQ YD	201	82	119	

28

* SPECIALTY ITEM

FILE NAME = c:\pw.work\pwidot\millerraj\d0249132\d876f92-sht-plan-2.dgn	USER NAME = millerraj	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/10/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS | SHEET NO. 1 OF 3 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	(74-1, 75, 75-1)RS-3	RANDOLPH	130	3
		CONTRACT NO. 76F92		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT