

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY 0005 URBAN
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	189	189
40600990	TEMPORARY RAMP	SQ YD	1963	1963
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	3358	3358
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	10192	10192
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	11980	11980
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	37428	37428
44000168	HOT-MIX ASPHALT SURFACE REMOVAL, 4 3/4"	SQ YD	21705	21705
44000173	HOT-MIX ASPHALT SURFACE REMOVAL, 6"	SQ YD	3204	3204
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	151	151
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	32	32
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	117	117
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	11	11
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	200	200
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	192	192

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY 0005 URBAN
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	116	116
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	267	267
44201019	CLASS B PATCHES, TYPE II, 14 INCH	SQ YD	8	8
44201299	DOWEL BARS 1 1/2"	EACH	1084	1084
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	20	20
44213100	PAVEMENT FABRIC	SQ YD	732	732
44213200	SAW CUTS	FOOT	4316	4316
44213204	TIE BARS 3/4"	EACH	176	176
48203100	HOT-MIX ASPHALT SHOULDERS	TON	230	230
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1

FILE NAME =	USER NAME = elyaskordio	DESIGNED -	REVISED -
c:\pwork\pwork\elyaskordio\d0910383\0376g86-shr-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -
	PLOT DATE = 4/12/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2	(101,102) RS-2, 202RS-4	MADISON	69	3
CONTRACT NO. 76G06			ILLINOIS FED. AID PROJECT	