

RESURFACING

LOCATION STATION TO STATION				HOT-MIX ASPHALT SURFACE COURSE MIX "D", N90 [SURFACE]	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N90 [BINDER]	BITUMINOUS MATERIALS (PRIME COAT) *	AGGREGATE (PRIME COAT)
				TON	TON	GAL	TON
IL 1 (FAP 332) WHITE COUNTY							
URBAN LIMITS							
STA	474+00.00	TO	STA 474+63.00	29	15	60	1.0
STA	474+63.00	TO	STA 475+00.00	17	9	36	0.5
STA	475+00.00	TO	STA 475+70.00	32	16	68	1.0
STA	475+70.00	TO	STA 488+80.00	568	284	1,216	11.0
STA	488+80.00	TO	STA 489+20.00	13	7	26	0.5
STA	489+20.00	TO	STA 493+63.00	137	69	292	2.5
STA	493+63.00	TO	STA 498+70.00 BK	124	62	264	2.5
STA	497+94.74 AH	TO	STA 502+75.00	99	50	212	2.0
STA	502+75.00	TO	STA 552+00.00	1,104	552	2,364	20.0
URBAN MAINLINE TOTALS				2,123	1,064	4,538	41.0
URBAN SHOULDERS				629	316	1,338	10.0
URBAN TOTALS				2,752	1,380	5,876	51.0

* MAINLINE QUANTITIES REFLECT TWO APPLICATIONS

FILE NAME =	USER NAME = \$USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	RESURFACING SCHEDULE (URBAN)			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pwork\pwork\weemsbf\0300388\78287.sht.pln.dgn		DRAWN -	REVISED -					332	(3,3-2,2)RS-3	WHITE	49	30	
		CHECKED -	REVISED -			SCALE:	SHEET 30 OF 49 SHEETS	STA.					CONTRACT NO. 78287
		DATE -	REVISED -										ILLINOIS FED. AID PROJECT