

# RESURFACING

LOCATION STATION TO STATION				HOT-MIX ASPHALT SURFACE COURSE MIX "D", N90 [SURFACE] TON	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N90 [BINDER] TON	BITUMINOUS MATERIALS (PRIME COAT) * GAL	AGGREGATE (PRIME COAT) TON
IL 1 (FAP 332) WHITE COUNTY							
RURAL LIMITS							
STA	552+00.00	TO	STA 563+00.00	247	124	528	4.5
STA	563+00.00	TO	STA 581+27.90	410	205	878	7.5
STA	583+19.90	TO	STA 657+99.07	1,536	768	3,290	27.5
STA	657+99.07	TO	STA 667+34.92	193	97	412	3.5
STA	667+34.92	TO	STA 695+60.00	581	291	1,244	10.5
STA	695+60.00	TO	STA 701+00.00	111	56	238	2.0
STA	701+00.00	TO	STA 704+76.70	106	53	226	2.0
STA	704+76.70	TO	STA 709+74.42	177	89	378	3.5
STA	709+74.42	TO	STA 712+35.00	73	37	156	1.5
STA	712+35.00	TO	STA 762+35.60	1,027	514	2,200	18.5
STA	762+35.60	TO	STA 775+95.53	280	140	598	5.0
STA	775+95.53	TO	STA 876+28.13	2,061	1,031	4,414	37.0
STA	876+28.13	TO	STA 887+15.00	224	112	478	4.0
STA	887+15.00	TO	STA 930+05.25	881	441	1,888	16.0
STA	930+05.25	TO	STA 942+22.62	250	125	536	4.5
STA	942+22.62	TO	STA 965+69.52	482	241	1,032	9.0
STA	965+69.52	TO	STA 971+79.62	126	63	268	2.5
STA	971+79.62	TO	STA 988+86.68	351	176	752	6.5
STA	988+86.68	TO	STA 998+29.50	194	97	414	3.5
RURAL MAINLINE TOTALS				9,310	4,660	19,930	169.0
RURAL SHOULDERS				3,375	1,692	7,210	60.0
RURAL TOTALS				12,685	6,352	27,140	229.0
URBAN TOTALS				2,752	1,380	5,876	51.0
<b>PROJECT TOTALS</b>				<b>15,437</b>	<b>7,732</b>	<b>33,016</b>	<b>280.0</b>

\* MAINLINE QUANTITIES REFLECT TWO APPLICATIONS

FILE NAME =	USER NAME = \$USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>RESURFACING SCHEDULE (RURAL)</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\p\dot\weembf\0300388\78287-sht-plan.dgn		DRAWN -	REVISED -			SCALE:	SHEET 31 OF 49 SHEETS	STA.	TO STA.	332	(3,3-2,2)RS-3	WHITE	49 31
		CHECKED -	REVISED -										
		DATE -	REVISED -										