

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | |
|----------|---|-------|----------------|--------------------------|----------------------------------|
| | | | | 80% FEDERAL, 20% STATE | |
| | | | | ROADWAY 0004 URBAN | TRAFFIC SIGNALS 0021 URBAN |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 6 | 6 | |
| 40600990 | TEMPORARY RAMP | SQ YD | 735 | 735 | |
| 40603243 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 | TON | 461 | 461 | |
| 40603545 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 | TON | 396 | 396 | |
| 42000501 | PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) | SQ YD | 3791 | 3791 | |
| 42300300 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH | SQ YD | 845 | 845 | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 142 | 142 | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 8308 | 8308 | |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 415 | 415 | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 3360 | 3360 | |
| 44000162 | HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4" | SQ YD | 4256 | 4256 | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 1599 | 1599 | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 2272 | 2272 | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 6355 | 6355 | |

| | | | | | | | | | | | | | |
|--|--------------------|------------|-----------|---|------------------------------|-----------|----|--------|------------------------|--------------------|---------------------------|-----------------------|-------------------|
| FILE NAME * | USER NAME * #USER# | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | | F.A.U. RTE. 9481 | SECTION 12IN-11 | COUNTY FRANKLIN | TOTAL SHEETS 94 | SHEET NO. 5 |
| c:\pwwork\pvidot\puffarao\49270286\78288 | shl-plen.dgn | DRAWN - | REVISED - | | SCALE: | SHEET NO. | OF | SHEETS | STA. | TO STA. | CONTRACT NO. 78288 | | |
| | | CHECKED - | REVISED - | | | | | | | | ILLINOIS FED. AID PROJECT | | |
| | | DATE - | REVISED - | | | | | | | | | | |