	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 80% FEDERAL, 20% STATE	
					ROADWAY 0004 URBAN	TRAFFIC SIGNALS 0021 URBAN
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2000		2000
*	87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	545		545
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2261		2261
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,333		1,333
*	87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	4		4
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3		3
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60		60
*	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8		8
*	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2
*	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4		4
*	88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2		2
*	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4
*	88200100	TRAFFIC SIGNAL BACKPLATE	EACH	12		12
*	88600100	DETECTOR LOOP, TYPE I	FOOT	488		488
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8

*SPECIALTY ITEM

FILE NAME = c:\pw_work\peidot\pufferaa\d0293206\78288-sht-plan.dgn	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/22/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9481	12(N-1)	FRANKLIN	94	10
		CONTRACT NO. 78288		
		ILLINOIS FED. AID PROJECT		