

HSIP

F

SUMMARY OF QUANTITIES CONT.

COUNTY:	FRANKLIN	FRANKLIN
FUNDING:	90% FED 10% STATE	80% FED 20% STATE
LOCATION:	RURAL	RURAL
ROUTE:	FAS 2882 IL 37	FAS 2882 IL 37
	ROADWAY	STRUCTURE
	0004	0014

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1850		1850
50800515	BAR SPLICERS	EACH	38		38
52000110	PREFORMED JOINT STRIP SEAL	FOOT	102		102
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	139	139	
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	54	54	
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	42	42	
542A5497	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	47	47	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	773	773	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	121	121	
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	47	47	
542D1087	PIPE CULVERTS, CLASS D, TYPE 2 42"	FOOT	46	46	
54213453	END SECTIONS 18"	EACH	22	22	
54213459	END SECTIONS 24"	EACH	6	6	
54213471	END SECTIONS 36"	EACH	2	2	

FILE NAME *	USER NAME * puffera	DESIGNED -	REVISED -
c:\pwork\pwork\puffera\08305645\7037-plter-cv-seq-index.dgn		DRAWN -	REVISED -
Default	PLOT SCALE * 100.0000 * / in.	CHECKED -	REVISED -
	PLOT DATE * 3/22/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 4 OF 7 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2882	(11.12)R-1	FRANKLIN	196	8
CONTRACT NO. 78317			ILLINOIS FED. AID PROJECT	