

| CODE NUMBER | ITEM                                            | UNIT  | TOTAL QUANTITY | CONSTRUCTION CODE |              |
|-------------|-------------------------------------------------|-------|----------------|-------------------|--------------|
|             |                                                 |       |                | 100% STATE        |              |
|             |                                                 |       |                | GALLATIN COUNTY   | WHITE COUNTY |
|             |                                                 |       |                | ROADWAY           | ROADWAY      |
|             |                                                 |       |                | 0005              | 0005         |
|             |                                                 |       |                | RURAL             | RURAL        |
| 31100500    | SUBBASE GRANULAR MATERIAL, TYPE A 6"            | SO YD | 265            | 265               |              |
| 31100700    | SUBBASE GRANULAR MATERIAL, TYPE A 8"            | SO YD | 932            | 932               |              |
| 31102300    | SUBBASE GRANULAR MATERIAL, TYPE C 6"            | SO YD | 265            | 265               |              |
| 42000501    | PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) | SO YD | 855            | 855               |              |
| 42000541    | PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED) | SO YD | 265            | 265               |              |
| 42001200    | PAVEMENT FABRIC                                 | SO YD | 1120           | 1120              |              |
| 42001300    | PROTECTIVE COAT                                 | SO YD | 1370           | 1370              |              |
| 44000100    | PAVEMENT REMOVAL                                | SO YD | 1120           | 1120              |              |
| 44000500    | COMBINATION CURB AND GUTTER REMOVAL             | FOOT  | 457            | 457               |              |
| 44004250    | PAVED SHOULDER REMOVAL                          | SO YD | 18             | 18                |              |
| 44201037    | CLASS B PATCHES, TYPE IV, 15 INCH               | SO YD | 148            | 148               |              |
| 44201043    | CLASS B PATCHES, TYPE II, 16 INCH               | SO YD | 143            |                   | 143          |
| 44201047    | CLASS B PATCHES, TYPE III, 16 INCH              | SO YD | 34             |                   | 34           |
| 44201048    | CLASS B PATCHES, TYPE IV, 16 INCH               | SO YD | 100            |                   | 100          |

|                                      |                              |            |           |
|--------------------------------------|------------------------------|------------|-----------|
| FILE NAME =                          | USER NAME = #USER#           | DESIGNED - | REVISED - |
| c:\pwwork\pindot\kellyhd\0335268\783 | 6shl.rptn.dgn                | DRAWN -    | REVISED - |
|                                      | PLOT SCALE = 100.0000 "/ in. | CHECKED -  | REVISED - |
|                                      | PLOT DATE = 4/11/2013        | DATE -     | REVISED - |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

|                           |                    |                    |              |           |
|---------------------------|--------------------|--------------------|--------------|-----------|
| F.A. RTE.                 | SECTION            | COUNTY             | TOTAL SHEETS | SHEET NO. |
| VAR                       | D9 CM PATCH 2014-1 | *                  | 17           | 4         |
| * GALLATIN & WHITE        |                    | CONTRACT NO. 78356 |              |           |
| ILLINOIS FED. AID PROJECT |                    |                    |              |           |