

## LOCATION 1 PAVEMENT AND PATCHING SCHEDULE

LOCATION 1 STATION TO STATION	PAVEMENT REMOVAL	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SUB-BASE GRANULAR MATERIAL, TYPE C 6"	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	PCC PAVEMENT 10" (JOINTED)	PCC PAVEMENT 12" (JOINTED)	TIE BARS	COMBINATION CURB AND GUTTER REMOVAL	CONC. CURB & GUTTER, TYPE M-6.06	CONCRETE MEDIAN SURFACE, 4"	PROTECTIVE COAT	CLASS B PATCHES, TYPE IV, 15 INCH	SAW CUTS	DOWEL BARS	PAVEMENT FABRIC	REMARKS
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	EACH	FOOT	FOOT	SQ FT	SQ YD	SQ YD	FOOT	EACH	SQ YD	
<b>IL 142 NORTH LEG</b>																
315+66.84 SB TO 316+12.00 SB	106.6		106.6	106.6		106.6	18				106.6				106.6	PIPE UNDERDRAINS IN THIS AREA
316+12.00 SB TO 316+86.00 SB	158.3		158.3	158.3		158.3	30				158.3				158.3	PIPE UNDERDRAINS & OUTLETS
<b>IL 142 SOUTH LEG</b>																
321+03.00 SB TO 321+75.00 SB	128.0	140.0			128.0			72.0	72.0		138.9				128.0	
321+75.00 SB TO 322+50.00 SB	132.3	144.8			132.3			75.0	75.0		143.7				132.3	
322+50.00 SB TO 323+30.00 SB	135.6	148.9			135.6			80.0	80.0		147.7				135.6	
321+00.00 NB TO 321+75.00 NB	141.7	154.2			141.7			75.0	75.0	717.0	232.7				141.7	
321+75.00 NB TO 322+30.00 NB	106.9	116.1			106.9			55.0	55.0	440.0	164.2				106.9	
322+30.00 NB TO 322+81.00 NB	104.8	113.3			104.8			51.0	51.0	297.0	145.6				104.8	
322+81.00 NB TO 323+30.00 NB	106.2	114.3			106.2			49.0	49.0	166.0	132.1				106.2	
<b>IL 13 EAST LEG</b>																
<b>EASTBOUND</b>																
1601+61.00 TO 1601+92.00							31					55.1	110.0	28	55.1	FULL WIDTH PATCH
1602+91.00 TO 1603+23.00							32					56.9	112.0	28	56.9	FULL WIDTH PATCH
<b>WESTBOUND</b>																
1603+70.00 TO 1603+90.00							20					35.6	88.0	28	35.6	PATCH ADJACENT TO TURN LANE
<b>TOTALS</b>	<b>1120</b>	<b>932</b>	<b>265</b>	<b>265</b>	<b>855</b>	<b>265</b>	<b>131</b>	<b>457</b>	<b>457</b>	<b>1620</b>	<b>1370</b>	<b>148</b>	<b>310</b>	<b>84</b>	<b>1268</b>	