

F.A. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00027-00-SW	WINNEBAGO	15	2
SRTS-4009(056)		ILLINOIS	CONTRACT NO. 85584	

**McMAHON**  
ENGINEERS ARCHITECTS  
170 HUTCHINS ROAD, MACHESNEY PARK, IL 61115  
Tel: (708) 349-1000  
www.mcmahon.com

McMahon provides this drawing and data, regardless of form, as is. It is the responsibility of the client to verify the accuracy of the information. The client and/or recipient shall hold McMahon harmless for any errors or omissions in this drawing or data without prior written consent by McMahon.

NO.	DATE	REVISION
1	2/15/13	DOT CORRECTIONS
2	3/14/13	IDOT CORRECTIONS
3	4/08/13	IDOT CORRECTIONS

STATE OF ILLINOIS  
SAFE ROUTES TO SCHOOL SIDEWALK IMPROVEMENTS  
VILLAGE OF MACHESNEY PARK/CITY OF LOVES PARK

DESIGNED J.W.K.	DRAWN J.J.D.
SCALE NONE	
PROJECT NO. M0031-71-0102	
DATE JAN. 18, 2013	
SHEET NO. 2	

**SUMMARY OF QUANTITIES**  
**CONSTRUCTION TYPE CODE: 0021**

ITEM #	DESCRIPTION	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12
20100500	TREE REMOVAL, ACRES	ACRE	0.03
20200100	EARTH EXCAVATION	CU YD	638
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,420
25000100	SEEDING, CLASS 1	ACRE	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45
25100630	EROSION CONTROL BLANKET	SQ YD	2,420
28000510	INLET FILTERS	EACH	16
35101400	AGGREGATE BASE COURSE, TYPE B	TON	930
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	112
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	18,989
42400800	DETECTABLE WARNINGS	SQ FT	267
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	418
44000600	SIDEWALK REMOVAL	SQ FT	5,744
44213200	SAW CUTS	FOOT	47
67100100	MOBILIZATION	L SUM	1
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	173
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	93
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	143
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	142
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	235
* <b>XX008872</b>	<b>SOLAR POWERED PEDESTRIAN CROSSING SIGNAL SYSTEM COMPLETE</b>	EACH	2

\* SPECIALTY ITEMS