

SUMMARY OF QUANTITIES

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
						ROADWAY 0004	BRIDGE 0011
1		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	155	155	
2		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	178	178	
3		20200100	EARTH EXCAVATION	CU YD	737	737	
4		20300100	CHANNEL EXCAVATION	CU YD	455		455
5		20400800	FURNISHED EXCAVATION	CU YD	3176	3176	
6		20800150	TRENCH BACKFILL	CU YD	98	98	
7	SI	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4846	4846	
8	SI	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	91	91	
9	SI	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	91	91	
10	SI	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	91	91	
11	SI	25100115	MULCH, METHOD 2	ACRE	1	1	
12	SI	25200100	SODDING	SQ YD	4846	4846	
13	SI	25200200	SUPPLEMENTAL WATERING	UNIT	58	58	
14	SI	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400	400	
15	BDE, SI	28000305	TEMPORARY DITCH CHECKS	FOOT	96	96	
16	SI	28000400	PERIMETER EROSION BARRIER	FOOT	1186	1186	
17		28000500	INLET AND PIPE PROTECTION	EACH	4	4	
18		28000510	INLET FILTERS	EACH	4	4	
19		28100107	STONE RIPRAP, CLASS A4	SQ YD	115	115	
20		28100209	STONE RIPRAP, CLASS A5	TON	825		825
21		28200200	FILTER FABRIC	SQ YD	688	197	491
22		31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2460	2460	
23		35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	131	131	
24		40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	120	120	
25	SP	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	39	39	
26		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	932	932	
27		40600300	AGGREGATE (PRIME COAT)	TON	10	10	
28		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	714	714	
29		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	182	182	
30		40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	22	22	
31		42001300	PROTECTIVE COAT	SQ YD	1217	143	1074
32		42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	36	36	
33		44000100	PAVEMENT REMOVAL	SQ YD	1875	1875	
34		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	89	89	
35		48101200	AGGREGATE SHOULDERS, TYPE B	TON	139	139	
36		48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	347	347	
37	SP	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
38		50105220	PIPE CULVERT REMOVAL	FOOT	92	92	
39		50200300	COFFERDAM EXCAVATION	CU YD	2950		2950
40	GBSP	50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1		1

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
						ROADWAY 0004	BRIDGE 0011
41	GBSP	50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1		1
42	GBSP	50201123	COFFERDAM (TYPE 2) (LOCATION - 3)	EACH	1		1
43	GBSP	50201124	COFFERDAM (TYPE 2) (LOCATION - 4)	EACH	1		1
44		50300100	FLOOR DRAINS	EACH	28		28
45		50300225	CONCRETE STRUCTURES	CU YD	688.2		688.2
46		50300255	CONCRETE SUPERSTRUCTURE	CU YD	350.2		350.2
47		50300260	BRIDGE DECK GROOVING	SQ YD	762		762
48		50300265	SEAL COAT CONCRETE	CU YD	488		488
49		50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50		50500505	STUD SHEAR CONNECTORS	EACH	4050		4050
51	BDE	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	157300		157300
52		50800515	BAR SPLICERS	EACH	90		90
53		50900105	ALUMINUM RAILING, TYPE L	FOOT	211		211
54		50901050	STEEL RAILING, TYPE SM	FOOT	219		219
55		51201400	FURNISHING STEEL PILES HP10X42	FOOT	3654		3654
56		51201600	FURNISHING STEEL PILES HP12X53	FOOT	574		574
57		51202305	DRIVING PILES	FOOT	4228		4228
58		51203400	TEST PILE STEEL HP10X42	EACH	2		2
59		51203600	TEST PILE STEEL HP12X53	EACH	2		2
60		51204650	PILE SHOES	EACH	134		134
61		51500100	NAME PLATES	EACH	1		1
62		52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12
63		52000110	PREFORMED JOINT STRIP SEAL	FOOT	88		88
64		52100520	ANCHOR BOLTS, 1"	EACH	48		48
65		54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
66		54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
67		54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2	
68		54215553	METAL END SECTIONS 18"	EACH	2	2	
69		542A1093	PIPE CULVERTS, CLASS A, TYPE 2, 48"	FOOT	94	94	
70		542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	42	42	
71		550A0060	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	138	138	
72		550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	88	88	
73		58700300	CONCRETE SEALER	SQ FT	486		486
74		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	315		315
75		60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
76		60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2	2	
77		60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1	
78		60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
79		60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1	
80		60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1	

SP = SPECIAL PROVISIONS / SI = SPECIALITY ITEMS / BDE = BUREAU OF DESIGN AND ENVIRONMENT / GBSP = GUIDE BRIDGE SPECIAL PROVISION

FILE NAME = \\V2595\CADD SHEETS\2595-sh1-SC0-1.dgn
 USER NAME = amousta1
 PLOT SCALE = 1.000' / 1"
 PLOT DATE = 3/28/2013

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

DE KALB COUNTY
C.H. 26 (FIVE POINTS RD.)
OVER SOUTH BRANCH OF KISHWAUKEE RIVER

C.H. 26 (FIVE POINTS RD.)
SUMMARY OF QUANTITIES
 SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. N/A TO STA. N/A

RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 26	05-00044-01-BR	DE KALB	49	3
			CONTRACT NO. 87477	
ILLINOIS FED. AID PROJECT				