SUMMARY OF QUANTITIES			
ITEM NUMBER	ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	1497
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	449
25100630	EROSION CONTROL BLANKET	SQ YD	288
28000400	PERIMETER EROSION BARRIER	FOOT	572
28000500	INLET AND PIPE PROTECTION	EACH	2
28100211	STONE RIPRAP, CLASS A6	TON	1239
28200200	FILTER FABRIC	SQ YD	598
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	380
48101200	AGGREGATE SHOULDERS, TYPE B	TON	55
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	284
50300225	CONCRETE STRUCTURES	CU YD	39
50300300	PROTECTIVE COAT	SQ YD	321
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	1852
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4820
△ 50901050	STEEL RAILING, TYPE SM	FOOT	136
51201600	FURNISHING STEEL PILES HP12X53	FOOT	456
51202305	DRIVING PILES	FOOT	456
51203600	TEST PILE STEEL HP12X53	EACH	2
51204650	PILE SHOES	EACH	10
51500100	NAME PLATES	EACH	1
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	47
△ 66500105	WOVEN WIRE FENCE, 4'	FOOT	74
67100100	MOBILIZATION	L SUM	1
* X5420618	PIPE CULVERTS TO BE CLEANED 18"	FOOT	50
* X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	138
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
* XX006343	SEEDING (COMPLETE)	SQ YD	449
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
* Z0022800	FENCE REMOVAL	FOOT	137
* Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	170
* XX008811	MULCH	SQ YD	161

△ SPECIALTY ITEMS

EARTHWORK SUMMARY					
		20200100			
LOCATION		EARTH EXCAVATION CU YD	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
SOUTH OF BRIDGE					
176+07.00	176+55.92	50	37	0	37
NORTH OF BRIDGE					
177+26.08	178+57.00	164	123	18	105
CREEK AND BRIDGE					
176+55.92	177+26.08	1283	962	1	961
TOTAL		1497	1122	19	1103

SIGN REMOVAL SCHEDULE			
			SIGN REMOVAL
STATION	OFFSET	LT/RT	EACH
177+03.77	14.71	LT	1
TOTAL			1

INLET AND PIPE PROTECTION SCHEDULE			
			28000500
			INLET AND PIPE PROTECTION
STATION	OFFSET	LT/RT	EACH
177+52.68	39.79	LT	1
177+99.18	37.76	LT	1
TOTAL			2

© Copyright Hanson Professional Services Inc. 2013

HANSON Hanson Professional Services Inc.

FILE NAME = c:\pwise.work\do.not.delete\dms48234\D4	USER NAME = ander00846	DESIGNED - KNB	REVISED -
		DRAWN - SIP	REVISED -
	PLOT SCALE = 10.0000 ' / in.	CHECKED - CAL	REVISED -
Default	PLOT DATE = 03\27\2013	DATE - 3-26-13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FULTON CO HWY 26
SUMMARY OF QUANTITIES & SCHEDULES

SCALE: N/A | SHEET 3 OF 23 SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH26	11-00143-00-BR	FULTON	23	3

CONTRACT NO. 89597

ILLINOIS FED. AID PROJECT BROS 0057 (032)