

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	
				0004	NONE
20100110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER)	UNIT	200	200	
20100210	TREE REMOVAL ( OVER 15 UNITS DIAMETER)	UNIT	130	130	
20200100	EARTH EXCAVATION	CU YD	18273	18273	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	55	55	
20400800	FURNISHED EXCAVATION	CU YD	5473	5473	
20700110	POROUS GRANULAR EMBANKMENT	TON	55	55	
20800150	TRENCH BACKFILL	CU YD	4850	4850	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	500	500	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	3659	3659	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	6000	6000	
25000100	SEEDING, CLASS 1	ACRE	6.8	6.8	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	614	614	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	614	614	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	614	614	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	
				0004	NONE
25100115	MULCH, METHOD 2	ACRE	6.8	6.8	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2042	2042	
28000305	TEMPORARY DITCH CHECKS	FOOT	570	570	
28000400	PERIMETER EROSION BARRIER	FOOT	2000	2000	
28000500	INLET AND PIPE PROTECTION	EACH	172	172	
28100107	STONE RIPRAP, CLASS A4	SQ YD	101	101	
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	34	34	
28200200	FILTER FABRIC	SQ YD	150	150	
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	26800	26800	
30201500	LIME	TON	800	800	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	600	600	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	3700	3700	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	95	95	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	800	800	



DESIGNED - PJM	REVISED -
DRAWN - JJO/LAT	REVISED -
CHECKED - PJM	REVISED -
DATE - 01/18/13	REVISED -

**TOWN OF NORMAL  
NORTHTOWN ROAD FROM  
1200' WEST OF LINDEN STREET TO TOWANDA AVENUE**

**SUMMARY OF QUANTITIES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6375	00-00206-00-RP	McLEAN	129	3
CONTRACT NO. 91479				
[ILLINOIS] FED. AID PROJECT				