


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0004	NONE
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3900	3900	
40600300	AGGREGATE (PRIME COAT)	TON	15	15	
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5 FG, N50	TON	230	230	
40600990	TEMPORARY RAMP	SQ YD	40	40	
40603082	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N50	TON	710	710	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1450	1450	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	665	665	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	65	65	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	24500	24500	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1850	1850	
42400800	DETECTABLE WARNINGS	SQ FT	75	75	
44000100	PAVEMENT REMOVAL	SQ YD	800	800	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2685	2685	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1550	1550	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0004	NONE
44000600	SIDEWALK REMOVAL	SQ FT	395	395	
44201329	CLASS C PATCHES, TYPE II, 8 INCH	SQ YD	250	250	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	725	725	
50102400	CONCRETE REMOVAL	CU YD	10	10	
50104400	CONCRETE HEADWALL REMOVAL	EACH	5	5	
50105220	PIPE CULVERT REMOVAL	FOOT	108	108	
50800105	REINFORCEMENT BARS	POUND	12840	12840	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16	16	
54003000	CONCRETE BOX CULVERTS	CU YD	49.1	49.1	
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	28	28	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	3	3	

 <p>Farnsworth GROUP, INC. 2709 McGraw Drive Bloomington, Illinois 61704 309/893-8435, 309/863-1571 fax</p>	DESIGNED - PJM	REVISED -	TOWN OF NORMAL NORTHTOWN ROAD FROM 1200' WEST OF LINDEN STREET TO TOWANDA AVENUE	SUMMARY OF QUANTITIES		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - JJO/LAT	REVISED -				6375	00-00206-00-RP	McLEAN	129	4
	CHECKED - PJM	REVISED -				CONTRACT NO. 91479				
	DATE - 01/18/13	REVISED -				ILLINOIS FED. AID PROJECT				
				SCALE:	SHEET OF SHEETS STA.	TO STA.				