

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0004 NONE	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	12500	12500	
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	3	3	
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	3	3	
61139900	STORM SEWERS (SPECIAL), 6"	FOOT	500	500	
61140000	STORM SEWERS (SPECIAL), 8"	FOOT	100	100	
61140100	STORM SEWERS (SPECIAL), 10"	FOOT	100	100	
61140200	STORM SEWERS (SPECIAL), 12"	FOOT	100	100	
67100100	MOBILIZATION	L SUM	1	1	
67201000	SEALING ABANDONED WATER WELLS	EACH	1	1	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	100	100	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3200	3200	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	60	60	
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	50	50	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	5700	5700	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0004 NONE	
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	165	165	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	830	830	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2400	2400	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	21200	21200	
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	2025	2025	
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	1200	1200	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	160	160	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	375	375	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Δ Z0076600	TRAINEES	HOURL	500	500	
Δ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	500	500	
LR420029	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	25200	25200	
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2	2	
X0324058	OUTLET SPECIAL	EACH	4	4	
* X0325402	MODIFY SPRINKLER SYSTEM	L SUM	1	1	

* SPECIALTY ITEMS Δ 0042



DESIGNED - PJM	REVISED -
DRAWN - JJO/LAT	REVISED -
CHECKED - PJM	REVISED -
DATE - 01/18/13	REVISED -

TOWN OF NORMAL
NORTHTOWN ROAD FROM
1200' WEST OF LINDEN STREET TO TOWANDA AVENUE

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS
			STA. TO STA.

F.A.U. RTE. 6375	SECTION 00-00206-00-RP	COUNTY McLEAN	TOTAL SHEETS 129	SHEET NO. 6
CONTRACT NO. 91479				
ILLINOIS FED. AID PROJECT				