

78001100 - PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS			
STATION	TO	STATION	SQ. FT.
NORTHTOWN RD. (LARGE ARROWS - WHITE)			
36+34.40	RT	- 37+39.40	47
39+24.00	LT	- 40+39.00	47
41+93.00	LT/R	- 90+14.00	593
90+91.00	RT	- 92+57.40	47
SUBTOTAL			733
LINDEN ST.			
8+17.40	RT	- 9+57.40	47
10+71.50	LT	- 12+11.50	47
SUBTOTAL			94
CONTINGENCY			3
TOTAL			830

78001110 - PAINT PAVEMENT MARKING - LINE 4"			
STATION	TO	STATION	FOOT
LINDEN ST. (WHITE)			
3+03.40	LT	- 8+23.10	520
3+03.40	RT	- 9+14.90	612
10+85	LT	- 17+27.39	642
11+51.50	RT	- 17+27.39	576
SUBTOTAL			2,350
CONTINGENCY			50
TOTAL			2,400

78001130 - PAINT PAVEMENT MARKING - LINE 6"			
STATION	TO	STATION	FOOT
NORTHTOWN RD. (6" YELLOW)			
30+73.42	LT	- 37+91.40	1,154
37+91.40	LT	(NOSE)	10
30+73.42	RT	- 37+91.40	1,154
39+22.00	RT	- 41+93.15	543
39+22.00	RT	(NOSE)	10
39+22.00	RT	- 41+93.00	542
41+93.00	LT/R	- 90+14.00	9,642
90+14.00	LT	- 92+46.00	464
41+93.00	LT/R	- 90+14.00	2,420
SUBTOTAL			15,939
WHITE SKIP DASHES			
90+91.00	RT	- 92+57.00	40
SUBTOTAL			40
LINDEN ST. (6" YELLOW)			
3+03.40	LT	- 9+59.40	1,282
3+03.40	RT	- 9+59.40	1,272
9+59.40	LT	(NOSE)	6
10+69.50	RT	- 17+27.40	1,304
10+69.50	RT	- 17+27.40	1,312
10+69.50	RT	(NOSE)	6
SUBTOTAL			5,190
SUBTOTAL			21,169
CONTINGENCY			31
TOTAL			21,200

78001140 - PAINT PAVEMENT MARKING - LINE 8"			
STATION	TO	STATION	FOOT
NORTHTOWN RD. (WHITE)			
TRANSITION TO 2-12' LANES:			
86+18.00	RT	- 91+06.00	488
STORAGE LANES:			
36+34.40	RT	- 37+89.40	155
39+24.00	LT	- 40+39.00	115
90+91.00	RT	- 92+59.00	168
Linden St.:			
8+17.40	RT	- 9+57.40	140
10+71.50	LT	- 12+11.50	140
SUBTOTAL			1,206
YELLOW: (ISLANDS)			
NORTHTOWN RD.:			
37+09.50	RT		100
38+24.00	LT		115
38+52.00	RT		57
38+67.00	LT		89
SUBTOTAL			361
WHITE (CROSSWALKS)			
NORTHTOWN RD.:			
39+08.00	LT/RT		109
LINDEN ST.:			
10+54.50	LT/RT		139
SUBTOTAL			248
WHITE (2' SKIP DASHES)			
NORTHTOWN RD. @ LINDEN			
34+78.42	RT	- 36+34.40	36
40+39.00	LT	- 41+93.00	36
NORTHTOWN RD. @ TOWANDA			
89+06.00	RT	- 90+93.00	44
SUBTOTAL			116
LINDEN ST.			
6+64.00	RT	- 8+19.00	36
12+11.00	LT	- 13+67.00	36
SUBTOTAL			72
SUBTOTAL			2,003
CONTINGENCY			22
TOTAL			2,025



DESIGNED - PJM	REVISED -
DRAWN - JJO/LAT	REVISED -
CHECKED - PJM	REVISED -
DATE - 01/18/13	REVISED -

**TOWN OF NORMAL
NORTHTOWN ROAD FROM
1200' WEST OF LINDEN STREET TO TOWANDA AVENUE**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6375	00-00206-00-RP	MCLEAN	129	16
CONTRACT NO. 91479				
ILLINOIS FED. AID PROJECT				