

78001150 - PAINT PAVEMENT MARKING - LINE 12"				
STATION	TO	STATION	FOOT	
YELLOW 45° ANGLE				
NORTHTOWN RD.:				
30+73.42	LT/R	- 36+34.50	LT/RT	308
40+39.00	LT/R	- 41+93.50	LT/RT	105
LINDEN ST.:				
3+03.40	LT/RT	- 8+19.40	LT/RT	223
12+11.40	LT/R	- 17+27.40	LT/RT	212
SUBTOTAL			848	
WHITE (CROSSWALKS)				
NORTHTOWN RD.				
39+11.50	LT/RT		108	
LINDEN ST.				
10+59.50	LT/RT		228	
SUBTOTAL			336	
CONTINGENCY			16	
TOTAL			1,200	

78001180 - PAINT PAVEMENT MARKING - LINE 24"			
STATION	TO	STATION	FOOT
WHITE			
NORTHTOWN RD.:			
37+77.00	RT		18
37+89.40	LT/RT		24
39+22.00	LT/RT		27
92+59.00	RT		26
SUBTOTAL			95
LINDEN ST.:			
9+57.40	LT/RT		35
10+69.50	LT/RT		26
SUBTOTAL			61
SUBTOTAL			156
CONTINGENCY			4
TOTAL			160

78100100 - RAISED REFLECTIVE PAVEMENT MARKER				
STATION	TO	STATION	EACH	
30+73.42	LT	- 37+91.40	LT	14
30+73.42	RT	- 37+91.40	LT	14
36+34.40	RT	- 37+89.40	RT	4
39+22.00	RT	- 41+93.15	RT	7
39+22.00	RT	- 41+93.15	LT	7
39+24.00	LT	- 40+39.00	LT	3
41+93.15	LT/RT	- 90+14.00	LT/RT	242
90+14.00	LT	- 92+46.00	LT	6
90+91.00	LT	- 92+46.00	LT	4
90+91.00	RT	- 92+56.00	RT	2
SUBTOTAL			303	
LINDEN ST.:				
3+03.40	LT	- 9+59.40	LT	16
3+03.40	RT	- 9+59.40	LT	16
8+17.40	RT	- 9+57.40	RT	4
10+69.50	RT	- 17+27.40	LT	16
10+69.50	RT	- 17+27.40	RT	16
10+71.50	RT	- 12+11.50	LT	4
SUBTOTAL			72	
TOTAL			375	

Z0013798 - CONSTRUCTION LAYOUT			
STATION	TO	STATION	LUMP SUM
PROJECT LIMIT			
TOTAL			1

Z0076600 - TRAINEES			
STATION	TO	STATION	HOURS
PROJECT			
TOTAL			1,000

LR420029 - PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)				
STATION	TO	STATION	SQ. YD.	
31+74.32	LT/RT	- 34+78.42	LT/RT	304
34+78.42	LT/RT	- 36+65.00	LT/RT	311
36+65.00	LT/RT	- 38+17.00	LT/RT	709
NW QUAD @ LINDEN				
SW QUAD @ LINDEN			201	
NE QUAD @ LINDEN			181	
SE QUAD @ LINDEN			124	
38+59.50	LT/RT	- 41+93.15	LT/RT	1,552
41+93.15	LT/RT	- 42+85.15	LT/RT	409
42+85.15	LT/RT	- 86+18.00	LT/RT	18,294
86+18.00	LT/RT	- 91+33.87	LT/RT	2,837
SUBTOTAL			25,114	
CONTINGENCY			86	
TOTAL			25,200	

X0322936 - REMOVE EXISTING FLARED END SECTION			
STATION	TO	STATION	EACH
62+45.00	RT		1
70+24.00	RT		1
TOTAL			2

X0324058 - OUTLET SPECIAL			
STATION	TO	STATION	EACH
8+24.00	LT		1
9+21.00	RT		1
10+82.00	LT		1
11+46.00	RT		1
TOTAL			4

X0325402 - MODIFY SPRINKLER SYSTEM				
STATION	TO	STATION	L SUM	
55+66	RT	- 57+20	RT	1
TOTAL			1	

X0326899 - SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)			
STATION	TO	STATION	EACH
6+57.4	RT		1
9+48	RT		1
10+64	LT		1
13+69.5	LT		1
37+60	RT		1
39+12	LT		1
TOTAL			6

X4240420 - PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL			
STATION	TO	STATION	FOOT
81+89.97	-	81+94.97	25
82+10.39	-	82+15.39	25
TOTAL			50

X4400500 - COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)				
STATION	TO	STATION	FOOT	
NORTHTOWN RD.:				
91+33.87	LT		6	
91+33.87	RT		6	
SUBTOTAL			12	
LINDEN ST.:				
9+35	LT		6	
10+35	LT	- 10+85	LT	50
SUBTOTAL			56	
CONTINGENCY			2	
TOTAL			70	

X4401198 - HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH				
STATION	TO	STATION	FOOT	
LINDEN ST.:				
8+00	LT	- 13+00	LT	667
9+00	RT	- 10+25	RT	167
CONTINGENCY			16	
TOTAL			850	

X4402400 - CURB REMOVAL (SPECIAL)			
STATION	TO	STATION	FOOT
92+17.6	LT	- 92+41.2	26
TOTAL			26

X5504200 - DUCTILE IRON, STORM SEWER, 12 INCH				
STATION	TO	STATION	FOOT	
34+50.00	RT		2	
35+50.00	RT		2	
36+75.00	RT		2	
37+75.00	RT	- 37+77.00	RT	10
38+80.00	RT	- 39+00.00	RT	20
39+00.00	RT	- 39+14.00	RT	14
40+00.00	RT		8	
41+09.00	RT		10	
42+33.00	RT		12	
43+00.00	RT		12	
45+25.00	RT		10	
46+16.00	RT		10	
46+75.00	RT		8	
47+50.00	RT		6	
47+90.00	RT		6	
47+90.00	RT	- 48+00.00	RT	8
49+00.00	RT		4	
50+25.00	RT		2	
62+45.00	RT		14	
70+24.00	RT		30	
90+00.00	RT		4	
91+00.00	RT		6	
91+00.00	RT	- 91+25.00	RT	22
SUBTOTAL			222	
CONTINGENCY			8	
TOTAL			230	

X6025602 - MANHOLES TO BE ADJUSTED WITH FRAME AND GRATE (SPECIAL)		
STATION	EACH	
34+50.00	RT	1
TOTAL		1

X7010216 - TRAFFIC CONTROL AND PROTECTION (SPECIAL)			
STATION	TO	STATION	LUMP SUM
PROJECT LIMIT			
TOTAL			1

**Farnsworth**  
GROUP, INC.  
2709 McGraw Drive  
Bloomington, Illinois 61704  
309/865-8435, 309/865-1271 fax

DESIGNED - PJM  
DRAWN - JJO/LAT  
CHECKED - PJM  
DATE - 01/18/13

REVISED -  
REVISED -  
REVISED -  
REVISED -

**TOWN OF NORMAL**  
**NORTHTOWN ROAD FROM**  
**1200' WEST OF LINDEN STREET TO TOWANDA AVENUE**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6375	00-00206-00-RP	McLEAN	129	17

CONTRACT NO. 91479  
ILLINOIS FED. AID PROJECT