

SUMMARY OF QUANTITIES		CONSTRUCTION CODE		0004	0028
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% LOCAL QUANTITY	80% I/TEP 20% LOCAL QUANTITY
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	72		72
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18		18
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10		10
* 20600110	GRANULAR EMBANKMENT, SPECIAL	TON	20		20
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	30		30
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	2745		2745
* 25000100	SEEDING, CLASS 1	ACRE	0.6		0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54		54
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	54		54
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54		54
* 25100115	MULCH, METHOD 2	ACRE	0.6		0.6
* 25200100	SODDING	SQ YD	180		180
* 25200200	SUPPLEMENTAL WATERING	UNIT	46		46
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100		100
28000400	PERIMETER EROSION BARRIER	FOOT	1400		1400
28000500	INLET AND PIPE PROTECTION	EACH	2		2
28000510	INLET FILTERS	EACH	74	74	
* 31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	445		445
* 35101400	AGGREGATE BASE COURSE, TYPE B	TON	251		251
* 35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1744	458	1286
* 35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	67		67
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	130		130
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4131	2921	1210
40600300	AGGREGATE (PRIME COAT)	TON	100	70	30
* 40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	6	3
* 40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
* 40600909	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	311	311	
40600990	TEMPORARY RAMP	SQ YD	520	520	
* 40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	4497	3136	1361
* 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	8	8	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	327		327
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	115		115
* 42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	27804	3510	24294
* 42400800	DETECTABLE WARNINGS	SQ FT	305		305
* 44000100	PAVEMENT REMOVAL	SQ YD	68		68
* 44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	38869	26844	12025

* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES		CONSTRUCTION CODE		0004	0028
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% LOCAL QUANTITY	80% I/TEP 20% LOCAL QUANTITY
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	478		478
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1222	107	1115
44000600	SIDEWALK REMOVAL	SQ FT	8112		8112
* 44200990	CLASS B PATCHES, TYPE I, 12 INCH	SQ YD	100	100	
* 44200994	CLASS B PATCHES, TYPE II, 12 INCH	SQ YD	100	100	
* 44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	100	100	
* 44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	100	100	
* 44400100	FIBERGLASS FABRIC REPAIR SYSTEM	SQ YD	1484	1484	
* 54248510	CONCRETE COLLAR	CU YD	3		3
* 550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	5		5
* 550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	6		6
* 550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	17		17
* 55100300	STORM SEWER REMOVAL 8"	FOOT	8		8
* 55100400	STORM SEWER REMOVAL 10"	FOOT	7		7
* 55101200	STORM SEWER REMOVAL 24"	FOOT	4		4
* 56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	2		2
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	8		8
* 59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	5		5
* 60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4		4
* 60255500	MANHOLES TO BE ADJUSTED	EACH	6	1	5
* 60260100	INLETS TO BE ADJUSTED	EACH	1		1
* 60266600	VALVE BOXES TO BE ADJUSTED	EACH	6		6
* 60500060	REMOVING INLETS	EACH	4		4
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	245		245
* 60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	201		201
* 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	806		806
* 66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1	
67100100	MOBILIZATION	L SUM	1	0.50	0.50
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1440	1440	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1230	1230	
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	200	200	
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1290	1290	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	152		152
* 72900200	METAL POST - TYPE B	FOOT	402		402
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	630	630	
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21181	21181	

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

FILE NAME = p:\00070062_Urbana - Main Street I/TEP\Plans\Sheets\04-summary.dgn
 PLOT DATE = 6/8/2013 11:51:33 AM

DESIGNED - J.A.J.	REVISED -
DRAWN - J.L.B.	REVISED -
CHECKED - S.M.W.	REVISED -
DATE - 03/2013	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE : NONE SHEET NO. 4 OF 75 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7124	09-00483-01-R5	CHAMPAIGN	75	4
MAIN STREET		CONTRACT NO. 91480		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		