

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				0005 ROADWAY	0011 STRUCTURE	0042 TRAINEES
• 50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	4032		4032	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	109730		109730	
50800515	BAR SPLICERS	EACH	84		84	
50800530	MECHANICAL SPLICERS	EACH	248		248	
Δ 50901730	BRIDGE FENCE RAILING	FOOT	370		370	
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	897		897	
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	574		574	
51202305	DRIVING PILES	FOOT	1471		1471	
51203200	TEST PILE METAL SHELLS	EACH	4		4	
51500100	NAME PLATES	EACH	1		1	
• 52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12	
52100520	ANCHOR BOLTS, 1"	EACH	24		24	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24		24	
• 542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	86	86		
• 542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	46	46		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	154	154		
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	60		60	
60220005	MANHOLES, TYPE A, 4' -DIAMETER, WITH MEDIAN INLET (604101)	EACH	1	1		
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
Δ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125		

• SPECIAL PROVISION

Δ SPECIALTY ITEMS

FILE NAME *	USER NAME = bgj	DESIGNED - SEB	REVISED - SEB - 1/16/13	ADAMS COUNTY HIGHWAY DEPARTMENT	FAS 1598 (CH 27 /CANNONBALL ROAD) SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Q:\11\files\110015\05 Plans\Current\SH.Su.org.11015.dgn		DRAWN - EBB	REVISED -			1598	11-00218-00-BR	ADAMS	53	5	
PLOT SCALE * 20.0000 1/16" in.		CHECKED - SRW	REVISED -			CONTRACT NO. 11-00218-00-BR					
PLOT DATE = 1/30/2013		DATE - 6-21-12	REVISED -			SCALE:	SHEET NO. 3 OF 4 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	