


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004 URBAN	0011 084-6019
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	105	105	
20100500	TREE REMOVAL, ACRES	ACRE	0.7	0.7	
20200100	EARTH EXCAVATION	CU YD	1254	1254	
20300100	CHANNEL EXCAVATION	CU YD	1820	1820	
• 20800150	TRENCH BACKFILL	CU YD	694	694	
Δ 25000100	SEEDING, CLASS 1	ACRE	0.5	0.5	
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45	
Δ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45	
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45	
Δ 25100115	MULCH, METHOD 2	ACRE	0.5	0.5	
• 25100630	EROSION CONTROL BLANKET	SQ YD	275	275	
Δ 25200100	SODDING	SQ YD	941	941	
Δ 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60	60	
28000305	TEMPORARY DITCH CHECKS	FOOT	30	30	

• SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

FILE NAME * \$FILEL\$	USER NAME * \$USER\$	DESIGNED -	REVISED -	 <b>Allen Henderson &amp; Associates, Inc.</b> Civil and Structural Engineers Springfield, IL. 62703 Phone: (217)544-8033 IL Design Firm No. 184-001907	<b>SUMMARY OF QUANTITIES</b>			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE * \$SCALE\$	DRAWN -	REVISED -		SCALE: NONE	SHEET NO. 1 OF 9 SHEETS	STA.	TO STA.	8006	10-00470-00-BR	SANGAMON	90	3
	PLOT DATE * \$DATE\$	CHECKED -	REVISED -					CONTRACT NO. 93600					
		DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					