


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004 URBAN	0011 084-6019
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SO FT	9307		9307
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	127520		127520
50800515	BAR SPLICERS	EACH	439		439
Δ 50901720	BICYCLE RAILING	FOOT	369		369
Δ 50901750	PARAPET RAILING	FOOT	344		344
51201610	FURNISHING STEEL PILES HP12X63	FOOT	3726		3726
51202305	DRIVING PILES	FOOT	3726		3726
51203610	TEST PILE STEEL HP12X63	EACH	4		4
51500100	NAME PLATES	EACH	1		1
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	24	24	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	34	34	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	40	40	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	17	17	

• SEE SPECIAL PROVISIONS
Δ SPECIALTY ITEMS

FILE NAME = \$FILEL\$	USER NAME = \$USER\$	DESIGNED - DRAWN -	REVISED - REVISED -	 Allen Henderson & Associates, Inc. Civil and Structural Engineers Springfield, IL. 62703 Phone: (217)544-8033 IL Design Firm No. 184-001907	SUMMARY OF QUANTITIES			F.A.J. RTE. 8006	SECTION 10-00470-00-BR	COUNTY SANGAMON	TOTAL SHEETS 90	SHEET NO. 6
PLOT SCALE = \$SCALE\$	CHECKED -	REVISED -	REVISED -		SCALE: NONE	SHEET NO. 4 OF 9 SHEETS	STA.	TO STA.	CONTRACT NO. 93600			
PLOT DATE = \$DATE\$	DATE -	REVISED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							