


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004 URBAN	0011 084-6019
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	74	74	
55100500	STORM SEWER REMOVAL 12"	FOOT	56	56	
55100700	STORM SEWER REMOVAL 15"	FOOT	26	26	
55101800	STORM SEWER REMOVAL 42"	FOOT	121	121	
60218500	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
60219500	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 15 FRAME AND LID	EACH	3	3	
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
60223810	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
60224447	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1	
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID	EACH	1	1	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
60255900	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1	1	

• SEE SPECIAL PROVISIONS

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - DRAWN	REVISED - REVISED	 Allen Henderson & Associates, Inc. Civil and Structural Engineers Springfield, IL. 62703 Phone: (217)544-8033 IL Design Firm No. 184-001907	SUMMARY OF QUANTITIES		F.A.U. RTE. 8006	SECTION 10-00470-00-BR	COUNTY SANGAMON	TOTAL SHEETS 90	SHEET NO. 7
PLOT SCALE = #SCALE#	CHECKED -	REVISED -	REVISED -		SCALE: NONE	SHEET NO. 5 OF 9 SHEETS	STA.	TO STA.	CONTRACT NO. 93600		
PLOT DATE = #DATE#	DATE	REVISED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						