

EARTHWORK				
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 205+00 TO STA. 208+00	343	257	272	-15
STA. 208+50 TO SA. 213+80	911	683	368	315
TOTAL	1254	940	640	300

SEEDING					
LOCATION	SEEDING CLASS 1	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2
	ACRE	POUND	POUND	POUND	ACRE
STA. 205+00 TO STA. 207+28 LT	0.08	7	7	7	0.08
STA. 208+27 TO STA. 208+87 LT	0.02	2	2	2	0.02
STA. 207+00 TO STA. 209+72 RT	0.2	18	18	18	0.2
STA. 209+32 TO STA. 213+63 RT	0.2	18	18	18	0.2
TOTAL	0.5	45	45	45	0.5

TREE REMOVAL		
LOCATION	TREE REMOVAL, (6 TO 15) UNITS	TREE REMOVAL, ACRES
	STA. 205+93, 39' LT.	15
STA. 206+13, 39' LT.	15	
STA. 206+25, TO STA. 208+35 LT.		0.3
STA. 206+58, 38' LT.	15	
STA. 206+78, 38' LT.	15	
STA. 206+97, 38' LT.	15	
STA. 207+17, 38' LT.	15	
STA. 207+58, 38' LT.	15	
STA. 208+25 TO STA. 210+65 RT.		0.4
TOTAL	105	0.7

PULVERIZATION	
LOCATION	QUANTITY
	SQ YD
STA. 206+50 TO STA. 207+50	620
STA. 209+00 TO STA. 210+10	606
TOTAL	1226

PAVEMENT REMOVAL	
LOCATION	QUANTITY
	SQ YD
STA. 205+00 TO STA. 206+50	915
STA. 207+50 TO STA. 208+00	255
STA. 208+72 TO STA. 209+00	140
STA. 210+10 TO STA. 213+80	2140
TOTAL	3450

SODDING	
LOCATION	QUANTITY
	SQ YD
STA. 205+00 TO STA. 207+00 RT	229
STA. 208+85 TO STA. 213+20 RT	675
STA. 214+19 TO STA. 214+44 LT. (ST II TEMP ACCESS)	37
TOTAL	941

HMA SURFACE REMOVAL - BUTT JOINT	
LOCATION	QUANTITY
	SQ. YD.
STA. 213+81 RT - CE	74
TOTAL	74

TREE (CLEVELAND GALLERY PEAR)	
LOCATION	QUANTITY
	EACH
STA. 206+03, 37' LT.	1
STA. 206+23, 37' LT.	1
STA. 206+43, 37' LT.	1
STA. 206+63, 37' LT.	1
TOTAL	4

TRENCH BACKFILL	
LOCATION	QUANTITY
	CU YD
STA. 207+70 TO STA. 207+90, 19' RT. (SAN SEWER)	295
STA. 208+95 TO STA. 209+20, 19' RT. (SAN SEWER)	368
STA. 208+83, 24' RT TO STA. 210+21, 30' RT	14.5
STA. 210+16.5, 43' RT TO STA. 210+23, 34' RT	11.5
STA. 210+76, 49' LT TO STA. 210+76, 56' LT	1.5
STA. 210+78.5, 58' LT TO STA. 211+05, 58' LT	3.5
TOTAL	694

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	
LOCATION	QUANTITY
	SQ FT
STA. 205+00 TO STA. 207+06 LT	1010
STA. 208+85 TO STA. 209+67, 8 LT	390
STA. 209+87.8 TO STA. 210+72 LT	400
STA. 211+14 TO STA. 213+13.5 LT	970
STA. 213+59 TO STA. 213+80 LT	90
STA. 205+75 TO STA. 207+74 RT	980
STA. 209+54 TO STA. 211+90 RT	1160
STA. 212+27 TO STA. 212+51 RT	100
STA. 212+90 TO STA. 213+59 RT	330
STA. 214+19 TO STA. 214+44 LT. (ST II TEMP ACCESS)	97
TOTAL	5527

CHANNEL EXCAVATION	
LOCATION	QUANTITY
	CU YD
STA. 206+50 LT TO STA. 209+75 RT	1820
TOTAL	1820

SUBBASE GRANULAR MATERIAL, TYPE A	
LOCATION	QUANTITY
	TON
STA. 205+00 TO STA. 208+00	1965
STA. 208+50 TO STA. 213+80	3150
STA. 209+78 LT - PE	30
TOTAL	5145

CURB REMOVAL AND REPLACEMENT	
LOCATION	QUANTITY
	FOOT
STA. 214+19.5 TO STA. 214+43.8', 48' LT (ST II TEMP ACCESS)25	25
TOTAL	25