

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	1367	1367		
50105220	PIPE CULVERT REMOVAL	FOOT	31	31		
50300225	CONCRETE STRUCTURES	CU YD	44	44		
50800105	REINFORCEMENT BARS	POUND	80	80		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,210	3,210		
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2		
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16	16		
54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	27	27		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1		
54248510	CONCRETE COLLAR	CU YD	1.6	1.6		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	40	40		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	11	11		
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	4925	4925		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
60107700	PIPE UNDERDRAINS 6"	FOOT	6590	6590		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	220	220		
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	1	1		
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	75	75		
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2	2		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	562	562		
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	16	16		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1		
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		

*SPECIALTY ITEM