



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2013

SUBJECT: General Dacey Trail  
Project TE-00D7(063)  
Section 11-00052-00-BT (Shelbyville)  
Shelby County  
Contract No. 95707  
Item 180  
June 14, 2013 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

1. **Pages 2 and 3 of the Schedule of Prices.**
2. **Index of Special Provisions.**
3. **Page 13 of the Special Provisions.**
4. **Sheet 2 of Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

GENERAL  
 11-00052-00-BT (SHELBYVILLE)  
 SHELBY

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - 95707

ECMS002 DTGECM03 ECMR003 PAGE 2  
 RUN DATE - 06/04/13  
 RUN TIME - 183106

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
42400200	PC CONC SIDEWALK 5	SQ FT	5,340.000 X	=		=	
42400800	DETECTABLE WARNINGS	SQ FT	60.000 X	=		=	
44000100	PAVEMENT REM	SQ YD	335.000 X	=		=	
44000200	DRIVE PAVEMENT REM	SQ YD	68.000 X	=		=	
44000500	COMB CURB GUTTER REM	FOOT	523.000 X	=		=	
44000600	SIDEWALK REM	SQ FT	3,365.000 X	=		=	
44003100	MEDIAN REMOVAL	SQ FT	160.000 X	=		=	
550A0360	STORM SEW CL A 2 15	FOOT	6.000 X	=		=	
56500300	DOM MET VLTS ADJ	EACH	1.000 X	=		=	
60218500	MAN TA 4 DIA T3F&G	EACH	1.000 X	=		=	
60255800	MAN ADJ NEW T1F CL	EACH	2.000 X	=		=	
60605000	COMB CC&G TB6.24	FOOT	612.000 X	=		=	
60618300	CONC MEDIAN SURF 4	SQ FT	116.000 X	=		=	
66900200	NON SPL WASTE DISPOS	CU YD	25.000 X	=		=	
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000 X	=		=	

Revised 6/5/13

GENERAL  
11-00052-00-BT (SHELBYVILLE)  
SHELBY

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES  
CONTRACT NUMBER - 95707

ECMS002 DTGECM03 ECMR003 PAGE 3  
RUN DATE - 06/04/13  
RUN TIME - 183106

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
66900530	SOIL DISPOSAL ANALY	EACH	1.000 X				
67100100	MOBILIZATION	L SUM	1.000 X				
70102625	TR CONT & PROT 701606	L SUM	1.000 X				
70102640	TR CONT & PROT 701801	L SUM	1.000 X				
70103815	TR CONT SURVEILLANCE	CAL DA	8.000 X				
78005100	EPOXY PVT MK LTR-SYM	SQ FT	183.600 X				
78005110	EPOXY PVT MK LINE 4	FOOT	513.000 X				
78005150	EPOXY PVT MK LINE 12	FOOT	93.000 X				
78005180	EPOXY PVT MK LINE 24	FOOT	93.000 X				
78300100	PAVT MARKING REMOVAL	SQ FT	525.000 X				

TOTAL \$

- NOTE:
1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
  2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
  3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
  4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

Revised 6/5/13

INDEX OF SPECIAL PROVISIONS

INTRODUCTORY PARAGRAPH.....	1
DESCRIPTION OF WORK .....	1
LOCATION OF WORK .....	1
TRAFFIC CONTROL PLAN .....	1-3
REMOVAL OF BROKEN CONCRETE .....	3
OVERHAUL.....	3
BORROW AREAS, USE AREAS, AND/OR WASTE AREAS.....	3
FURNISHED EXCAVATION.....	4
MECHANICAL SWEEPERS .....	4
EPOXY PAVEMENT MARKINGS.....	4
REMOVAL OF UNCLASSIFIED MATERIAL.....	5
COURSE AGGREGATE GRADATION CA-06.....	5
EXISTING PIPES .....	5
MANHOLES .....	6
<del>JULINE</del> .....	6
PRECAUTIONS FOR UTILITIES .....	6
UTILITIES.....	7-8
MANHOLES TO BE ADJUSTED .....	9
UNIT PAVERS .....	10 - 11
INLETS TO BE REMOVED, SPECIAL.....	12
INSTALL SIGN .....	12 - 13
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	13

**STATE OF ILLINOIS**  
**SHELBY COUNTY**  
**SPECIAL PROVISIONS**

**CONTINUE INSTALL SIGN:**

The work shall be done as specified in these Special Provisions and as shown on the plans. The work will be paid for at the unit price EACH for INSTALL SIGN. This shall include all labor, equipment and materials required for completing the work and no additional compensation shall be allowed to the contractor.

**REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES**

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities.

All contaminated materials shall be managed as either "uncontaminated soil" or non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances. The Environmental Firm shall continuously monitor all soil excavation for worker protection and soil contamination. Phase I Preliminary Engineering information is available through the District's Environmental Studies Unit. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

The Contractor shall manage any excavated soils and sediment within the following areas:

- Station 7+25 to Station 7+80 0 to 30 feet LT (Shelby County Visitor Center, PESA Site 2427-7, 315 East Main Street). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: Arsenic.