

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	QUANTITY	UNIT
20200100	EARTH EXCAVATION	32	CU YD
20400800	FURNISHED EXCAVATION	37	CU YD
20800150	TRENCH BACKFILL	3	CU YD
25000400	NITROGEN FERTILIZER NUTRIENT	2	POUND
25000500	PHOSPHORUS FERTILIZER NUTRIENT	2	POUND
25000600	POTASSIUM FERTILIZER NUTRIENT	2	POUND
25200100	SODDING	66	SQ YD
25200200	SUPPLEMENTAL WATERING	6	UNIT
28000400	PERIMETER EROSION BARRIER	233	FOOT
28000500	INLET AND PIPE PROTECTION	1	EACH
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	45	SQ YD
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	5340	SQ FT
42400800	DETECTABLE WARNINGS	60	SQ FT
44000100	PAVEMENT REMOVAL	335	SQ YD
44000200	DRIVEWAY PAVEMENT REMOVAL	68	SQ YD
44000500	COMBINATION CURB AND GUTTER REMOVAL	523	FOOT
44000600	SIDEWALK REMOVAL	3365	SQ FT
44003100	MEDIAN REMOVAL	160	SQ FT
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	6	FOOT
Δ 56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	1	EACH
60218500	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 3 FRAME AND GRATE	1	EACH
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	2	EACH
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	612	FOOT
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	116	SQ FT
67100100	MOBILIZATION	1	L SUM
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	1	L SUM
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	1	L SUM
70103815	TRAFFIC CONTROL SURVEILLANCE	8	CAL DA
Δ 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	183.6	SQ FT
Δ 78005110	EPOXY PAVEMENT MARKING - LINE 4"	513	FOOT
Δ 78005150	EPOXY PAVEMENT MARKING - LINE 12"	93	FOOT
Δ 78005180	EPOXY PAVEMENT MARKING - LINE 24"	93	FOOT
78300100	PAVEMENT MARKING REMOVAL	525	SQ FT
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	1	L SUM
X6028300	INLETS TO BE REMOVED, SPECIAL	1	EACH
XX003219	UNIT PAVERS	2424	SQ FT
XX008864	INSTALL SIGN	1	EACH

Δ SPECIALTY ITEMS

INDEX OF PLANS

COVER SHEET.....	1
SUMMARY OF QUANTITIES, INDEXES, LIST OF STANDARDS.....	2
GENERAL NOTES.....	3
EXISTING TYPICAL SECTIONS.....	4
PROPOSED TYPICAL SECTIONS.....	5 - 6
REMOVAL SCHEDULES.....	7
DRAINAGE SCHEDULES.....	8
EROSION CONTROL SCHEDULES.....	9
PROPOSED SURFACING SCHEDULES.....	10
UNIT PAVERS AND LOOKING FOR LINCOLN SIGN DETAILS.....	11
DRIVEWAY DETAILS.....	12-14
PAVEMENT MARKING SCHEDULES.....	15
DEMOLITION PLAN SHEETS.....	16 - 19
PROPOSED PLAN SHEETS.....	20 - 23
PROFILE SHEET.....	24
CROSS SECTION SHEETS.....	25 - 28

INDEX OF STANDARDS

STANDARD NUMBER	STANDARD NAME
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREA OF REINFORCEMENT BARS
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
424001-07	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
602401-03	MANHOLE TYPE A
602601-02	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
602701-02	MANHOLE STEPS
604001-03	FRAME AND LIDS TYPE 1
604006-04	FRAME AND GRATE TYPE 3
606001-05	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB & GUTTER
701006-04	OFF-RD OPERATIONS, 2L 2W, 15' TO 24' FROM PAVEMENT EDGE
701301-04	LANE CLOSURE, 2L 2W SHORT TIME OPERATIONS
701311-03	LANE CLOSURE 2L 2W MOVING OPERATIONS DAY ONLY
701806-08	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701801-05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS

QUANTITIES, INDEX, STANDARDS			
SCALE: N/A	APPROVED BY: SAS	DATE: 01/31/13	DRAWN BY: CRS
			REVISED: KPP
11-00052-00-BT			DRAWING NUMBER