

SUMMARY OF QUANTITIES

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
*	20100500	TREE REMOVAL, ACRES	ACRE	0.8
*	20200100	EARTH EXCAVATION	CU YD	1,915
*	20300100	CHANNEL EXCAVATION	CU YD	901
*	20400800	FURNISHED EXCAVATION	CU YD	670
#	25000210	SEEDING, CLASS 2A	ACRE	1.5
#	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	135
#	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	135
#	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	135
#	25100115	MULCH, METHOD 2	ACRE	1.5
#	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150
	28000305	TEMPORARY DITCH CHECKS	FOOT	100
	28000315	AGGREGATE DITCH CHECKS	TON	12
	28000400	PERIMETER EROSION BARRIER	FOOT	484
	28000500	INLET AND PIPE PROTECTION	EACH	2
*	28100807	STONE DUMPED RIPRAP, CLASS A4	TON	345
*	35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,330
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,118
	40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	2,977
	40300500	COVER COAT AGGREGATE	TON	55
	40300600	SEAL COAT AGGREGATE	TON	28
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	62
	48100100	AGGREGATE SHOULDERS, TYPE A	TON	384
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
	50105220	PIPE CULVERT REMOVAL	FOOT	53
	50200100	STRUCTURE EXCAVATION	CU YD	74
	50300225	CONCRETE STRUCTURES	CU YD	53.8
	50300280	CONCRETE ENCASMENT	CU YD	32.7
	50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	3,318
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7,560
#	50901050	STEEL RAILING, TYPE SM	FOOT	240

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
	51201400	FURNISHING STEEL PILES HP10X42	FOOT	370
	51201610	FURNISHING STEEL PILES HP12X63	FOOT	368
	51202305	DRIVING PILES	FOOT	738
	51203400	TEST PILE STEEL HP10X42	EACH	1
	51203610	TEST PILE STEEL HP12X63	EACH	1
	51500100	NAME PLATES	EACH	1
*	542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	72
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4
	58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	370
	58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	712
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	23.8
#	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* *	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
	67100100	MOBILIZATION	L SUM	1
#	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	42
*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1
#	A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	6
#	B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10
*	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

FILE NAME: H:\01\02\23\SUMMARY\5119.dgn

USER NAME: JSEAF0500L

DESIGNED: DRAWN

REVISED: REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

TR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
156	02-04116-00-BR	BOND	28	3
SN 003-3414			CONTRACT NO. 97521	
[ILLINOIS] FED. AID PROJECT				

H&G NO. 5119