

### GENERAL

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION, AS INDICATED BY THE SUB-NUMBER LISTED IN THE INDEX OF SHEETS, OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS. FOR CODED PAY ITEM DESCRIPTIONS, INCLUDED ITEMS, AND ALL MATERIAL SPECIFICATIONS, PLEASE REFER TO THE LATEST EDITION OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.

THE CONTRACTOR SHALL CONFINE HIS/HER OPERATIONS TO THE AREA LOCATED WITHIN THE CONSTRUCTION LIMIT LINES, AS SHOWN ON PLANS. ANY AREA DISTURBED BEYOND THESE LIMITS SHALL BE RESTORED TO ITS ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.

IT IS NOT WARRANTED THAT THIS DOCUMENT CONTAINS COMPLETE INFORMATION REGARDING EASEMENTS, RESERVATIONS, RESTRICTIONS, RIGHT-OF-WAYS, BUILDING LINE SETBACKS, AND OTHER ENCUMBRANCES. FOR COMPLETE INFORMATION, A TITLE OPINION OR COMMITMENT FOR TITLE INSURANCE SHOULD BE OBTAINED AND THOROUGHLY REVIEWED.

THE CORPS OF ENGINEERS PERMIT DOES NOT AUTHORIZE THE CLEARING AND GRUBBING OF MATURE TREES DUE TO THE FEDERALLY ENDANGERED SPECIES, INDIANA BAT (MYOTIS SODALIS).

### UTILITIES - LOCATIONS/INFORMATION ON PLANS

UNLESS NOTED OTHERWISE, THE TYPE, SIZE, DEPTH AND LOCATION OF EXISTING WATER MAINS, GAS MAINS, SEWERS, ELECTRIC POWER LINES, TELEPHONE LINES AND OTHER UTILITIES AS DELINEATED ON THE PLANS HAVE BEEN DETERMINED BY REVIEW OF AVAILABLE EXISTING "AS-BUILT" OR RECORD DRAWINGS, FIELD SURVEY OF J.U.L.I.E. MARKED UTILITIES, OR FIELD SURVEY OF ABOVE GROUND SURFACE UTILITY FEATURES. THE OWNER AND ENGINEER HAVE NOT UNDERTAKEN SUBSURFACE EXPLORATORY INVESTIGATIONS TO CONFIRM OR VERIFY THE UTILITIES SHOWN ON THESE PLANS; THEREFORE THEIR EXACT LOCATION, SIZE AND FUNCTION MUST BE CONSIDERED APPROXIMATE. THE EXISTING LOCATION OF ALL FIBER OPTIC, UNDERGROUND ELECTRIC, UNDERGROUND TELEPHONE, CABLE, WATER LINES AND PROPOSED SEWER FORCE MAIN LINES HAVE BEEN APPROXIMATED AT MINIMUM DEPTHS OF 24", 30", 24", 24", 30", AND 30", RESPECTIVELY.

THE ENGINEER AND OWNER FURTHER DO NOT WARRANT THAT ALL UTILITIES HAVE BEEN ILLUSTRATED ON THE DOCUMENTS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONTACTING J.U.L.I.E. FOR FIELD VERIFICATION OF ALL UTILITIES ON THE SITE PRIOR TO COMMENCEMENT OF CONSTRUCTION. IF THE CONTRACTOR DETERMINES THAT SUBSTANTIAL DISCREPANCY EXISTS BETWEEN FIELD VERIFIED UTILITIES AND THESE PLANS WHICH WOULD SIGNIFICANTLY AFFECT THE FUNCTION, COST, OR PERFORMANCE OF THE PROJECT, THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE ENGINEER FOR CLARIFICATION AND PROJECT DIRECTION.

### EROSION CONTROL

IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT ALL EROSION AND DISPLACED SEDIMENT DOES NOT MIGRATE OFF SITE. IF UNEXPECTED EROSION OR SEDIMENTATION OCCURS, OR IF THE EROSION PLAN STRUCTURES BECOME DAMAGED, THE CONTRACTOR SHALL PROVIDE SUFFICIENT MEASURES TO REPAIR, REPLACE, OR INSTALL EROSION CONTROL STRUCTURES TO INSURE OFF-SITE DAMAGE DOES NOT OCCUR. ANY SEDIMENT OR EROSION DAMAGE WHICH OCCURS OFF-SITE SHALL BE REPAIRED BY THE CONTRACTOR AT HIS/HER EXPENSE.

### COMMITMENTS

NONE.

### UTILITY OWNERS AND CONTACT INFORMATION

GAS AMEREN ILLINOIS JASON KLEIN (618) 236-4309	ELECTRIC MONROE COUNTY ELECTRIC CO-OPERATIVE ALAN W. WATTLES (618) 939-7171
CABLE TELEVISION CHARTER COMMUNICATIONS (618) 345-8003	CITY OF COLUMBIA RON WILLIAMS (618) 281-4264
TELEPHONE HARRISONVILLE TELEPHONE CO (618) 939-9256	

ITEM NO	PAY ITEM	UNIT	TOTAL
20300100	CHANNEL EXCAVATION	CU YD	235
28100107	STONE RIPRAP, CLASS A4	SQ YD	608
28200200	FILTER FABRIC	SQ YD	608
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	53
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	3053
△ 50901050	STEEL RAILING, TYPE SM	FOOT	227
51500100	NAME PLATES	EACH	1
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	341
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	916
△ 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
△ 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
△ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3
63200310	GUARDRAIL REMOVAL	FOOT	193
67100100	MOBILIZATION	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
△ 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8
△ 78200530	BARRIER WALL MARKERS, TYPE C	EACH	6
△ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3
X0327301	RELOCATE EXISTING MAILBOX	EACH	3
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.25

△ SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS		GENERAL NOTES AND SUMMARY OF QUANTITIES		F.A.U.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PA\12861314-CA00 - DWG\4.2-TR\Sheets\12861314-shr\gennotes_S00.dgn	hastermiller	-	-	DEPARTMENT OF TRANSPORTATION				9304	12-00023-01-BR	MONROE	16	2
	PLOT SCALE = 40,0000 1/4" = 1'	CHECKED	REVISED			SCALE: NONE		SHEET NO. 1 OF 1 SHEETS		CONTRACT NO. 97524		
	PLOT DATE = 4/18/2013	DATE	REVISED			STA.		TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		