



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2019

SUBJECT: Various Routes
Project STP-TH35(673)
Section 2018-099-TS
Various Counties
Contract No. 62H46
Item No. 16, June 14, 2019 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised pages 1 & 42 of the Special Provisions
3. Revised sheets 2-10 & 52-55 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

MS

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted April 1, 2016, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of Various Routes, Project STP-TH35 (673), Section 2018-099-TS, Various Counties, Contract No. 62H46 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

Various Routes
Project STP-TH35 (673)
Section 2018-099-TS
Various Counties
Contract No. 62H46

LOCATION OF PROJECT

The project is located in:

5 locations in Cook County:

1. PALATINE RD AT WINDSOR DR
2. PALATINE RD AT SCHOENBECK RD
3. PALATINE RD AT WHEELING RD
4. US RTE 14 AT RAND RD/NORTHWEST HWY
5. TOUHY AVE AT DEE RD

2 locations in Lake County:

6. IL RTE 176 (ROCKLAND RD) AT IL RTE 43 (WAUKEGAN RD)
7. IL RTE 176 (ROCKLAND RD) AT IL RTE 131 (GREEN BAY RD)

DESCRIPTION OF PROJECT

This work includes trombone mast arm and pole replacement, installation of LED signal heads, traffic signal posts, relocation of pedestrian signal heads and push buttons, and all incidental and collateral work necessary to complete the project as shown on the plans and as described herein.

Revised 6-7-2019

RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON

Effective: August 4, 2017

Relocation.

Revise the last paragraph of Article 895.02 of the Standard Specifications to read:

When relocating an existing pedestrian push-button, the related sign shall be removed and installed at the new location. The push-button shall be installed according to Article 888.03. Mounting / extension brackets shall be used to assure that the push button is accessible from a paved or concrete surface and is in full compliance with ADA. Mounting / extension brackets shall not be paid for separately but shall be included in the cost of the RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON pay item.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Intersection of IL Route 176 (Rockland Road) and IL Route 43 (Waukegan Road), Lake Bluff, Lake County

- All excavation planned at the northwest quadrant, and northeast quadrant at the intersection of IL Route 176 (Rockland Road) and IL Route 43 (Waukegan Road). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.
- All excavation planned at the southwest quadrant, and southeast quadrant at the intersection of IL Route 176 (Rockland Road) and IL Route 43 (Waukegan Road). The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Revised 6-7-2019