

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED - 20% STATE NHPP (FAP 698)	80% FED - 20% STATE NHPP (FAU 5605)	80% FED - 20% STATE STP (FAP 698)
				ROADWAY	ROADWAY	ROADWAY
				0005 URBAN	0005 URBAN	0005 URBAN
20400800	FURNISHED EXCAVATION	CU YD	33	33		
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	56	56		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	33	33		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	31	26	3	2
40600535	LEVELING BINDER (HAND METHOD), N70	TON	49	44	5	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	9682	9296	386	
40600990	TEMPORARY RAMP	SQ YD	518	366	152	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9243	8471	772	
40700100	BITUMINOUS MATERIALS (TACK COAT)	POUND	68861	59,876	6468	2517
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	878	804	74	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	704	704		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	20052	7130	9194	3728
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	80305	80,305		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	780	780		



MODEL: Default
FILE NAME: P:\uplanroom.dwg
PROJECT: I:\CDData\366E21\CDData\366E21-1-1-500.dwg

USER NAME = nugentaj	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISIED -
PLOT DATE = 3/20/2019	CHECKED -	REVISIED -
	DATE -	REVISIED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 5 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	BUREAU	52	3
CONTRACT NO. 66E21				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED - 20% STATE NHPP (FAP 698)	80% FED - 20% STATE NHPP (FAU 5605)	80% FED - 20% STATE STP (FAP 698)	
				ROADWAY	ROADWAY	ROADWAY	
				0005	0005	0005	
				URBAN	URBAN	URBAN	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1492		1492		
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	2		2		
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	42282		35,135	3754	3393
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2679		2098	581	
* X7830060	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	125				125
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	3459		3459		
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	1158				1158
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	5577		4186	1027	364
* X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	566		437	35	94
* X8860100	LOOP DETECTOR TESTING	EACH	2		1		1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	105		63	21	21
Ø Z0076600	TRAINEES	HOUR	1000		1000		
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	34435		30,209	4226	
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1000		1000		
Z0034105	MATERIAL TRANSFER DEVICE	TON	18,925		17,759	1158	

*= SPECIALTY ITEM Ø 0042

MODEL: Default
FILE: Main: P:\p1\p1room.dwg
PROJECT: \CADD\DATA\366E21\366E21-1-1-500.dgn

USER NAME = nugentaj	DESIGNED -	REVISED -
DRAWN -	CHECKED -	REVISED -
PLOT SCALE = 100.0000' / in.	DATE -	REVISED -
PLOT DATE = 3/20/2019		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET 5	OF 5 SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**		52	7
			CONTRACT NO. 66E21	
		ILLINOIS	FED. AID PROJECT	

