

MODEL: 4400E1.MXD
 FILE NAME: S:\2019\181018_Various Structure IDOT D3 Farnsworth PTB 1612\Work Order 13 - 180_Temp Crossover\CADD\CADD_Sheets\0366421-ph-S00.dgn

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE |
|----------|---|-------|----------------|------------------------|
| | | | | 90% FED 10% STATE |
| | | | | ROADWAY |
| | | | | 0006 |
| | | | | URBAN |
| 20200100 | EARTH EXCAVATION | CU YD | 455 | 455 |
| 20400800 | FURNISHED EXCAVATION | CU YD | 85 | 85 |
| 25000200 | SEEDING, CLASS 2 | ACRE | 0.50 | 0.50 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 45 | 45 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 45 | 45 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 45 | 45 |
| 25100115 | MULCH, METHOD 2 | ACRE | 0.50 | 0.50 |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 24 | 24 |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 50 | 50 |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 299 | 299 |
| 31101810 | SUBBASE GRANULAR MATERIAL, TYPE B 12" | SQ YD | 1,193 | 1,193 |
| 40600275 | BITUMINOUS MATERIALS (PRIME COAT) | POUND | 2,683 | 2,683 |
| 40600290 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 5,402 | 5,402 |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 371 | 371 |

* SPECIALTY ITEM



| | | |
|----------------------------|------------------|-----------|
| USER NAME = tneffsmith | DESIGNED - GSN | REVISED - |
| | DRAWN - TNS | REVISED - |
| PLOT SCALE = 2.0000' / in. | CHECKED - PEC | REVISED - |
| PLOT DATE = 3/12/2019 | DATE - 2/13/2019 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------|-----------|---------|---------------------------|-----------|
| 80 | (50-2)I-4 | LASALLE | 25 | 3 |
| CONTRACT NO. 66J74 | | | ILLINOIS FED. AID PROJECT | |

MODEL: 4409E1NAME.F
 FILE NAME: S:\2018\1811\1811018_Various Structure IDOT D3_Fairsworth PTB_1612\1Work Order_13 - 140_Temp_Crossovers\CADD\CADD_Sheets\0366H21-ph-S00.dgn

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE | |
|----------|---|--------|----------------|------------------------|---|
| | | | | 90% FED 10% STATE | |
| | | | | ROADWAY | |
| | | | | 0006 | |
| | | | | URBAN | |
| | | | | | 1 |
| 40603090 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 | TON | 1,679 | 1,679 | |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 183 | 183 | |
| 40603345 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 | TON | 755 | 755 | |
| 44000173 | HOT-MIX ASPHALT SURFACE REMOVAL, 6" | SQ YD | 7,207 | 7,207 | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 376 | 376 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 0.20 | 0.20 | |
| 542D0223 | PIPE CULVERTS, CLASS D, TYPE 1 18" | FOOT | 182 | 182 | |
| 54260818 | SLOPED METAL END SECTION, STANDARD 542416, 18", 1:4 | EACH | 2 | 2 | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 619 | 619 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 1 | 1 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100420 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 | EACH | 2 | 2 | |
| 70100825 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701456 | L SUM | 1 | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 10 | 10 | |

* SPECIALTY ITEM



| | | |
|----------------------------|------------------|-----------|
| USER NAME = tneffsmith | DESIGNED - GSN | REVISED - |
| PLOT SCALE = 2.0000' / in. | DRAWN - TNS | REVISED - |
| PLOT DATE = 3/19/2019 | CHECKED - PEC | REVISED - |
| | DATE - 2/13/2019 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 2 OF 3 SHEETS STA. TO STA.

| | | | | |
|---------------------------|-----------|---------|-----------------|--------------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 80 | (50-2)I-4 | LASALLE | 25 | 4 |
| CONTRACT NO. 66J74 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |

1

| I-80 SHOULDER PAVING SCHEDULE | | | | | | | | | | |
|-------------------------------|----|-----------|-------------------------|--------------|---|--|---|--|-------------------------------------|----------------------------------|
| STATION TO STATION | | | | | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 | HOT-MIX ASPHALT SURFACE REMOVAL, 6" | BITUMINOUS MATERIALS (TACK COAT) |
| | | | | | TONS | TONS | TONS | TONS | SQ YD | POUND |
| EASTBOUND | | | | | | | | | | |
| STATION | to | STATION | SHOULDER INSIDE/OUTSIDE | WIDTH (FT) | | | | | | |
| 595+00.00 | | 612+43.00 | OUTSIDE | 3 | | | 130 | 65 | 581 | 392 |
| 617+07.00 | | 626+50.00 | OUTSIDE | 3 | | | 70 | 35 | 314 | 212 |
| 627+00.00 | | 640+20.00 | OUTSIDE | 3 | | | 99 | 49 | 440 | 297 |
| 643+40.00 | | 662+00.00 | OUTSIDE | 3 | | | 139 | 69 | 620 | 419 |
| 676+50.00 | | 695+00.00 | OUTSIDE | 3 | | | 138 | 69 | 617 | 416 |
| 674+37.00 | | 676+75.00 | INSIDE | 4 | | | 24 | 12 | 106 | 71 |
| 688+97.22 | | 699+97.22 | INSIDE | ENTIRE SHLDR | | | 219 | 109 | 977 | 660 |
| WESTBOUND | | | | | | | | | | |
| STATION | to | STATION | | | | | | | | |
| 607+00.00 | | 612+20.00 | OUTSIDE | 3 | 39 | 19 | | | 173 | 117 |
| 614+50.00 | | 627+46.00 | OUTSIDE | 3 | 97 | 48 | | | 432 | 292 |
| 627+75.00 | | 633+50.00 | OUTSIDE | 3 | 43 | 21 | | | 192 | 129 |
| 609+00.00 | | 612+20.00 | INSIDE | 4 | 32 | 16 | | | 142 | 96 |
| 617+07.00 | | 627+18.00 | INSIDE | 4 | 101 | 50 | | | 449 | 303 |
| 627+62.00 | | 633+50.00 | INSIDE | 4 | 59 | 29 | | | 261 | 176 |
| 688+97.22 | | 699+97.22 | INSIDE | ENTIRE SHLDR | | | 216 | 108 | 966 | 652 |
| TOTAL | | | | | 371 | 183 | 1,035 | 516 | 6,270 | 4,232 |

MODEL: 4409E1\MNMF5
FILE NAME: S:\2019\1811811818_Various Structure IDOT D3_Farmsworth_PTB_1612\Work Order 13 - I-80_Temp_Crossovers\Addendum\CADD\CADD_Sheets\036642-ent-schedule.dgn



USER NAME = tneffsmith
DRAWN - TNS
CHECKED - PEC
DATE - 2/13/2019

DESIGNED - GSN
DRAWN - TNS
CHECKED - PEC
DATE - 2/13/2019

REVISED 5/22/2019 GSN
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 3 OF 3 SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|------------|---------|--------------|-----------|
| 80 | (50-2)-I-4 | LASALLE | 25 | 11 |
| CONTRACT NO. 66J74 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |