



CONSTR. CODE
CONTRACT MAINTENANCE
100% STATE
ROADWAY
0006
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
42000060	WELDED WIRE REINFORCEMENT	SQ YD	83	83 
44201043	CLASS B PATCHES, TYPE II, 16 INCH	SQ YD	1552	1552
44201047	CLASS B PATCHES, TYPE III, 16 INCH	SQ YD	99	99
44201048	CLASS B PATCHES, TYPE IV, 16 INCH	SQ YD	33	33
44201299	DOWEL BARS 1 1/2"	EACH	3280	3280
44213200	SAW CUTS	FOOT	8056	8056
44213204	TIE BARS 3/4"	EACH	46	46 
67100100	MOBILIZATION	L SUM	1	1
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
Z0017099	DOWEL BAR ASSEMBLY	EACH	4	4
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	42	42

FILE NAME =	USER NAME = MARINIEJ	DESIGNED - EVAN MARINI	REVISED -
pw:\planroom.dot\illinois.gov\PWIDOT\Documents\DOT	files\District 3\Projects\0366K06\CADData\66K06-cover.dgn	DRAWN - EVAN MARINI	REVISED -
Default	PLOT SCALE = 5.5242' / mm	CHECKED - RON WOODSHANK	REVISED -
	PLOT DATE = 3/11/2019	DATE - 1/22/2019	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	D3 IL 1 PP 2020-8	IROQUOIS	10	3
CONTRACT NO. 66K06				
ILLINOIS FED. AID PROJECT				

PATCHING SCHEDULE - IL 1

NORTHBOUND LANE								
LOCATION	PATCH LENGTH	CLASS B			DOWEL BARS 1 1/2"	SAW CUTS	WELDED WIRE REINF. SQ YD	TIE BARS 3/4"
		TYPE II	TYPE III	TYPE IV				
LOG MILE	(FT)	16"	16"	16"	EACH	FOOT	SQ YD	EACH
0.01	8	13			20	52		
0.10	8	13			20	52		
0.10	6	10			20	48		
0.30	20			33	20	76		10
0.60	6	10			20	48		
0.70	6	10			20	48		
0.80	8	13			20	52		
0.90	6	10			20	48		
1.00	6	10			20	48		
1.70	6	10			20	48		
3.10	6	10			20	48		
3.30	6	10			20	48		
3.60	6	10			20	48		
3.70	6	10			20	48		
3.80	6	10			20	48		
3.90	6	10			20	48		
4.40	6	10			20	48		
4.50	8	13			20	52		
4.60	6	10			20	48		
4.80	8	13			20	52		
4.90	6	10			20	48		
5.10	6	10			20	48		
5.10	6	10			20	48		
5.50	8	13			20	52		
5.80	13		22		20	62	22	
6.10	6	10			20	48		
6.20	6	10			20	48		
6.30	6	10			20	48		
6.60	6	10			20	48		
6.60	6	10			20	48		
7.20	8	13			20	52		4
7.32	8	13			20	52		4
7.40	8	13			20	52		4
7.50	8	13			20	52		4
7.60	8	13			20	52		4
10.60	6	9			20	48		
11.00	6	9			20	48		
11.10	6	9			20	48		
11.40	10		16		20	56		
11.80	6	9			20	48		
11.90	8	12			20	52		
12.00	6	9			20	48		
12.10	6	9			20	48		
12.20	6	9			20	48		
12.20	6	9			20	48		
12.30	6	9			20	48		
12.30	6	9			20	48		
12.40	6	9			20	48		
12.40	6	9			20	48		
12.60	6	9			20	48		
13.40	6	9			20	48		
13.70	6	9			20	48		
13.80	6	9			20	48		
13.90	6	9			20	48		
14.10	6	9			20	48		
18.30	8	12			20	52		
19.00	13		20		20	62	20	
SUBTOTALS		549	58	33	1140	2852	42	30

\*  
\*  
\*  
\*  
\*

\*CC&G Section 15-FT Wide w/ties to Curb

PATCHING SCHEDULE - IL 1

NORTHBOUND LANE (CONT.)								
LOCATION	PATCH LENGTH	CLASS B			DOWEL BARS 1 1/2"	SAW CUTS	WELDED WIRE REINF. SQ YD	TIE BARS 3/4"
		TYPE II	TYPE III	TYPE IV				
LOG MILE	(FT)	16"	16"	16"	EACH	FOOT	SQ YD	EACH
19.00	6	9			20	48		
19.20	8	12			20	52		
19.80	6	9			20	48		
20.00	6	9			20	48		
20.10	6	9			20	48		
20.20	6	9			20	48		
20.50	6	9			20	48		
20.60	6	9			20	48		
21.10	6	9			20	48		
21.20	6	9			20	48		
21.40	6	9			20	48		
21.50	6	9			20	48		
21.70	6	9			20	48		
21.80	6	9			20	48		
21.80	6	9			20	48		
21.80	6	9			20	48		
22.00	6	9			20	48		
22.10	6	9			20	48		
22.60	6	9			20	48		
23.30	6	9			20	48		
23.30	6	9			20	48		
23.40	6	9			20	48		
23.50	6	9			20	48		
23.70	6	9			20	48		
24.00	6	9			20	48		
24.10	6	9			20	48		
24.30	6	9			20	48		
24.50	6	9			20	48		
25.10	6	9			20	48		
25.20	6	9			20	48		
25.30	6	9			20	48		
25.60	6	9			20	48		
25.60	6	9			20	48		
25.80	12		19		20	60	19	
25.80	8	12			20	52		
26.00	6	9			20	48		
26.10	8	12			20	52		
26.30	6	9			20	48		
26.40	6	9			20	48		
26.50	8	12			20	52		
26.50	6	9			20	48		
26.90	6	9			20	48		
27.00	6	9			20	48		
27.00	6	9			20	48		
27.10	6	9			20	48		
27.20	6	9			20	48		
27.40	6	9			20	48		
27.50	8	12			20	52		
27.50	6	9			20	48		
27.70	6	9			20	48		
27.80	6	9			20	48		
29.30	14		22		20	64	22	
29.80	8	12			20	52		
SUBTOTALS		477	41		1060	2596	41	

FILE NAME =	USER NAME = woodshank1	DESIGNED - EVAN MARINI	REVISED - RW 5/31/2019
pw:\planroom\dot\illinois.gov\PWDOT\Documents\IDOT\Files\District 3\Projects\D366K06\CADData\66K06-cover.dgn		DRAWN - EVAN MARINI	REVISED -
Default	PLOT SCALE = 140,0000' / In.	CHECKED - RON WOODSHANK	REVISED -
	PLOT DATE = 5/31/2019	DATE - 1/22/2019	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	D3 IL 1 PP 2020-8	IROQUOIS	10	6
CONTRACT NO. 66K06				
ILLINOIS FED. AID PROJECT				