

43

June 14, 2024 Letting

Notice to Bidders, Specifications and Proposal



**Illinois Department
of Transportation**

**Contract No. 68J24
PEORIA-TAZEWELL Counties
Section D4 HIGHWAY LIGHTING 2025
Route FAI 74
District 4 Construction Funds**

Prepared by

S

Checked by

(Printed by authority of the State of Illinois)



NOTICE TO BIDDERS

- 1. TIME AND PLACE OF OPENING BIDS.** Electronic bids are to be submitted to the electronic bidding system (iCX-Integrated Contractors Exchange). All bids must be submitted to the iCX system prior to 12:00 p.m. June 14, 2024 prevailing time at which time the bids will be publicly opened from the iCX SecureVault.
- 2. DESCRIPTION OF WORK.** The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

**Contract No. 68J24
PEORIA-TAZEWELL Counties
Section D4 HIGHWAY LIGHTING 2025
Route FAI 74
District 4 Construction Funds**

D4 highway lighting 2025: Inspection of existing high mast towers, luminaire repair and re-lamping, maintenance of existing lighting controllers in Peoria and Tazewell Counties.

- 3. INSTRUCTIONS TO BIDDERS.** (a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 101.09 of the Standard Specifications for Road and Bridge Construction, become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.

(b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.
- 4. AWARD CRITERIA AND REJECTION OF BIDS.** This contract will be awarded to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

By Order of the
Illinois Department of Transportation

Omer Osman,
Secretary

INDEX
FOR
SUPPLEMENTAL SPECIFICATIONS
AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2024

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS and frequently used RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction (Adopted 1-1-22) (Revised 1-1-24)

SUPPLEMENTAL SPECIFICATIONS

<u>Std. Spec. Sec.</u>	<u>Page No.</u>
202 Earth and Rock Excavation	1
204 Borrow and Furnished Excavation	2
207 Porous Granular Embankment	3
211 Topsoil and Compost	4
407 Hot-Mix Asphalt Pavement (Full-Depth)	5
420 Portland Cement Concrete Pavement	6
502 Excavation for Structures	7
509 Metal Railings	8
540 Box Culverts	9
542 Pipe Culverts	29
586 Granular Backfill for Structures	34
630 Steel Plate Beam Guardrail	35
644 High Tension Cable Median Barrier	36
665 Woven Wire Fence	37
782 Reflectors	38
801 Electrical Requirements	40
821 Roadway Luminaires	43
1003 Fine Aggregates	44
1004 Coarse Aggregates	45
1010 Finely Divided Minerals	46
1020 Portland Cement Concrete	47
1030 Hot-Mix Asphalt	48
1061 Waterproofing Membrane System	49
1067 Luminaire	50
1097 Reflectors	57

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

<u>CHECK SHEET #</u>	<u>PAGE NO.</u>
1	Additional State Requirements for Federal-Aid Construction Contracts 59
2	Subletting of Contracts (Federal-Aid Contracts) 62
3	X EEO 63
4	X Specific EEO Responsibilities Non Federal-Aid Contracts 73
5	X Required Provisions - State Contracts 78
6	Asbestos Bearing Pad Removal 84
7	Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal 85
8	Temporary Stream Crossings and In-Stream Work Pads 86
9	Construction Layout Stakes 87
10	Use of Geotextile Fabric for Railroad Crossing 90
11	Subsealing of Concrete Pavements 92
12	Hot-Mix Asphalt Surface Correction 96
13	Pavement and Shoulder Resurfacing 98
14	Patching with Hot-Mix Asphalt Overlay Removal 99
15	Polymer Concrete 101
16	Reserved 103
17	Bicycle Racks 104
18	Temporary Portable Bridge Traffic Signals 106
19	Nighttime Inspection of Roadway Lighting 108
20	English Substitution of Metric Bolts 109
21	Calcium Chloride Accelerator for Portland Cement Concrete 110
22	Quality Control of Concrete Mixtures at the Plant 111
23	Quality Control/Quality Assurance of Concrete Mixtures 119
24	Reserved 135
25	Reserved 136
26	Temporary Raised Pavement Markers 137
27	Restoring Bridge Approach Pavements Using High-Density Foam 138
28	Portland Cement Concrete Inlay or Overlay 141
29	Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching 145
30	Longitudinal Joint and Crack Patching 148
31	Concrete Mix Design – Department Provided 150
32	Station Numbers in Pavements or Overlays 151

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES	2
TRAFFIC CONTROL PLAN	2
CONTRACT GUARANTEE	3
CONTRACTOR RESPONSIBILITIES	4
REPLACEMENT OF POWER FUSING.....	4
INSPECT HIGH MAST LIGHTING TOWER.....	5
RELAMP HIGH MAST TOWER LUMINAIRE, 400 WATT	6
REPLACE HIGH MAST LUMINAIRE BALLAST ASSEMBLY, 400 WATT	6
REPLACE HIGH MAST TOWER LOWERING DEVICE MOTOR.....	7
REPLACE HIGH MAST TOWER GEAR BOX ASSEMBLY	7
RELAMP UNDERPASS LUMINAIRE, 100 WATT	8
REPLACE UNDERPASS LUMINAIRE BALLAST ASSEMBLY, 100 WATT.....	8
MAINTAIN EXISTING LIGHTING CONTROLLER	9
CLEAN AND RELAMP EXISTING LUMINAIRE	10
REPLACE LUMINAIRE BALLAST ASSEMBLY	11
AVIATION OBSTRUCTION WARNING LUMINAIRE, LED	11
HPS LAMP RECYCLING	12
HIGH MAST TOWER LOWERING DEVICE MOTOR (MATERIAL ONLY).....	13
REPLACE BOLLARD LED LAMP	14
TOWER LIGHTING INSPECTION AND MAINTENANCE CHECKSHEET	15
CEMENT, TYPE IL (BDE).....	19
COMPENSABLE DELAY COSTS (BDE)	19
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	22
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)..	32
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	32
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	34
SPEED DISPLAY TRAILER (BDE)	37
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	38
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	38
SUBMISSION OF PAYROLL RECORDS (BDE).....	39
TRAFFIC SPOTTERS (BDE).....	40

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....41
WEEKLY DBE TRUCKING REPORTS (BDE).....41
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....42
WORKING DAYS (BDE).....43

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2022 (revised January 1, 2024), the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of FAI Route 74 (I-74), Section D4 Highway Lighting 2025, Peoria and Tazewell Counties, Contract No. 68J24 and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

LOCATION OF PROJECT

This project improvement is located in the following areas:

Peoria County: Interstate 74 through Peoria (from 1900 feet west of the Sterling Avenue interchange to the Murray Baker Bridge).

Tazewell County: Interstate 74 through East Peoria (from Murray Baker Bridge to 2400 ft. east of the Washington Street interchange).

DESCRIPTION OF PROJECT

This project consists of inspecting existing high mast lighting towers, re-lamping and repairing existing high mast luminaires, re-lamping and repairing existing underpass luminaires, performing maintenance on existing lighting controllers, replacing luminaires, and performing all other related collateral work required to the improvements on this project.

LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES

Effective: August 3, 2007 Revised: July 31, 2009

The Contractor shall be responsible for locating existing and proposed IDOT electrical facilities (traffic signal, overhead lighting, Intelligent Transportation System, etc.) prior to performing any work at his/her own expense if required. The Contractor shall also be liable for any damage to IDOT facilities resulting from inaccurate locating.

The Contractor may obtain, on request, plans for existing electrical facilities from the Department.

The Contractor shall also be responsible for locating and providing protection for IDOT facilities during all phases of construction. If at any time the facilities are damaged, the Contractor shall immediately notify the Department and make all necessary arrangements for repair to the satisfaction of the Engineer. This work will not be paid for separately, but shall be included in the contract bid price.

TRAFFIC CONTROL PLAN

Effective: March 15, 2024

Traffic control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction," the applicable guidelines contained in the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways," these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Section 701 and Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction" and the following Highway Standards relating to traffic control:

701001	701006	701101	701106	701400
701406	701428	701456	701601	701901

All traffic control devices shall be furnished, erected, maintained, and removed by the Contractor in accordance with the Standard Specifications. Where possible, all post-mounted signs shall be placed a minimum of two feet (2') (0.6 m) beyond the curb or edge of shoulder. Proposed sign spacing may be modified as approved by the Engineer in order to meet existing field conditions or to prevent obstruction of the motorist's view of permanent signing and lane restrictions at all times.

Traffic shall be maintained on the associated roadways at all times during construction. All lane closures shall be made during off-peak traffic hours, defined as time periods from 8:30 a.m. to 3:30 p.m. and 6:00 p.m. to 6:00 a.m. The Contractor shall notify the Engineer forty-eight (48) hours before the time of a planned closure. The exact time and duration of all lane closures, however, shall be as determined by the Engineer.

The lane closures for work on the seven (7) high mast light towers in the center median on the Peoria side and the seven (7) high mast light towers in the center median on the Tazewell side of the Murray Baker Bridge shall be restricted as shown below (on the next page).

Lane Closure Restrictions		
Light Tower	County	Lane Closure Restrictions
GCD L-01	Peoria	SUNDAY ONLY 8:30 A.M. to 3:30 P.M.
GCD L-02	Peoria	
GCD L-03	Peoria	
ABC L-01	Peoria	
AFG L-01	Peoria	
AFG L-02	Peoria	
AFG L-03	Peoria	
RCD L-01	Tazewell	
RAB L-01	Tazewell	
RAB L-02	Tazewell	
RAB L-03	Tazewell	
RAB L-04	Tazewell	
MAB L-04	Tazewell	
MAB L-03	Tazewell	

When working on light towers located in the median, the Contractor will be required to close the inside lanes in both directions. There will be no additional compensation for closing interstate lanes in both directions.

Method of Measurement: Traffic Control and Protection will be measured by Lump Sum, Complete.

Basis of Payment: This work shall be paid for at the contract unit price per Lump Sum for TRAFFIC CONTROL AND PROTECTION, (SPECIAL), which shall be payment in full for all labor, materials, and equipment required to furnish, install, and remove the traffic control with the Highway Standards listed above.

CONTRACT GUARANTEE

The Contractor shall guarantee all electrical equipment, apparatus, materials, and workmanship provided under the contract for a period of six (6) months after the date of final inspection according to Article 801.14.

All instruction sheets required to be furnished by the manufacturer for materials and supplies and for operations shall be delivered to the Engineer prior to the acceptance of the project, with the following warranties and guarantees:

1. The manufacturer's standard written warranty for each piece of electrical equipment or apparatus furnished under the contract.
2. The Contractor's written guarantee that, for a period of six (6) months after the date of final inspection of the project, all necessary repairs to or replacement of said warranted equipment, or apparatus shall be made by the Contractor at no cost to the Department.
3. The Contractor's written guarantee for satisfactory operation of all electrical systems furnished and constructed under the contract for a period of 6 months after final inspection of the project.

The Department will perform a lighting check near the end of the six-month warranty period to determine the number of non-functioning luminaires. The Contractor shall repair all non-functioning luminaires under the contract guarantee. In the event that the luminaire failure is not related to the nature of the work that was completed, the Contractor shall receive payment for the repair under Article 109.04 of the Standard Specifications (payment for extra work).

If the luminaire repair requires a mainline interstate lane closure, the Contractor shall be responsible for making the repair; however, the associated interstate lane closure will be paid for under Article 109.04 of the Standard Specifications (payment for extra work).

CONTRACTOR RESPONSIBILITIES

Prior to commencing work, the Contractor shall acquire all pertinent Manufacturer's operation and maintenance manuals for the tower lowering devices and luminaires. The Contractor shall be familiarized and knowledgeable in the maintenance and operation of the lighting equipment.

The Contractor shall have all required equipment and sufficient supplies of all required materials available at the immediate work site to minimize operations and traffic disruptions, maximize work efficiency, and prevent unnecessary lowering of the luminaire ring.

The Department will provide, upon request, electronic copies of installation plans as well as any other maintenance and operation documentation to the Contractor.

This work will not be paid for separately but shall be included in the bid price for the contract.

REPLACEMENT OF POWER FUSING

This work shall be in accordance with the applicable Articles of Sections 825 and 1068 of the Standard Specifications.

Upon finding a failed fuse in a main tower power feeder fuse holder, motor branch circuit, upper tower junction box, or luminaire (high mast, underpass, and tunnel), the Contractor shall thoroughly analyze the component and perform troubleshooting to determine the cause of the fuse failure and remedy the cause of the failure before replacing the fuse.

The Contractor shall remove failed fuses and install new KTK, FNM, or other type fuses as required to restore operation.

The Contractor shall supply all required materials and perform all other work that is required to complete the work described above.

This work will not be paid separately but shall be included in the cost of the contract and its associated pay items.

INSPECT HIGH MAST LIGHTING TOWER

This work shall be in accordance with the applicable Articles of Sections 835 and 1069 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall inspect each high mast tower utilizing the attached check sheet.
- The Contractor shall perform all routine maintenance procedures that are detailed on the check sheet and complete all entries.
- The Contractor shall supply all required materials and perform all other work that is required to complete the items listed on the check sheet.
- The Contractor shall perform all work to the satisfaction of the Engineer.

Some of the luminaire maintenance items that are included on the check sheet to be performed during tower inspection will be paid for under separate pay items. These items are notated on the check sheet.

Towers located in median barrier wall will require lane closures in both the eastbound and westbound inside lanes due to the width of the median.

The Contractor shall immediately inform the Engineer of any repair work that is outside of the work contained on check sheet so that repairs can be performed during the initial tower inspection. These repairs will be considered extra work and shall be paid for in accordance with Article 109.04 of the Standard Specifications.

Basis of Payment: This work will be paid for at the contract unit price per Each for INSPECT HIGH MAST LIGHTING TOWER which price shall be payment in full for all labor, materials, and equipment required to inspect the high mast light towers and their associated equipment as described above.

RELAMP HIGH MAST TOWER LUMINAIRE, 400 WATT

This work shall be in accordance with the applicable Articles of Sections 821, 1065, 1066, 1067, and 1068 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall furnish and install a new 400-watt HPS non-cycling lamp in the high mast luminaire.
- The Contractor shall remove and dispose of the existing lamp in accordance with the manufacturer's instructions and all applicable EPA regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for RELAMP HIGH MAST TOWER LUMINAIRE, 400 WATT which price shall be payment in full for all labor, materials, and equipment required to remove and dispose of the existing lamp and install a new lamp in the high mast luminaire as described above.

REPLACE HIGH MAST LUMINAIRE BALLAST ASSEMBLY, 400 WATT

This work shall be in accordance with the applicable Articles of Sections 821, 1065, 1066, 1067, and 1068 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall furnish and install a new 400-watt magnetic regulated ballast assembly in high mast tower luminaires that are not functioning after the installation of a new lamp and fuses.
- The ballast assembly for the Holophane high mast luminaires located along I-74 through Peoria and East Peoria shall be a manufacturer approved retrofit that has been designed for installation in a Holophane ballast tray. The assembly shall not require any drilling of the ballast tray or the installation of additional brackets and other components to secure the assembly to the tray. In order to minimize the repair time required in the field, the Department will supply eighteen Holophane empty ballast trays to the Contractor. The Contractor shall install new ballast assemblies in these trays and utilize them for replacements in non-functioning luminaires. At the completion of the project, the Contractor shall return eighteen fully functional ballast trays, complete with new ballast assemblies to the Department.
- The Contractor shall supply all required materials and perform all other work that is required for the replacement of the high mast luminaire ballast assembly and installation of the assembly in the high mast luminaire.
- The Contractor shall remove and dispose of failed components in accordance with the manufacturer's instructions and all applicable EPA regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for REPLACE HIGH MAST LUMINAIRE BALLAST ASSEMBLY, 400 WATT which price shall be payment in full for all labor, materials, and equipment required to pick up the ballast trays from the Department, retrofit new ballast assemblies in the ballast trays, install the ballast trays in non-functioning luminaires, and deliver the ballast trays complete with new ballast assemblies to the Department upon the completion of the project as described above.

REPLACE HIGH MAST TOWER LOWERING DEVICE MOTOR

This work shall be in accordance with the applicable Articles of Sections 835 and 1069 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall pick up the new lowering device from the IDOT Traffic Building located at 1025 W. Detweiller Drive, Peoria. Contact Tony Bridson at telephone number (309) 370-7522 a minimum of forty-eight hours (48 hrs.) prior to pick up.
- The Contractor shall install the new lowering device motor in a high mast tower as directed by the Engineer.
- The Contractor shall supply all other required materials and perform all other work that is required for the replacement of the lowering device motor.
- The Contractor shall remove and dispose of the failed motors in accordance with all applicable regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for REPLACE HIGH MAST TOWER LOWERING DEVICE MOTOR which price shall be payment in full for all labor, materials, and equipment required to pick up the lowering device motor from the IDOT traffic building and deliver it to the job site, remove the failed lowering device motor, install a new lowering device motor in a high mast tower, and test the new motor for correct operation as described above.

REPLACE HIGH MAST TOWER GEAR BOX ASSEMBLY

This work shall be in accordance with the applicable Articles of Sections 835 and 1069 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall pick up the new gear box assembly from the IDOT Traffic Building located at 1025 West Detweiller Drive, Peoria, Illinois. Contact Tony Bridson at telephone number (309) 370-7522 a minimum of forty-eight hours (48 hrs.) prior to pick up.

- The Contractor shall install a new lowering device gear box in a high mast tower as directed by the Engineer.
- The Contractor shall supply all other required materials and perform all other work that is required for the replacement of the lowering device gear box assembly.
- The Contractor shall remove and dispose of the failed gear box assembly components in accordance with all applicable regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for REPLACE HIGH MAST TOWER GEAR BOX ASSEMBLY which price shall be payment in full for all labor, materials, and equipment required to pick up the gear box from the IDOT traffic building and deliver it to the job site, remove the failed lowering device gear box assembly, and install a new lowering device gear box assembly in a high mast tower as described above.

RELAMP UNDERPASS LUMINAIRE, 100 WATT

This work shall be in accordance with the applicable Articles of Sections 821, 1065, 1066, 1067, and 1068 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall furnish and install a new 100-watt HPS non-cycling lamp in the underpass luminaire.
- The Contractor shall clean the inside and outside of the luminaire lens.
- The Contractor shall remove and dispose of the existing lamp in accordance with the manufacturer's instructions and all applicable EPA regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for RELAMP UNDERPASS LUMINAIRE, 100 WATT which price shall be payment in full for all labor, materials, and equipment required to remove, clean the luminaire lens, and dispose of the existing lamp and install a new lamp in the underpass luminaire as described above.

REPLACE UNDERPASS LUMINAIRE BALLAST ASSEMBLY, 100 WATT

This work shall be in accordance with the applicable Articles of Sections 821, 1065, 1066, 1067, and 1068 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall furnish and install a new 100-watt magnetic regulated ballast assembly in underpass luminaires that are not functioning after the installation of a new lamp and fuses.

- The ballast assembly for the Holophane underpass luminaires located along I-74 through Peoria and East Peoria shall be a manufacturer approved retrofit that has been designed for installation in a Holophane ballast tray. The assembly shall not require any drilling of the ballast tray or the installation of additional brackets and other components to secure the assembly to the tray. In order to minimize the repair time required in the field, the Department will supply three completely functional Holophane ballast trays to the Contractor. The Contractor shall utilize these trays for replacements in non-functioning luminaires. At the completion of the project, the Contractor shall return three fully functional ballast trays, complete with new ballast assemblies to the Department.
- The Contractor shall supply all required materials and perform all other work that is required for the replacement of the underpass luminaire ballast assembly and installation of the assembly in the underpass luminaire.
- The Contractor shall remove and dispose of failed components in accordance with the manufacturer's instructions and all applicable EPA regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for REPLACE UNDERPASS LUMINAIRE BALLAST ASSEMBLY, 100 WATT which price shall be payment in full for all labor, materials, and equipment required to pick up the ballast trays from the Department, retrofit new ballast assemblies in the ballast trays, install the ballast trays in non-functioning luminaires, and deliver the ballast trays complete with new ballast assemblies to the Department upon the completion of the project as described above.

MAINTAIN EXISTING LIGHTING CONTROLLER

This work shall be in accordance with the applicable Articles of Sections 825 and 1068 of the Standard Specifications.

The work shall consist of the following items:

- The Contractor shall thoroughly clean and vacuum all dust and debris from the lighting controller cabinet.
- The Contractor shall lubricate all hinges and locks.
- The Contractor shall install new silicone sealant around the controller cabinet base if needed to prevent water intrusion.
- The Contractor shall remove the existing door filter and furnish and install a new deluxe reinforced pleated filter of the correct size.
- The Contractor shall renew or install duct seal in all conduits to prevent rodent entry.
- The Contractor shall check all electrical connections for tightness.

- The Contractor shall thoroughly inspect all electrical service connections and ensure that the service conductors are secured tight in the circuit break lugs and electrical disconnect components. The contractor shall notify the Department of any deficiencies and note them on the inspection form.
- The Contractor shall inspect all circuit breakers, contactors, switches, photocells, and other components for damage and ensure proper operation of the manual and automatic operations of the Lighting Controller.
- The Contractor shall supply all required materials and perform all other work that is required to complete the work described above.
- The Contractor shall remove and dispose of failed components in accordance with all applicable regulations.
- All work shall be performed to the satisfaction of the Engineer.

The Contractor shall notify the Engineer of any damaged or deficient lighting controller components. The replacement of failed components will be considered extra work and shall be paid for in accordance with Article 109.04 of the Standard Specifications.

Basis of Payment: This work will be paid for at the contract unit price per Each for MAINTAIN EXISTING LIGHTING CONTROLLER which price shall be payment in full for all labor, materials, and equipment required to perform the lighting controller maintenance as described above.

CLEAN AND RELAMP EXISTING LUMINAIRE

This work shall be in accordance with the applicable Articles of Sections 821, 1065, 1066, 1067, and 1068 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall furnish and install a new 250-watt or 400-watt HPS non-cycling lamp (as required for the roadway luminaire). The luminaires are installed on light poles at the locations shown on the plan sheets.
- The Contractor shall clean the inside and outside of the luminaire lens.
- The Contractor shall remove and dispose of the existing lamp in accordance with the manufacturer's instructions and all applicable EPA regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for CLEAN AND RELAMP EXISTING LUMINAIRE which price shall be payment in full for all labor, materials, and equipment required to remove and dispose of the existing lamp, clean the luminaire lens, and install a new lamp in the roadway luminaire as described above.

REPLACE LUMINAIRE BALLAST ASSEMBLY

This work shall be in accordance with the applicable Articles of Sections 821, 1065, 1066, 1067, and 1068 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall furnish and install a new 250-volt or 400-volt 480-volt magnetic regulated ballast assembly in roadway luminaires that are not functioning after the installation of a new lamp and fuses.
- The luminaires are installed on light poles at the locations shown on the plan sheets.
- The Contractor shall supply all required materials and perform all other work that is required for the replacement of the tunnel luminaire ballast assembly and installation of the assembly in the tunnel luminaire.
- The Contractor shall remove and dispose of failed components in accordance with the manufacturer's instructions and all applicable EPA regulations.

Basis of Payment: This work will be paid for at the contract unit price per Each for REPLACE LUMINAIRE BALLAST ASSEMBLY which price shall be payment in full for all labor, materials, and equipment required to remove and dispose of the existing ballast, in the roadway luminaire as described above.

AVIATION OBSTRUCTION WARNING LUMINAIRE, LED

This work shall be in accordance with the applicable Articles of Sections 822 and 1067 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall remove the existing LED light.
- The Contractor shall furnish and install a new red LED warning beacon on the luminaire ring of a high mast light tower.
- The luminaires are installed on light towers at the locations shown on the plan sheets.
- The Contractor shall supply all required materials and perform all other work that is required for the replacement installation of the warning light.
- The Contractor shall remove and dispose of failed components in accordance with the manufacturer's instructions and all applicable EPA regulations.

The luminaire shall be a Carmanah model OL2A general purpose hazard marker (or approved equal) that conform to the following minimum specifications:

- Automatic dusk to dawn operation
- Optional external switch for easy activation and programming
- Field-proven durability
- Solar Panel High-efficiency cells with blocking diode function.
- Programming/Configuration Infrared programmer or external switch optional
- Battery Non-replaceable (average 5-year life)
- Light Source High power LED, Red
- Intensity Peak intensity 1.2 cd
- Flash Patterns 7
- Autonomy 300 hours (flashing) at full charge
- Construction Premium grade UV stabilized
- Temperature: -22°F to 122°F (-30°C to 50°C) operating and -40°F to 176°F (-40°C to 80°C) storage
- Weight 2.45 lbs. (1.1 kg)
- Energy Management System MICROSOURCE® code suite
- RoHS Compliant
- CE Approval As per EN 60945:1997
- IP 68 waterproof rating

Basis of Payment: This work will be paid for at the contract unit price per Each for AVIATION OBSTRUCTION WARNING LUMINAIRE, LED which price shall be payment in full for all labor, materials, and equipment required to remove and dispose of the existing aviation obstruction luminaire and furnish and install a new aviation obstruction luminaire on a light tower as described above.

HPS LAMP RECYCLING

The Contractor shall properly dispose of all HPS lamps through a certified waste company. The Contractor shall submit detailed information pertaining to lamp disposal to the Department for review along with the electrical material submittals. The Contractor shall submit proof of recycling to the Department.

Basis of Payment: This work will not be paid for separately but shall be included in the contract unit price for the HPS lamp replacement pay items.

HIGH MAST TOWER LOWERING DEVICE MOTOR (MATERIAL ONLY)

Description: This work shall consist of furnishing and delivering high mast tower lowering device motors to the IDOT Traffic Building at 1025 West Detweiller Drive, Peoria, Illinois.

Materials: The high mast tower lowering device motor shall be one of the following, or an approved equal:

- Lincoln Motors, SRF4S1.5TLCN1B6028 (Leeson General Purpose Motor)
- Milwaukee, 4262-1 (3/4" Motor for Electromagnetic Drill Press)

The motor shall meet or exceed the following specifications:

Nameplate Specifications

- Output HP: 1.50 hp
- Output KW: 1.1 kW
- Frequency: 60 Hz
- Voltage: 115/208-230 V
- Current: 15.2/8.2-7.6 A
- Speed: 1725 rpm
- Service Factor: 1.15
- Phase: 1
- Efficiency: 80%
- Duty: Continuous
- Insulation Class: B
- Design Code: N
- KVA Code: J
- Frame: 56C
- Enclosure: Totally Enclosed Fan Cooled
- Overload Protector: No
- Ambient Temperature: 40°C
- Drive End Bearing Size: 6203
- Opp Drive End Bearing Size: 6203
- UL: Recognized
- CSA: Yes
- CE: No
- IP Code: 43

Technical Specifications:

- Electrical Type: Capacitor Start Capacitor Run
- Starting Method: Across The Line
- Poles: 4
- Rotation: Selective Counterclockwise
- Mounting: Round
- Motor Orientation: Horizontal
- Drive End Bearing: Ball
- Opp Drive End Bearing: Ball
- Frame Material: Rolled Steel
- Shaft Type: NEMA 56

The Contractor shall verify that the proposed motor is compatible with and a direct retrofit (frame size, HP, voltage, wattage, etc.) for the existing motors that are installed in the light tower prior to ordering materials.

Basis of Payment: This work will be paid for at the contract unit price per Each for HIGH MAST TOWER LOWERING DEVICE MOTOR (MATERIAL ONLY) which price shall be payment in full for all labor, materials, and equipment required to deliver the lowering device motor to IDOT traffic building.

REPLACE BOLLARD LED LAMP

This work shall be in accordance with the applicable Articles of Sections 821, 1065, 1066, 1067, and 1068 of the Standard Specifications.

This work shall consist of the following items:

- The Contractor shall furnish and install a new 240V LED lamp (as required for the bollard luminaire.) The luminaires are installed on bollards at the locations shown on the plan sheets. The lamp shall meet the following specifications: Cool White (6500K color temperature), Medium Base, 240V, 360 degree and top illumination, 75 CRI, and 1200 lumens. The Contractor shall submit catalog cut sheets for the lamp to the Department for review and approval prior to ordering.
- The Contractor shall clean the inside and outside of the luminaire lens.
- The Contractor shall remove and dispose of the existing lamp in accordance with the manufacturer's instructions and all applicable EPA regulations.

The Contractor shall verify that the proposed LED lamp is compatible with and a direct retrofit for the existing LED lamps that are installed in the bollard light fixtures prior to ordering materials.

Basis of Payment: This work will be paid for at the contract unit price Each for REPLACE BOLLARD LED LAMP which price shall be payment in full for all labor, materials, equipment,

and traffic control required to remove and dispose of the existing lamp, clean the luminaire lens, and install a new lamp in the bollard luminaire as described above.

TOWER LIGHTING INSPECTION AND MAINTENANCE CHECKSHEET

The Tower Lighting Inspection and Maintenance Checksheet needs to be included with these special provisions to be completed by the Contractor and submitted to the Resident Engineer. (See next page.)

Tower Lighting Inspection and Maintenance Checksheet			
District: Four	County:	Route:	Milepost:
Location:			
Date of Inspection:	Inspected by:	Method of Inspection:	
Inspectors:			
Pole Manufacturer:	Pole ID:	Location ID:	
Pole Height: Ft.	Year Installed:	Station:	

Pole Inspection	Comments
<input type="checkbox"/> Inspect pole for cracks, corrosion, and damage.	
<input type="checkbox"/> Inspect screening around pole base. Adjust or repair as needed to prevent rodent entry.	
<input type="checkbox"/> Remove all debris or rodent droppings from inside of pole.	
<input type="checkbox"/> Lubricate door hinges.	
<input type="checkbox"/> Adjust door clamps to ensure a tight even seal.	
<input type="checkbox"/> Inspect rubber door seal. Secure rubber seal with adhesive if needed.	
<input type="checkbox"/> Inspect anchor bolts. Check nuts for tightness.	
<input type="checkbox"/> Inspect concrete foundation. Check for cracks or spalling.	
<input type="checkbox"/> Inspect pole finish. Note any major paint issues.	

Additional Comments:

Lowering Device (check before lowering ring)	Comments
<input type="checkbox"/> Inspect padlocks and lubricate.	
<input type="checkbox"/> Inspect power cord for wear and damage. Check power cord caps.	
<input type="checkbox"/> Inspect winch assembly and lubricate.	
<input type="checkbox"/> Inspect winch cable for wear and damage. If cable has more than 12 broken wires in one lay of cord, the cable needs to be replaced. Cable replacement will be paid for separately.	
<input type="checkbox"/> Clean cable with a soft absorbent cloth and lubricate cable with good quality acid free grease.	
<input type="checkbox"/> Inspect pole base electrical junction box (on door) and check connections for tightness. Tighten connections if needed.	
<input type="checkbox"/> Inspection transition assembly for wear and damage.	

Additional Comments:

Lighting Ring		Comments
<input type="checkbox"/>	Inspect ring and ring components for wear and damage. Check to see if ring is level.	
<input type="checkbox"/>	Lubricate moving parts on the ring.	
<input type="checkbox"/>	Inspect hoist and support cables for wear and damage. Check Kellum grips if equipped.	
<input type="checkbox"/>	Inspect electrical cables for wear and damage.	
<input type="checkbox"/>	Inspect electrical connectors and connections for wear or damage. Tighten any loose connections.	
<input type="checkbox"/>	Inspect electrical junction boxes for water and damage. Seal with silicone sealant if needed.	
Additional Comments:		
Luminaires		Comments
<input type="checkbox"/>	Replace lamp with new non-cycling lamp (this item will be paid for separately under a different pay item).	
<input type="checkbox"/>	Inspect luminaire ballasts, starters, and fuses. Repair and replace as needed (this item will be paid for separately under a different pay item).	
<input type="checkbox"/>	Clean luminaire refractor.	
<input type="checkbox"/>	Clean luminaire lens on the inside and outside.	
<input type="checkbox"/>	Inspect shield for damage. Re-align, tighten, and re-attach loose shields in accordance with manufacturer's instructions (Contractor to provide all materials required).	
Additional Comments:		
Lowering Device (inspect after raising ring)		Comments
<input type="checkbox"/>	Lubricate turnbuckle. Tighten until tightening ring is secure against stops.	
<input type="checkbox"/>	Tension cable in accordance with manufacturer's instructions. Note if cable does not tension according to specifications.	
<input type="checkbox"/>	Attach winch cable safety mechanism.	
Additional Comments:		
Inspector's Signature:		Date of Inspection:

CEMENT, TYPE IL (BDE)

Effective: August 1, 2023

Add the following to Article 302.02 of the Standard Specifications:

“(k) Type IL Portland-Limestone Cement1001”

Revise Note 2 of Article 352.02 of the Standard Specifications to read:

“Note 2. Either Type I or Type IA portland cement or Type IL portland-limestone cement shall be used.”

Revise Note 1 of Article 404.02 of the Standard Specifications to read:

“Note 1. The cement shall be Type I portland cement or Type IL portland-limestone cement.”

Revise Article 1019.02(a) of the Standard Specifications to read:

“(a) Cement, Type I or IL1001”

COMPENSABLE DELAY COSTS (BDE)

Effective: June 2, 2017

Revised: April 1, 2019

Revise Article 107.40(b) of the Standard Specifications to read:

“(b) Compensation. Compensation will not be allowed for delays, inconveniences, or damages sustained by the Contractor from conflicts with facilities not meeting the above definition; or if a conflict with a utility in an unanticipated location does not cause a shutdown of the work or a documentable reduction in the rate of progress exceeding the limits set herein. The provisions of Article 104.03 notwithstanding, compensation for delays caused by a utility in an unanticipated location will be paid according to the provisions of this Article governing minor and major delays or reduced rate of production which are defined as follows.

- (1) Minor Delay. A minor delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two hours, but not to exceed two weeks.
- (2) Major Delay. A major delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two weeks.
- (3) Reduced Rate of Production Delay. A reduced rate of production delay occurs when the rate of production on the work in conflict with the utility in an unanticipated location decreases by more than 25 percent and lasts longer than seven calendar days.”

Revise Article 107.40(c) of the Standard Specifications to read:

“(c) Payment. Payment for Minor, Major, and Reduced Rate of Production Delays will be made as follows.

- (1) Minor Delay. Labor idled which cannot be used on other work will be paid for according to Article 109.04(b)(1) and (2) for the time between start of the delay and the minimum remaining hours in the work shift required by the prevailing practice in the area.

Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4).

- (2) Major Delay. Labor will be the same as for a minor delay.

Equipment will be the same as for a minor delay, except Contractor-owned equipment will be limited to two weeks plus the cost of move-out to either the Contractor’s yard or another job and the cost to re-mobilize, whichever is less. Rental equipment may be paid for longer than two weeks provided the Contractor presents adequate support to the Department (including lease agreement) to show retaining equipment on the job is the most economical course to follow and in the public interest.

- (3) Reduced Rate of Production Delay. The Contractor will be compensated for the reduced productivity for labor and equipment time in excess of the 25 percent threshold for that portion of the delay in excess of seven calendar days. Determination of compensation will be in accordance with Article 104.02, except labor and material additives will not be permitted.

Payment for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be determined according to Article 109.13.”

Revise Article 108.04(b) of the Standard Specifications to read:

“(b) No working day will be charged under the following conditions.

- (1) When adverse weather prevents work on the controlling item.
- (2) When job conditions due to recent weather prevent work on the controlling item.
- (3) When conduct or lack of conduct by the Department or its consultants, representatives, officers, agents, or employees; delay by the Department in making the site available; or delay in furnishing any items required to be furnished to the Contractor by the Department prevents work on the controlling item.
- (4) When delays caused by utility or railroad adjustments prevent work on the controlling item.

- (5) When strikes, lock-outs, extraordinary delays in transportation, or inability to procure critical materials prevent work on the controlling item, as long as these delays are not due to any fault of the Contractor.
- (6) When any condition over which the Contractor has no control prevents work on the controlling item.”

Revise Article 109.09(f) of the Standard Specifications to read:

“(f) Basis of Payment. After resolution of a claim in favor of the Contractor, any adjustment in time required for the work will be made according to Section 108. Any adjustment in the costs to be paid will be made for direct labor, direct materials, direct equipment, direct jobsite overhead, direct offsite overhead, and other direct costs allowed by the resolution. Adjustments in costs will not be made for interest charges, loss of anticipated profit, undocumented loss of efficiency, home office overhead and unabsorbed overhead other than as allowed by Article 109.13, lost opportunity, preparation of claim expenses and other consequential indirect costs regardless of method of calculation.

The above Basis of Payment is an essential element of the contract and the claim cost recovery of the Contractor shall be so limited.”

Add the following to Section 109 of the Standard Specifications.

“**109.13 Payment for Contract Delay.** Compensation for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be allowed when such costs result from a delay meeting the criteria in the following table.

Contract Type	Cause of Delay	Length of Delay
Working Days	Article 108.04(b)(3) or Article 108.04(b)(4)	No working days have been charged for two consecutive weeks.
Completion Date	Article 108.08(b)(1) or Article 108.08(b)(7)	The Contractor has been granted a minimum two week extension of contract time, according to Article 108.08.

Payment for each of the various costs will be according to the following.

- (a) Escalated Material and/or Labor Costs. When the delay causes work, which would have otherwise been completed, to be done after material and/or labor costs have increased, such increases will be paid. Payment for escalated material costs will be limited to the increased costs substantiated by documentation furnished by the Contractor. Payment for escalated labor costs will be limited to those items in Article 109.04(b)(1) and (2), except the 35 percent and 10 percent additives will not be permitted.

(b) Extended Project Overhead. For the duration of the delay, payment for extended project overhead will be paid as follows.

(1) Direct Jobsite and Offsite Overhead. Payment for documented direct jobsite overhead and documented direct offsite overhead, including onsite supervisory and administrative personnel, will be allowed according to the following table.

Original Contract Amount	Supervisory and Administrative Personnel
Up to \$5,000,000	One Project Superintendent
Over \$ 5,000,000 - up to \$25,000,000	One Project Manager, One Project Superintendent or Engineer, and One Clerk
Over \$25,000,000 - up to \$50,000,000	One Project Manager, One Project Superintendent, One Engineer, and One Clerk
Over \$50,000,000	One Project Manager, Two Project Superintendents, One Engineer, and One Clerk

(2) Home Office and Unabsorbed Overhead. Payment for home office and unabsorbed overhead will be calculated as 8 percent of the total delay cost.

(c) Extended Traffic Control. Traffic control required for an extended period of time due to the delay will be paid for according to Article 109.04.

When an extended traffic control adjustment is paid under this provision, an adjusted unit price as provided for in Article 701.20(a) for increase or decrease in the value of work by more than ten percent will not be paid.

Upon payment for a contract delay under this provision, the Contractor shall assign subrogation rights to the Department for the Department's efforts of recovery from any other party for monies paid by the Department as a result of any claim under this provision. The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this provision."

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)

Effective: September 1, 2000

Revised: March 2, 2019

FEDERAL OBLIGATION. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR Part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise

(DBE) means a business certified by the Department in accordance with the requirements of 49 CFR Part 26 and listed in the Illinois Unified Certification Program (IL UCP) DBE Directory.

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

CONTRACTOR ASSURANCE. The Contractor makes the following assurance and agrees to include the assurance in each subcontract the Contractor signs with a subcontractor.

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

- (a) Withholding progress payments;
- (b) Assessing sanctions;
- (c) Liquidated damages; and/or
- (d) Disqualifying the Contractor from future bidding as non-responsible.

OVERALL GOAL SET FOR THE DEPARTMENT. As a requirement of compliance with 49 CFR Part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE companies performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. The determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates, in the absence of unlawful discrimination and in an arena of fair and open competition, DBE companies can be expected to perform 0.00% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will only award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for

award consideration if either of the following is done in accordance with the procedures set for in this Special Provision:

- (a) The bidder documents enough DBE participation has been obtained to meet the goal or,
- (b) The bidder documents a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

DBE LOCATOR REFERENCES. Bidders shall consult the IL UCP DBE Directory as a reference source for DBE-certified companies. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217) 785-4611, or by visiting the Department's website at: <http://www.idot.illinois.gov/doing-business/certifications/disadvantaged-business-enterprise-certification/il-ucp-directory/index>.

BIDDING PROCEDURES. Compliance with this Special Provision is a material bidding requirement and failure of the bidder to comply will render the bid not responsive.

The bidder shall submit a DBE Utilization Plan (form SBE 2026), and a DBE Participation Statement (form SBE 2025) for each DBE company proposed for the performance of work to achieve the contract goal, with the bid. If the Utilization Plan indicates the contract goal will not be met, documentation of good faith efforts shall also be submitted. The documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor is selected over a DBE for work on the contract. The required forms and documentation must be submitted as a single .pdf file using the "Integrated Contractor Exchange (iCX)" application within the Department's "EBids System".

The Department will not accept a Utilization Plan if it does not meet the bidding procedures set forth herein and the bid will be declared not responsive. In the event the bid is declared not responsive, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty and may deny authorization to bid the project if re-advertised for bids.

GOOD FAITH EFFORT PROCEDURES. The contract will not be awarded until the Utilization Plan is approved. All information submitted by the bidder must be complete, accurate and adequately document enough DBE participation has been obtained or document the good faith efforts of the bidder, in the event enough DBE participation has not been obtained, before the Department will commit to the performance of the contract by the bidder. The Utilization Plan will be approved by the Department if the Utilization Plan documents sufficient commercially useful DBE work to meet the contract goal or the bidder submits sufficient documentation of a good faith effort to meet the contract goal pursuant to 49 CFR Part 26, Appendix A. This means the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which, by their scope, intensity and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not successful. The Department will consider the quality, quantity, and intensity of the kinds of efforts the bidder has made. Mere *pro forma* efforts, in other words efforts done as a matter of form, are not good faith efforts; rather, the bidder is expected to have taken genuine efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

- (a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases and will be considered by the Department.
- (1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.
 - (2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the Contractor might otherwise prefer to perform these work items with its own forces.
 - (3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.
 - (4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.

b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also the ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable. In accordance with the above Bidding Procedures, the documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract.
 - (5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not

legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.

- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
 - (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
 - (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.
- (b) If the Department determines the bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided it is otherwise eligible for award. If the Department determines the bidder has failed to meet the requirements of this Special Provision or that a good faith effort has not been made, the Department will notify the responsible company official designated in the Utilization Plan that the bid is not responsive. The notification will also include a statement of reasons for the adverse determination. If the Utilization Plan is not approved because it is deficient as a technical matter, unless waived by the Department, the bidder will be notified and will be allowed no more than a five calendar day period to cure the deficiency.
- (c) The bidder may request administrative reconsideration of an adverse determination by emailing the Department at "DOT.DBE.UP@illinois.gov" within the five calendar days after the receipt of the notification of the determination. The determination shall become final if a request is not made on or before the fifth calendar day. A request may provide additional written documentation or argument concerning the issues raised in the determination statement of reasons, provided the documentation and arguments address efforts made prior to submitting the bid. The request will be reviewed by the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person to consider all issues of documentation and whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

CALCULATING DBE PARTICIPATION. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR Part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines

are provided in 49 CFR Part 26.55, the provisions of which govern over the summary contained herein.

- (a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE does not count toward the DBE goals.
- (b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.
- (c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE does not count toward the DBE goal.
- (d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contract. Credit will be given for the following:
 - (1) The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.
 - (2) The DBE may also lease trucks from a non-DBE firm, including from an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement.
- (e) DBE as a material supplier:
 - (1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.
 - (2) 100 percent goal credit for the cost of materials or supplies obtained from a DBE manufacturer.
 - (3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a DBE regular dealer or DBE manufacturer.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Utilization Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and

contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal. All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the DBE Participation Commitment Statement.

- (a) NO AMENDMENT. No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be emailed to the Department at DOT.DBE.UP@illinois.gov.
- (b) CHANGES TO WORK. Any deviation from the DBE condition-of-award or contract plans, specifications, or special provisions must be approved, in writing, by the Department as provided elsewhere in the Contract. The Contractor shall notify affected DBEs in writing of any changes in the scope of work which result in a reduction in the dollar amount condition-of-award to the contract. Where the revision includes work committed to a new DBE subcontractor, not previously involved in the project, then a Request for Approval of Subcontractor, Department form BC 260A or AER 260A, must be signed and submitted. If the commitment of work is in the form of additional tasks assigned to an existing subcontract, a new Request for Approval of Subcontractor will not be required. However, the Contractor must document efforts to assure the existing DBE subcontractor is capable of performing the additional work and has agreed in writing to the change.
- (c) SUBCONTRACT. The Contractor must provide copies of DBE subcontracts to the Department upon request. Subcontractors shall ensure that all lower tier subcontracts or agreements with DBEs to supply labor or materials be performed in accordance with this Special Provision.
- (d) ALTERNATIVE WORK METHODS. In addition to the above requirements for reductions in the condition of award, additional requirements apply to the two cases of Contractor-initiated work substitution proposals. Where the contract allows alternate work methods which serve to delete or create underruns in condition of award DBE work, and the Contractor selects that alternate method or, where the Contractor proposes a substitute work method or material that serves to diminish or delete work committed to a DBE and replace it with other work, then the Contractor must demonstrate one of the following:
 - (1) The replacement work will be performed by the same DBE (as long as the DBE is certified in the respective item of work) in a modification of the condition of award; or
 - (2) The DBE is aware its work will be deleted or will experience underruns and has agreed in writing to the change. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so; or
 - (3) The DBE is not capable of performing the replacement work or has declined to perform the work at a reasonable competitive price. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so.
- (e) TERMINATION AND REPLACEMENT PROCEDURES. The Contractor shall not terminate or replace a DBE listed on the approved Utilization Plan, or perform with other

forces work designated for a listed DBE except as provided in this Special Provision. The Contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the Contractor obtains the Department's written consent as provided in subsection (a) of this part. Unless Department consent is provided for termination of a DBE subcontractor, the Contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the DBE in the Utilization Plan.

As stated above, the Contractor shall not terminate or replace a DBE subcontractor listed in the approved Utilization Plan without prior written consent. This includes, but is not limited to, instances in which the Contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm. Written consent will be granted only if the Bureau of Small Business Enterprises agrees, for reasons stated in its concurrence document, that the Contractor has good cause to terminate or replace the DBE firm. Before transmitting to the Bureau of Small Business Enterprises any request to terminate and/or substitute a DBE subcontractor, the Contractor shall give notice in writing to the DBE subcontractor, with a copy to the Bureau, of its intent to request to terminate and/or substitute, and the reason for the request. The Contractor shall give the DBE five days to respond to the Contractor's notice. The DBE so notified shall advise the Bureau and the Contractor of the reasons, if any, why it objects to the proposed termination of its subcontract and why the Bureau should not approve the Contractor's action. If required in a particular case as a matter of public necessity, the Bureau may provide a response period shorter than five days.

For purposes of this paragraph, good cause includes the following circumstances:

- (1) The listed DBE subcontractor fails or refuses to execute a written contract;
- (2) The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent with normal industry standards. Provided, however, that good cause does not exist if the failure or refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or discriminatory action of the Contractor;
- (3) The listed DBE subcontractor fails or refuses to meet the Contractor's reasonable, nondiscriminatory bond requirements;
- (4) The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness;
- (5) The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215 and 1200 or applicable state law.
- (6) The Contractor has determined the listed DBE subcontractor is not a responsible contractor;
- (7) The listed DBE subcontractor voluntarily withdraws from the projects and provides written notice to the Contractor of its withdrawal;
- (8) The listed DBE is ineligible to receive DBE credit for the type of work required;

- (9) A DBE owner dies or becomes disabled with the result that the listed DBE subcontractor is unable to complete its work on the contract;

- (10) Other documented good cause that compels the termination of the DBE subcontractor. Provided, that good cause does not exist if the Contractor seeks to terminate a DBE it relied upon to obtain the contract so that the Contractor can self-perform the work for which the DBE contractor was engaged or so that the Contractor can substitute another DBE or non-DBE contractor after contract award.

When a DBE is terminated or fails to complete its work on the Contract for any reason, the Contractor shall make a good faith effort to find another DBE to substitute for the original DBE to perform at least the same amount of work under the contract as the terminated DBE to the extent needed to meet the established Contract goal. The good faith efforts shall be documented by the Contractor. If the Department requests documentation under this provision, the Contractor shall submit the documentation within seven days, which may be extended for an additional seven days if necessary at the request of the Contractor. The Department will provide a written determination to the Contractor stating whether or not good faith efforts have been demonstrated.

- (f) FINAL PAYMENT. After the performance of the final item of work or delivery of material by a DBE and final payment therefore to the DBE by the Contractor, but not later than 30 calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Agreement on Department form SBE 2115 to the Resident Engineer. If full and final payment has not been made to the DBE, the DBE Payment Agreement shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Utilization Plan and after good faith efforts are reviewed, the Department may deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages. The Contractor may request an administrative reconsideration of any amount deducted as damages pursuant to subsection (h) of this part.
- (g) ENFORCEMENT. The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.
- (h) RECONSIDERATION. Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor may request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department. The result of the reconsideration process is not administratively appealable to the U.S. Department of Transportation.

ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)

Effective: June 2, 2021

Revised: April 2, 2024

Illinois Works Jobs Program Act (30 ILCS 559/20-1 et seq.). For contracts having an awarded contract value of \$500,000 or more, the Contractor shall comply with the Illinois Works Apprenticeship Initiative (30 ILCS 559/20-20 to 20-25) and all applicable administrative rules. The goal of the Illinois Apprenticeship Works Initiative is that apprentices will perform either 10% of the total labor hours actually worked in each prevailing wage classification or 10% of the estimated labor hours in each prevailing wage classification, whichever is less. Of this goal, at least 50% of the labor hours of each prevailing wage classification performed by apprentices shall be performed by graduates of the Illinois Works Pre-Apprenticeship Program, the Illinois Climate Works Pre-Apprenticeship Program, or the Highway Construction Careers Training Program.

The Contractor may seek from the Department of Commerce and Economic Opportunity (DCEO) a waiver or reduction of this goal in certain circumstances pursuant to 30 ILCS 559/20-20(b). The Contractor shall ensure compliance during the term of the contract and will be required to report on and certify its compliance. An apprentice use plan, apprentice hours, and a compliance certification shall be submitted to the Engineer on forms provided by the Department and/or DCEO.

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)

Effective: January 1, 2024

Revised: April 1, 2024

Revise the first paragraph of Article 669.04 of the Standard Specifications to read:

“669.04 Regulated Substances Monitoring. Regulated substances monitoring includes environmental observation and field screening during regulated substances management activities. The excavated soil and groundwater within the work areas shall be managed as either uncontaminated soil, hazardous waste, special waste, or non-special waste.

As part of the regulated substances monitoring, the monitoring personnel shall perform and document the applicable duties listed on form BDE 2732 “Regulated Substances Monitoring Daily Record (RSMDR)”.

Revise the first two sentences of the nineteenth paragraph of Article 669.05 of the Standard Specifications to read:

“The Contractor shall coordinate waste disposal approvals with the disposal facility and provide the specific analytical testing requirements of that facility. The Contractor shall make all arrangements for collection, transportation, and analysis of landfill acceptance testing.”

Revise the last paragraph of Article 669.05 of the Standard Specifications to read:

“The Contractor shall select a permitted landfill facility or CCDD/USFO facility meeting the requirements of 35 Ill. Admin. Code Parts 810-814 or Part 1100, respectively. The Department will review and approve or reject the facility proposed by the Contractor based upon information provided in BDE 2730. The Contractor shall verify whether the selected facility is compliant with those applicable standards as mandated by their permit and whether the facility is presently, has previously been, or has never been, on the United States Environmental Protection Agency (U.S. EPA) National Priorities List or the Resource Conservation and Recovery Act (RCRA) List of Violating Facilities. The use of a Contractor selected facility shall in no manner delay the construction schedule or alter the Contractor's responsibilities as set forth.”

Revise the first paragraph of Article 669.07 of the Standard Specifications to read:

“**669.07 Temporary Staging.** Soil classified according to Articles 669.05(a)(2), (b)(1), or (c) may be temporarily staged at the Contractor's option. All other soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) shall be managed and disposed of without temporary staging to the greatest extent practicable. If circumstances beyond the Contractor's control require temporary staging of these latter materials, the Contractor shall request approval from the Engineer in writing.

Topsoil for re-use as final cover which has been field screened and found not to exhibit PID readings over daily background readings as documented on the BDE 2732, visual staining or odors, and is classified according to Articles 669.05(a)(2), (a)(3), (a)(4), (b)(1), or (c) may be temporarily staged at the Contractor's option.”

Add the following paragraph after the sixth paragraph of Article 669.11 of the Standard Specifications.

“The sampling and testing of effluent water derived from dewatering discharges for priority pollutants volatile organic compounds (VOCs), priority pollutants semi-volatile organic compounds (SVOCs), or priority pollutants metals, will be paid for at the contract unit price per each for VOCS GROUNDWATER ANALYSIS using EPA Method 8260B, SVOCs GROUNDWATER ANALYSIS using EPA Method 8270C, or RCRA METALS GROUNDWATER ANALYSIS using EPA Methods 6010B and 7471A. This price shall include transporting the sample from the job site to the laboratory.”

Revise the first sentence of the eight paragraph of Article 669.11 of the Standard Specifications to read:

“Payment for temporary staging of soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) to be managed and disposed of, if required and approved by the Engineer, will be paid according to Article 109.04.”

SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)

Effective: April 1, 2024

Revised: April 2, 2024

Revise Article 701.02(d) of the Standard Specifications to read:

“(d) Pavement Marking Tapes (Note 3)1095.06”

Add the following Note to the end of Article 701.02 of the Standard Specifications:

“Note 3. White or yellow pavement marking tape that is to remain in place longer than 14 days shall be Type IV tape.”

Revise Article 703.02(c) of the Standard Specifications to read:

“(c) Pavement Marking Tapes (Note 1)1095.06”

Add the following Note to the end of Article 703.02 of the Standard Specifications:

“Note 1. White or yellow pavement marking tape that is to remain in place longer than 14 days shall be Type IV tape.”

Revise Article 1095.06 of the Standard Specifications to read:

1095.06 Pavement Marking Tapes. Type I white or yellow marking tape shall consist of glass spheres embedded into a binder on a foil backing that is precoated with a pressure sensitive adhesive. The spheres shall be of uniform gradation and distributed evenly over the surface of the tape.

Type IV tape shall consist of white or yellow tape with wet reflective media incorporated to provide immediate and continuing retroreflection in wet and dry conditions. The wet retroreflective media shall be bonded to a durable polyurethane surface. The patterned surface shall have approximately 40 ± 10 percent of the surface area raised and presenting a near vertical face to traffic from any direction. The channels between the raised areas shall be substantially free of exposed reflective elements or particles.

Blackout tape shall consist of a matte black, non-reflective, patterned surface that is precoated with a pressure sensitive adhesive.

(a) Color. The white and yellow markings shall meet the following requirements for daylight reflectance and color, when tested, using a color spectrophotometer with 45 degrees circumferential/zero degree geometry, illuminant D65, and two degree observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm.

Color	Daylight Reflectance %Y
White	65 min.
Yellow *	36 - 59

*Shall match Aerospace Material Specification Standard 595 33538 (Orange Yellow) and the chromaticity limits as follows.

x	0.490	0.475	0.485	0.530
y	0.470	0.438	0.425	0.456

- (b) Retroreflectivity. The white and yellow markings shall be retroreflective. Reflective values measured in accordance with the photometric testing procedure of ASTM D 4061 shall not be less than those listed in the table below. The coefficient of retroreflected luminance, R_L , shall be expressed as average millicandelas/footcandle/sq ft (millicandelas/lux/sq m), measured on a 3.0 x 0.5 ft (900 mm x 150 mm) panel at 86 degree entrance angle.

Coefficient of Retroreflected Luminance, R_L , Dry					
Type I			Type IV		
Observation Angle	White	Yellow	Observation Angle	White	Yellow
0.2°	2700	2400	0.2°	1300	1200
0.5°	2250	2000	0.5°	1100	1000

Wet retroreflectance shall be measured for Type IV under wet conditions according to ASTM E 2177 and meet the following.

Wet Retroreflectance, Initial R_L	
Color	R_L 1.05/88.76
White	300
Yellow	200

- (c) Skid Resistance. The surface of Type IV and blackout markings shall provide a minimum skid resistance of 45 BPN when tested according to ASTM E 303.
- (d) Application. The pavement marking tape shall have a precoated pressure sensitive adhesive and shall require no activation procedures. Test pieces of the tape shall be applied according to the manufacturer's instructions and tested according to ASTM D 1000, Method A, except that a stiff, short bristle roller brush and heavy hand pressure will be substituted for the weighted rubber roller in applying the test pieces to the metal test panel. Material tested as directed above shall show a minimum adhesion value of 750 g/in. (30 g/mm) width at the temperatures specified in ASTM D 1000. The adhesive shall be resistant to oils, acids, solvents, and water, and shall not leave objectionable stains or residue after removal. The material shall be flexible and conformable to the texture of the pavement.
- (e) Durability. Type IV and blackout tape shall be capable of performing for the duration of a normal construction season and shall then be capable of being removed intact or in large sections at pavement temperatures above 40 °F (4 °C) either manually or with a roll-up device without the use of sandblasting, solvents, or grinding. The Contractor shall provide a manufacturer's certification that the material meets the requirements for being removed after the following minimum traffic exposure based on transverse test decks with rolling traffic.

- (1) Time in place - 400 days
- (2) ADT per lane - 9,000 (28 percent trucks)
- (3) Axle hits - 10,000,000 minimum

Samples of the material applied to standard specimen plates will be measured for thickness and tested for durability in accordance with ASTM D 4060, using a CS-17 wheel and 1000-gram load, and shall meet the following criteria showing no significant change in color after being tested for the number of cycles indicated.

Test	Type I	Type IV	Blackout
Minimum Initial Thickness, mils (mm)	20 (0.51)	65 (1.65) ^{1/} 20 (0.51) ^{2/}	65 (1.65) ^{1/} 20 (0.51) ^{2/}
Durability (cycles)	5,000	1,500	1,500

- 1/ Measured at the thickest point of the patterned surface.
- 2/ Measured at the thinnest point of the patterned surface.

The pavement marking tape, when applied according to the manufacturer's recommended procedures, shall be weather resistant and shall show no appreciable fading, lifting, or shrinkage during the useful life of the marking. The tape, as applied, shall be of good appearance, free of cracks, and edges shall be true, straight, and unbroken.

(f) Sampling and Inspection.

- (1) Sample. Prior to approval and use of Type IV pavement marking tape, the manufacturer shall submit a notarized certification from an independent laboratory, together with the results of all tests, stating that the material meets the requirements as set forth herein. The independent laboratory test report shall state the lot tested, the manufacturer's name, and the date of manufacture.

After initial approval by the Department, samples and certification by the manufacturer shall be submitted for each subsequent batch of Type IV tape used. The manufacturer shall submit a certification stating that the material meets the requirements as set forth herein and is essentially identical to the material sent for qualification. The certification shall state the lot tested, the manufacturer's name, and the date of manufacture.

- (2) Inspection. The Contractor shall provide a manufacturer's certification to the Engineer stating the material meets all requirements of this specification. All material samples for acceptance tests shall be taken or witnessed by a representative of the Bureau of Materials and shall be submitted to the Engineer of Materials, 126 East Ash Street, Springfield, Illinois 62704-4766 at least 30 days in advance of the pavement marking operations."

SPEED DISPLAY TRAILER (BDE)

Effective: April 2, 2014

Revised: January 1, 2022

Revise the last paragraph of Article 701.11 of the Standard Specifications to read:

“When not being utilized to inform and direct traffic, sign trailers, speed display trailers, arrow boards, and portable changeable message boards shall be treated as nonoperating equipment.”

Add the following to Article 701.15 of the Standard Specifications:

“(m) Speed Display Trailer. A speed display trailer is used to enhance safety of the traveling public and workers in work zones by alerting drivers of their speed, thus deterring them from driving above the posted work zone speed limit.”

Add the following to Article 701.20 of the Standard Specifications:

“(k) When speed display trailers are shown on the Standard, this work will not be paid for separately but shall be considered as included in the cost of the Standard.

For all other speed display trailers, this work will be paid for at the contract unit price per calendar month or fraction thereof for each trailer as SPEED DISPLAY TRAILER.”

Add the following to Article 1106.02 of the Standard Specifications:

“(o) Speed Display Trailer. The speed display trailer shall consist of a LED speed indicator display with self-contained, one-direction radar mounted on an orange see-through trailer. The height of the display and radar shall be such that it will function and be visible when located behind concrete barrier.

The speed measurement shall be by radar and provide a minimum detection distance of 1000 ft (300 m). The radar shall have an accuracy of ± 1 mile per hour.

The speed indicator display shall face approaching traffic and shall have a sign legend of “YOUR SPEED” immediately above or below the speed display. The sign letters shall be between 5 and 8 in. (125 and 200 mm) in height. The digital speed display shall show two digits (00 to 99) in mph. The color of the changeable message legend shall be a yellow legend on a black background. The minimum height of the numerals shall be 18 in. (450 mm), and the nominal legibility distance shall be at least 750 ft (250 m).

The speed indicator display shall be equipped with a violation alert that flashes the displayed detected speed when the work zone posted speed limit is exceeded. The speed indicator shall have a maximum speed cutoff. On roadway facilities with a normal posted speed limit greater than or equal to 45 mph, the detected speeds of vehicles traveling more than 25 mph over the work zone speed limit shall not be displayed. On facilities with normal posted speed limit of less than 45 mph, the detected speeds of vehicles traveling more than 15 mph over the work zone speeds limit shall not be displayed. On any roadway facility if detected speeds are less than 25 mph, they shall not be displayed. The display shall include automatic dimming for nighttime operation.

The speed indicator measurement and display functions shall be equipped with the power supply capable of providing 24 hours of uninterrupted service.”

SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)

Effective: April 2, 2018

Add the following to Section 109 of the Standard Specifications.

“109.14 Subcontractor and Disadvantaged Business Enterprise Payment Reporting.
 The Contractor shall report all payments made to the following parties:

- (a) first tier subcontractors;
- (b) lower tier subcontractors affecting disadvantaged business enterprise (DBE) goal credit;
- (c) material suppliers or trucking firms that are part of the Contractor’s submitted DBE utilization plan.

The report shall be made through the Department’s on-line subcontractor payment reporting system within 21 days of making the payment.”

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)

Effective: November 2, 2017

Revised: April 1, 2019

Replace the second paragraph of Article 109.12 of the Standard Specifications with the following:

“This mobilization payment shall be made at least seven days prior to the subcontractor starting work. The amount paid shall be at the following percentage of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor’s work.

Value of Subcontract Reported on Form BC 260A	Mobilization Percentage
Less than \$10,000	25%
\$10,000 to less than \$20,000	20%
\$20,000 to less than \$40,000	18%
\$40,000 to less than \$60,000	16%
\$60,000 to less than \$80,000	14%
\$80,000 to less than \$100,000	12%
\$100,000 to less than \$250,000	10%
\$250,000 to less than \$500,000	9%
\$500,000 to \$750,000	8%
Over \$750,000	7%”

SUBMISSION OF PAYROLL RECORDS (BDE)

Effective: April 1, 2021

Revised: November 2, 2023

FEDERAL AID CONTRACTS. Revise the following section of Check Sheet #1 of the Recurring Special Provisions to read:

“STATEMENTS AND PAYROLLS

The payroll records shall include the worker’s name, social security number, last known address, telephone number, email address, classification(s) of work actually performed, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof), daily and weekly number of hours actually worked in total, deductions made, and actual wages paid.

The Contractor and each subcontractor shall submit certified payroll records to the Department each week from the start to the completion of their respective work, except that full social security numbers, last known addresses, telephone numbers, and email addresses shall not be included on weekly submittals. Instead, the payrolls need only include an identification number for each employee (e.g., the last four digits of the employee’s social security number). The submittals shall be made using LCPTracker Pro software. The software is web-based and can be accessed at <https://lcptracker.com/>. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate option (“No Work”, “Suspended”, or “Complete”) selected.”

STATE CONTRACTS. Revise Item 3 of Section IV of Check Sheet #5 of the Recurring Special Provisions to read:

- “3. Submission of Payroll Records. The Contractor and each subcontractor shall, no later than the 15th day of each calendar month, file a certified payroll for the immediately preceding month to the Illinois Department of Labor (IDOL) through the Illinois Prevailing Wage Portal in compliance with the State Prevailing Wage Act (820 ILCS 130). The portal can be found on the IDOL website at <https://www2.illinois.gov/idol/Laws-Rules/CONMED/Pages/Prevailing-Wage-Portal.aspx>. Payrolls shall be submitted in the format prescribed by the IDOL.

In addition to filing certified payroll(s) with the IDOL, the Contractor and each subcontractor shall certify and submit payroll records to the Department each week from the start to the completion of their respective work, except that full social security numbers shall not be included on weekly submittals. Instead, the payrolls shall include an identification number for each employee (e.g., the last four digits of the employee’s social security number). In addition, starting and ending times of work each day may be omitted from the payroll records submitted. The submittals shall be made using LCPTracker Pro software. The software is web-based and can be accessed at <https://lcptracker.com/>. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate option (“No Work”, “Suspended”, or “Complete”) selected.”

TRAFFIC SPOTTERS (BDE)

Effective: January 1, 2019

Revise Article 701.13 of the Standard Specifications to read:

“701.13 Flaggers and Spotters. Flaggers shall be certified by an agency approved by the Department. While on the job site, each flagger shall have in his/her possession a current driver’s license and a current flagger certification I.D. card. For non-drivers, the Illinois Identification Card issued by the Secretary of State will meet the requirement for a current driver’s license. This certification requirement may be waived by the Engineer for emergency situations that arise due to actions beyond the Contractor’s control where flagging is needed to maintain safe traffic control on a temporary basis. Spotters are defined as certified flaggers that provide support to workers by monitoring traffic.

Flaggers and spotters shall be stationed to the satisfaction of the Engineer and be equipped with a fluorescent orange, fluorescent yellow/green, or a combination of fluorescent orange and fluorescent yellow/green vest meeting the requirements of ANSI/ISEA 107-2004 or ANSI/ISEA 107-2010 for Conspicuity Class 2 garments. Flaggers shall be equipped with a stop/slow traffic control sign. Spotters shall be equipped with a loud warning device. The warning sound shall be identifiable by workers so they can take evasive action when necessary. Other types of garments may be substituted for the vest as long as the garments have a manufacturer’s tag identifying them as meeting the ANSI Class 2 requirement. The longitudinal placement of the flagger may be increased up to 100 ft (30 m) from that shown on the plans to improve the visibility of the flagger. Flaggers shall not encroach on the open lane of traffic unless traffic has been stopped. Spotters shall not encroach on the open lane of traffic, nor interact with or control the flow of traffic.

For nighttime flagging, flaggers shall be illuminated by an overhead light source providing a minimum vertical illuminance of 10 fc (108 lux) measured 1 ft (300 mm) out from the flagger’s chest. The bottom of any luminaire shall be a minimum of 10 ft (3 m) above the pavement. Luminaire(s) shall be shielded to minimize glare to approaching traffic and trespass light to adjoining properties. Nighttime flaggers shall be equipped with fluorescent orange or fluorescent orange and fluorescent yellow/green apparel meeting the requirements of ANSI/ISEA 107-2004 or ANSI/ISEA 107-2010 for Conspicuity Class 3 garments.

Flaggers and spotters shall be provided per the traffic control plan and as follows.

- (a) Two-Lane Highways. Two flaggers will be required for each separate operation where two-way traffic is maintained over one lane of pavement. Work operations controlled by flaggers shall be no more than 1 mile (1600 m) in length. Flaggers shall be in sight of each other or in direct communication at all times. Direct communication shall be obtained by using portable two-way radios or walkie-talkies.

The Engineer will determine when a side road or entrance shall be closed to traffic. A flagger will be required at each side road or entrance remaining open to traffic within the operation where two-way traffic is maintained on one lane of pavement. The flagger shall be positioned as shown on the plans or as directed by the Engineer.

(b) Multi-Lane Highways. At all times where traffic is restricted to less than the normal number of lanes on a multilane pavement with a posted speed limit greater than 40 mph and the workers are present, but not separated from the traffic by physical barriers, a flagger or spotter shall be furnished as shown on the plans. Flaggers shall warn and direct traffic. Spotters shall monitor traffic conditions and warn workers of errant approaching vehicles or other hazardous conditions as they occur. One flagger will be required for each separate activity of an operation that requires frequent encroachment in a lane open to traffic. One spotter will be required for each separate activity with workers near the edge of the open lane or with their backs facing traffic.

Flaggers will not be required when no work is being performed, unless there is a lane closure on two-lane, two-way pavement.”

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)

Effective: November 1, 2021

Revised: November 1, 2022

Add the following paragraph after the first paragraph of Article 701.08 of the Standard Specifications:

“The Contractor shall equip all vehicles and equipment with high-intensity oscillating, rotating, or flashing, amber or amber-and-white, warning lights which are visible from all directions. In accordance with 625 ILCS 5/12-215, the lights may only be in operation while the vehicle or equipment is engaged in construction operations.”

WEEKLY DBE TRUCKING REPORTS (BDE)

Effective: June 2, 2012

Revised: November 1, 2021

The Contractor shall submit a weekly report of Disadvantaged Business Enterprise (DBE) trucks hired by the Contractor or subcontractors (i.e. not owned by the Contractor or subcontractors) that are used for DBE goal credit.

The report shall be submitted to the Engineer on Department form “SBE 723” within ten business days following the reporting period. The reporting period shall be Sunday through Saturday for each week reportable trucking activities occur.

Any costs associated with providing weekly DBE trucking reports shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed.

WORK ZONE TRAFFIC CONTROL DEVICES (BDE)

Effective: March 2, 2020

Add the following to Article 701.03 of the Standard Specifications:

“(q) Temporary Sign Supports1106.02”

Revise the third paragraph of Article 701.14 of the Standard Specifications to read:

“For temporary sign supports, the Contractor shall provide a FHWA eligibility letter for each device used on the contract. The letter shall provide information for the set-up and use of the device as well as a detailed drawing of the device. The signs shall be supported within 20 degrees of vertical. Weights used to stabilize signs shall be attached to the sign support per the manufacturer’s specifications.”

Revise the first paragraph of Article 701.15 of the Standard Specifications to read:

“701.15 Traffic Control Devices. For devices that must meet crashworthiness standards, the Contractor shall provide a manufacturer’s self-certification or a FHWA eligibility letter for each Category 1 device and a FHWA eligibility letter for each Category 2 and Category 3 device used on the contract. The self-certification or letter shall provide information for the set-up and use of the device as well as a detailed drawing of the device.”

Revise the first six paragraphs of Article 1106.02 of the Standard Specifications to read:

“1106.02 Devices. Work zone traffic control devices and combinations of devices shall meet crashworthiness standards for their respective categories. The categories are as follows.

Category 1 includes small, lightweight, channelizing and delineating devices that have been in common use for many years and are known to be crashworthy by crash testing of similar devices or years of demonstrable safe performance. These include cones, tubular markers, plastic drums, and delineators, with no attachments (e.g. lights). Category 1 devices manufactured after December 31, 2019 shall be MASH-16 compliant. Category 1 devices manufactured on or before December 31, 2019, and compliant with NCHRP 350 or MASH 2009, may be used on contracts let before December 31, 2024.

Category 2 includes devices that are not expected to produce significant vehicular velocity change but may otherwise be hazardous. These include vertical panels with lights, barricades, temporary sign supports, and Category 1 devices with attachments (e.g. drums with lights). Category 2 devices manufactured after December 31, 2019 shall be MASH-16 compliant. Category 2 devices manufactured on or before December 31, 2019, and compliant with NCHRP 350 or MASH 2009, may be used on contracts let before December 31, 2024.

Category 3 includes devices that are expected to cause significant velocity changes or other potentially harmful reactions to impacting vehicles. These include crash cushions (impact attenuators), truck mounted attenuators, and other devices not meeting the definitions of Category 1 or 2. Category 3 devices manufactured after December 31, 2019 shall be MASH-16 compliant. Category 3 devices manufactured on or before December 31, 2019, and compliant with NCHRP 350 or MASH 2009, may be used on contracts let before December 31, 2029. Category 3 devices shall be crash tested for Test Level 3 or the test level specified.

Category 4 includes portable or trailer-mounted devices such as arrow boards, changeable message signs, temporary traffic signals, and area lighting supports. It is preferable for Category 4 devices manufactured after December 31, 2019 to be MASH-16 compliant; however, there are currently no crash tested devices in this category, so it remains exempt from the NCHRP 350 or MASH compliance requirement.

For each type of device, when no more than one MASH-16 compliant is available, an NCHRP 350 or MASH-2009 compliant device may be used, even if manufactured after December 31, 2019.”

Revise Articles 1106.02(g), 1106.02(k), and 1106.02(l) to read:

“(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.

(k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(l) Movable Traffic Barrier. The movable traffic barrier shall be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis.”

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **55** working days.

REVISIONS TO THE ILLINOIS PREVAILING WAGE RATES

The Prevailing rates of wages are included in the Contract proposals which are subject to Check Sheet #5 of the Supplemental Specifications and Recurring Special Provisions. The rates have been ascertained and certified by the Illinois Department of Labor for the locality in which the work is to be performed and for each craft or type of work or mechanic needed to execute the work of the Contract. As required by Prevailing Wage Act (820 ILCS 130/0.01, et seq.) and Check Sheet #5 of the Contract, not less than the rates of wages ascertained by the Illinois Department of Labor and as revised during the performance of a Contract shall be paid to all laborers, workers and mechanics performing work under the Contract. Post the scale of wages in a prominent and easily accessible place at the site of work.

If the Illinois Department of Labor revises the prevailing rates of wages to be paid as listed in the specification of rates, the contractor shall post the revised rates of wages and shall pay not less than the revised rates of wages. Current wage rate information shall be obtained by visiting the Illinois Department of Labor web site at <http://www.state.il.us/agency/idol/> or by calling 312-793-2814. It is the responsibility of the contractor to review the rates applicable to the work of the contract at regular intervals in order to insure the timely payment of current rates. Provision of this information to the contractor by means of the Illinois Department of Labor web site satisfies the notification of revisions by the Department to the contractor pursuant to the Act, and the contractor agrees that no additional notice is required. The contractor shall notify each of its subcontractors of the revised rates of wages.