06-14-2024 LETTING ITEM 075

FOR INDEX OF SHEETS, SEE SHEET NO. 2

ADT = 4,000

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

PROPOSED HIGHWAY PLANS

> FAP ROUTE 766 (ILL 32) SECTION D7 AGG SHLD 2024-4

SHOULDER RECONSTRUCTION SHELBY COUNTY

START PROJECT -C-97-009-24 END PROJECT -

EFFINGHAM CO LINE

STATE OF ILLINOIS

LOCATION OF SECTION INDICATED THUS: -

May 10, 2024

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

PROJECT ENGINEER: JACQUELYN SEALS

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS

ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

LENGTH = 13.0 MILE PROJECT MANAGER: KYLE PRICE

STA. 688+10

STA. 13+00

CONTRACT NO. 74C77

1-800-892-0123 OR 811

0

0

0

3 SUMMARY OF QUANTIES

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 3

STD. NO. DESCRIPTION

000001 - 08 STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS

001006 DECIMAL OF AN INCH AND OF A FOOT

406201 - 01 MAILBOX TURNOUT

701001 - 02 OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' (4 5 M) AWAY

701006 - 05 OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 M) TO 24" (600 MM) FROM PAVEMENT EDGE OFF-ROAD

701011 - 04 MOVING OPERATIONS, 2L, 2W, DAY ONLY

701301 - 04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS

701306 - 04 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS > 45 MPH


701901 - 09 TRAFFIC CONTROL DEVICES

GENERAL NOTES

AGGREGATE FOR MAILBOX TURNOUTS AND PRIVATE ENTRANCES SHALL BE PLACED AS DIRECTED BY THE ENGINEER AND WILL BE PAID FOR AS AGGREGATE SHOULDERS, TYPE B.

A RATE OF APPLICATION OF 2.05 TONS/CU YD HAS BEEN USED IN CALCULATING PLAN QUANTITY.

RAP IS NOT ALLOWED FOR THE AGGREGATE SHOULDERS.



SHOULDER DETAIL

REV. - MS

USER NAME = jessica.hille	DESIGNED	REVISED -	
	DRAWN	REVISED -	
PLOT SCALE = 100.0000 / in.	CHECKED	REVISED =	
PLOT DATE = 3/28/2024	DATE	REVISED 4	

100% STATE

CUI II I DE CUI II I I I I I I I I I I I I I I I I				CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE			
	SUMMARY OF QUANTITIES		TOTAL	0021				SUMMARY	UF	QUANTITIES		TOTAL			
CODE NO	ITEM	UNIT	OUANTITIES				CODE NO		ITEM		UNIT	QUANTITIES			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6253.9	6253.9											
46101200	AGGREGATE SHOULDERS, TIFE B	TON	6255.5	6253.3											
67100100	MOBILIZATION	L SUM	1	1											
			_												
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1											
	701306														
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28											
10101025	CHANGEABLE MESSAGE SIGN	CAL DA	26	20							<u> </u>			1	
								<u> </u>			<u> </u>				
	1				1										
				<u> </u>	<u> </u>						<u> </u>			<u> </u>	1
						<u> </u>									

USER NAME = jessica.hille	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 3/28/2024	DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE:

							SECTION	COUNTY	TOTAL SHEETS	SHEE NO.	
SUMMARY OF QUANTITIES						766	D7 AGG SHLD 202	4-4	SHELBY	3	3
									CONTRACT	NO. 74	4C77
	SHEET	OF	SHEETS	STA.	TO STA.		ILLINOIS	FED. A	D PROJECT		