



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2024

SUBJECT FAU Route 2721 (Kean Avenue)  
Section FAU 2721 221 RS  
Cook County  
Contract No. 62R41  
Item No. 108, June 14, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added pages 122 & 123 to the Special Provisions
4. Revised sheets 4 & 5 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT ..... 66

REBUILD EXISTING HANDHOLE ..... 67

COILABLE NON-METALLIC CONDUIT ..... 68

DETECTOR LOOP ..... 68

GEOCELL CONFINING SYSTEM ..... 71

AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)..... 72

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) ..... 73

CEMENT, TYPE IL (BDE)..... 74

COMPENSABLE DELAY COSTS (BDE)..... 75

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)..... 78

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... 81

FUEL COST ADJUSTMENT (BDE)..... 90

GRADING AND SHAPING DITCHES (BDE)..... 92

HOT-MIX ASPHALT (BDE)..... 93

HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)..... 93

ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)..... 95

PERFORMANCE GRADED ASPHALT BINDER (BDE)..... 95

PORTLAND CEMENT CONCRETE (BDE) ..... 100

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) ..... 100

SEEDING (BDE) ..... 102

SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)..... 107

SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) ..... 110

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 111

SUBMISSION OF PAYROLL RECORDS (BDE)..... 111

SURFACE TESTING OF PAVEMENTS – IRI (BDE) ..... 112

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) ..... 118

WEEKLY DBE TRUCKING REPORTS (BDE)..... 119

WORK ZONE TRAFFIC CONTROL DEVICES (BDE) ..... 119

WORKING DAYS (BDE)..... 121

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) ..... 122

Revised 6/5/2024

## REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

**Description.** This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

**Contract Specific Sites.** The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

**Soil Disposal Analysis.** When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

### Intersection of Kean Avenue and Windsor Drive, Palos Hills, Cook County

- All excavation planned at the northeast quadrant at the intersection of Kean Avenue and Windsor Drive. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

### Intersection of Kean Avenue and 95<sup>th</sup> Street, Palos Hills, Cook County

- All excavation planned for ADA ramp, pedestrian posts, and horse path improvements at the northwest quadrant, northeast quadrant, and southwest quadrant at the intersection of Kean Avenue and 95<sup>th</sup> Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

### Kean Avenue, Palos Hills, Cook County

- Station 86+00 to Station 88+00 (CL Kean Avenue), 0 to 35 feet RT. All excavation planned for grading and shaping of ditches. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.
- Station 89+00 to Station 90+00 (CL Kean Avenue), 0 to 35 feet RT. All excavation planned for grading and shaping of ditches. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Added 6/5/2024

- Station 107+35 to Station 108+70 (CL Kean Avenue), 0 to 40 feet RT. All excavation planned for grading and shaping of ditches. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.
- Station 110+00 to Station 111+15 (CL Kean Avenue), 0 to 40 feet RT. All excavation planned for grading and shaping of ditches. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

**Work Zones**

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

**None**

Added 6/5/2024