

MODEL: Default
 FILE NAME: \\pwrch01\pwrch01\0700\0702\DOT\DOT\DMR-PK-Roads\0702-0001-0002 - Ft. Massac Flood Repror_05_PTB\2024\05_W02\CADD_Prod\Drawings\046938.dwg 003-004_S&O.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE	
				ROADWAY	
				0004	RURAL
21400100	GRADING AND SHAPING DITCHES	FOOT	400		400
25100630	EROSION CONTROL BLANKET	SQ YD	400		400
28000400	PERIMETER EROSION BARRIER	FOOT	483		483
* 28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	359		359
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	569		569
42000060	WELDED WIRE REINFORCEMENT	SQ YD	584		584
* 42000200	PORTLAND CEMENT CONCRETE PAVEMENT 7"	SQ YD	597		597
42001300	PROTECTIVE COAT	SQ YD	597		597
* 50300225	CONCRETE STRUCTURES	CU YD	28.6		28.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1728		1728
63302700	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6	EACH	4		4
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3		3
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	4		4
67100100	MOBILIZATION	L SUM	1		1
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	817		817
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	86		86

2

2

* - DENOTES SPECIAL PROVISION
 * SPECIALTY ITEM

2 REVISD 6-4-2024

USER NAME = jboegue PLOT SCALE = 40.0000 ' / in. PLOT DATE = 3/21/2024	DESIGNED - SDK DRAWN - JEB CHECKED - RHD DATE - 3/21/2024	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DEPARTMENT OF NATURAL RESOURCES	SUMMARY OF QUANTITIES FORT MASSAC STATE PARK	F.A. RTE. SECTION COUNTY MASSAC ILLINOIS	TOTAL SHEETS 8 FED. AID PROJECT	SHEET NO. 3 CONTRACT NO. 46938
SCALE:			SHEET OF SHEETS STA. TO STA.				