





SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004 ROADWAY 80% FED 20% LOCAL	0021 SAFETY 80% FED 20% LOCAL
X	XX006659	FLOCCULATION POWDER	POUND	10	10	
X	XX009417	CASING PIPE, 16"	FOOT	71	71	
	Z0013798	CONSTRUCTION LAYOUT 	L SUM	1	1	
X	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	64	64	
X	Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	15		15
X	Z0033039	DISCONNECT AND RECONNECT ELECTRIC SERVICE	EACH	1		1
X	Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	334	334	
	Z0062456	TEMPORARY PAVEMENT	SQ YD	1,811	1,811	
	Z0070150	REMOVE AND RELOCATE EXISTING MONUMENT	EACH	1	1	
X	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	3	3	
	Z0076600	TRAINEES	HOURS	500	500	
	Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURS	500	500	
X	Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	20	20	

 DENOTES CONSTRUCTION TYPE CODE 0042

MODEL: Default  
FILE NAME: P:\08\1324 - US Rte 20 Roundabout\CAD\Sheets\03\_s04.dgn



DESIGNED - TGB	REVISED -  5/16/2024
DRAWN - KEH	REVISED -
CHECKED - RTM	REVISED -
DATE - 2/14/2024	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SHEET 10 OF 10 SHEETS STA. TO STA.

F.A.P./ F.A.U. 345A/ 2340	SECTION 19-00187-00-CH	COUNTY KANE	TOTAL SHEETS 115	SHEET NO. 12
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 61J28	