

CHAMLIN & ASSOCIATES, INC. © 2023  
 Drawing Name: G:\Users\A66200-11\Peru-Plank Rd Reconstruction-South Contract\CAD\015-01B-SCHED.dwg Last Modified: Friday, May 17, 2024 10:11:29 AM Plotted On: Friday, May 17, 2024 10:12:20 AM by Debbie Story

STORM SEWER STRUCTURE SCHEDULE																					
STRUCTURE NUMBER	STATION	OFFSET	RIM ELEV.	FLOW LINE ELEVATION				PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 18"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	FLUSH INLET BOX FOR MEDIAN	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	INLETS, TYPE B, TYPE 8 GRATE	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	REMARKS
				NORTH	SOUTH	EAST	WEST														
SUBTOTAL FROM PREVIOUS SHEET							19	3	4	0	2	3	1	0	0	21	0	0	10		
24G	1053+00	45' LT	649.88	642.00	642.00	642.00	-	-	-	-	-	-	-	-	1	-	-	-	-	-	NOT TRUE EAST
24H	1053+16.2	59.2' LT	-	-	-	-	645.73	-	1	-	-	-	-	-	-	-	-	-	-	-	
24I	1051+00	45' LT	649.60	642.60	642.60	-	-	-	-	-	-	1	-	-	-	-	-	-	-	-	NOT TRUE NORTH
24J	1050+67	12' LT	651.13	642.70	642.70	-	-	-	-	-	-	1	-	-	-	-	-	-	-	-	NOT TRUE SOUTH
24K	1050+05	12' LT	651.32	642.89	642.89	-	-	-	-	-	-	1	-	-	-	-	-	-	-	-	NOT TRUE NORTH
24L	1049+79	45' LT	650.20	642.96	642.96	642.96	-	-	-	-	-	-	-	1	-	-	-	-	-	-	NOT TRUE SOUTH
24M	1049+79	57.6' LT	646.80	-	-	-	643.06	-	-	-	1	-	-	-	-	-	-	-	-	-	
24N	1048+00	45' LT	650.10	643.50	643.50	643.50	643.50	-	-	-	-	-	-	1	-	-	-	-	-	-	
24O	1048+00	56.5' LT	646.88	-	-	-	644.20	-	-	-	1	-	-	-	-	-	-	-	-	-	
24P	1048+00	39.2' RT	647.71	-	-	643.90	-	-	-	-	1	-	-	-	-	-	-	-	-	-	
24Q	1045+75	45' LT	649.80	644.18	644.18	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	
24R	1045+60	45' RT	-	-	644.22	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	
25	1059+90	37.9' RT	-	-	-	643.14	-	1	-	-	-	-	-	-	-	-	-	-	-	-	
25A	1059+90	19' RT	646.60	-	-	-	643.60	-	-	-	-	-	-	-	-	1	-	-	-	-	
26	1059+90	49' LT	-	-	-	-	644.49	1	-	-	-	-	-	-	-	-	-	-	-	-	
26A	1058+05	19' LT	647.70	-	-	644.70	-	-	-	-	-	-	-	-	-	1	-	-	-	-	
27	1058+05	36.2' RT	-	-	-	644.37	-	1	-	-	-	-	-	-	-	-	-	-	-	-	
27A	1058+05	19' RT	647.70	-	-	-	644.70	-	-	-	-	-	-	-	-	1	-	-	-	-	
28	1056+65	50.1' LT	-	-	-	-	645.05	1	-	-	-	-	-	-	-	-	-	-	-	-	
28A	1056+65	19' LT	648.40	-	-	645.40	-	-	-	-	-	-	-	-	-	1	-	-	-	-	
29	1056+65	37' RT	-	-	-	645.06	-	1	-	-	-	-	-	-	-	-	-	-	-	-	
29A	1056+65	19' RT	648.40	-	-	-	645.40	-	-	-	-	-	-	-	-	1	-	-	-	-	
30	1055+64.1	36.0' RT	-	645.24	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	
30A	1055+25	19' RT	649.05	-	646.05	-	-	-	-	-	-	-	-	-	-	-	1	-	-	-	
31	1055+59.6	38' RT	-	645.26	-	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	
31A	1055+01.6	38' RT	-	-	645.46	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	
32	1055+25	51.2' LT	-	-	-	645.83	1	-	-	-	-	-	-	-	-	-	-	-	-	-	
32A	1055+25	19' LT	649.05	-	-	646.05	-	-	-	-	-	-	-	-	-	1	-	-	-	-	
33	1053+85	39.7' RT	-	-	-	645.88	-	1	-	-	-	-	-	-	-	-	-	-	-	-	
33A	1053+85	19' RT	649.80	-	-	-	646.80	-	-	-	-	-	-	-	-	1	-	-	-	-	
34	1052+30	53.1' LT	-	-	-	-	646.21	1	-	-	-	-	-	-	-	-	-	-	-	-	
34A	1052+30	19' LT	650.44	-	-	647.44	-	-	-	-	-	-	-	-	-	1	-	-	-	-	
SUBTOTAL							28	5	6	3	2	6	1	3	1	29	1	0	10		



CONTRACT 87838

DRAWN BY: DS	LEVEL	BY	DATE	REVISIONS	DESCRIPTION
CHECKED BY: JKC					
DATE: 11/2023					



PERU MORRIS  
 OTTAWA MENDOTA  
 ILLINOIS  
 CITY OF PERU  
 PLANK ROAD RECONSTRUCTION 2023  
 SECTION NO. 22-00070-01-PV

SCHEDULE OF QUANTITIES

<b>CONSTRUCTION PLANS</b>	CURRENT AS OF: 03/22/2024	
	SCALE: AS NOTED	SHEET 17
	FILE NO.: 66200.11 Y-	OF 112