

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
577	3114 N-1	COOK	72	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

90% FED. / 10% STATE CONTRACT NO. 60A25

SUMMARY OF QUANTITIES			90% FED. / 10% STATE		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES		100% VILLAGE			
				I000-1A	Y031-1F	Y031-3D		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1287	1287				
50105220	PIPE CULVERT REMOVAL	FOOT	455	455				
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	10	10				
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	208.15	208.15				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	452	452				
60107600	PIPE UNDERDRAINS 4"	FOOT	355.5	355.5				
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	2	2				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	415	415				
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	722	722				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	940	940				
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	331.25	331.25				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	5	5				
63200310	GUARDRAIL REMOVAL	FOOT	755.5	755.5				
66410302	CHAIN LINK FENCE REMOVAL, SPECIAL	FOOT	173	173				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	0.5	0.5			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1			

SUMMARY OF QUANTITIES			90% FED. / 10% STATE		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES		100% VILLAGE			
				I000-1A	Y031-1F	Y031-3D		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1		1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	326	326				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	184	184				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8836	8836				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	710	710				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	242	242				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	105	105				
70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	11600	11600				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	105	105				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4555	4555				
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	987.5	987.5				
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	987.5	987.5				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	28.5		28.5			
* 72000200	SIGN PANEL - TYPE 2	SQ FT	25		25			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	184	184				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8836	8836				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	710	710				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	242	242				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105	105				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	88	88				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4				

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILL 171 (ARCHER AVE.)  
AT ASHBURY DR. AND 131ST ST.  
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 5/3/2007

5/3/2007