

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-2	WILL	228	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEM	UNIT	URBAN		ROADWAY	BLACK RD	CATON FARM	SIGNING
			TOTAL QUANTITY	1000-2A				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3				
63200310	GUARDRAIL REMOVAL	FOOT	10,200	10,200				
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	125	125				
63500105	DELINEATORS	EACH	114	114				
63700805	CONCRETE BARRIER TRANSITION	FOOT	397	397				
63700900	CONCRETE BARRIER BASE	FOOT	16,829	16,829				
64200105	SHOULDER RUMBLE STRIP	FOOT	70,508	70,508				
67100100	MOBILIZATION	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	221,591	221,591				
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	20,707	20,707				
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	9,102	9,102				
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	823	823				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	50,982	50,982				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	34,770	34,770				
72000200	SIGN PANEL - TYPE 2	SQ FT	183				183	
72000300	SIGN PANEL - TYPE 3	SQ FT	2,129				2,129	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9				9	
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	11				11	
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	20				20	
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	2,018				2,018	
72600100	MILE POST MARKER ASSEMBLY	EACH	7				7	
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1,546				1,546	
73000100	WOOD SIGN SUPPORT	FOOT	280				280	
73400100	CONCRETE FOUNDATIONS	CU YD	3.9				3.9	
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	5				5	
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	5				5	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	74,121	74,121				
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4,197	4,197				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,020	2,020				
78003110	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1,467	1,467				
78003120	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	18,801	18,801				
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	45,674	45,674				
78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	28,890	28,890				
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	4,354	4,354				
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	439	439				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1904	1904				
78100300	REPLACEMENT REFLECTOR	EACH	388	388				
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	6,612	6,612				
78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18				
78200530	BARRIER WALL MARKERS, TYPE C	EACH	434	434				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	18,347	18,347				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	892	892				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	785	785				
X0322323	WEED CONTROL, TEASEL	GALLON	2.5	2.5				

\* SPECIALTY ITEMS  
 \*\* URBAN, 90% FEDERAL, 10% STATE (SEE NOTE)

NOTE:

TYPE 3 SIGN PANELS WHICH REQUIRE TYPE ZZ SHEETING WILL BE 100% PAID FOR BY STATE FUNDS. THE REST WILL BE PAID FOR BY 90% FEDERAL FUNDS AND 10% STATE FUNDS. A QUANTITY OF 952 SQ FT OF ITEM NO. 72000300, SIGN PANEL - TYPE 3 REQUIRES TYPE ZZ RETROREFLECTIVE SHEETING.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55 (BLACK ROAD TO U.S. 30)  
 WIDENING AND RESURFACING

SUMMARY OF QUANTITIES  
 III

SCALE: N.T.S.  
 DATE 03/22/07

DRAWN BY AG  
 CHECKED BY DDH



TENGL & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 CHICAGO, ILLINOIS