

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) WRS-2	WILL	228	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN			
				ROADWAY	BLACK RD	CATON FARM	SIGNING
				1000-2A	099-0209 SFTY-2A	099-0210 X231-2A	Y002-1C
X0322729	MATERIAL TRANSFER DEVICE	TON	35,210	35,210			
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	9	9			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	185	185			
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	139	139			
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	139	139			
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	8	8			
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2			
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,864	1,864			
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1,864	1,864			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	218			218	
X0484300	MEDIAN INLET BOX REMOVAL	EACH	6	6			
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	19,214	19,214			
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	15,996	15,996			
X6330100	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL	EACH	4	4			
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	16,432	16,432			
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	18			
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	18	18			
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	330	330			
XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	11,485	11,485			
XX004592	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2			
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	75,200	75,200			
NP Z0005305	BOX CULVERTS TO BE CLEANED	FOOT	141	141			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4			
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	9	9			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	6	6			
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	1	1			
Z0076600	TRAINEES	HOUR	4,000	4,000			
35501288	HOT-MIX ASPHALT BASE COURSE, 2 1/2"	SQ YD	68,549	68,549			
X0325733	TEMPORARY ASPHALT WEDGE	SQ YD	1,422	1,422			
X4421000	PARTIAL DEPTH PATCHING	TON	111	111			
X4422025	PARTIAL DEPTH REMOVAL, 2"	SQ YD	988	988			

PLOT DATE: 3/22/07
 FILE NAME: I:\S0810001.DGN
 USER: GARCIAJAZ

© 1080
 NP = NON-PARTICIPATING
 * SPECIALTY ITEMS
 ** URBAN, 90% FEDERAL, 10% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55 (BLACK ROAD TO U.S. 30)
 WIDENING AND RESURFACING

SUMMARY OF QUANTITIES IV

SCALE: N.T.S. DRAWN BY: AG
 DATE: 03/22/07 CHECKED BY: DDH

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS

Rev. 5-30-07