

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-2	WILL	228	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NO.	ITEM	UNIT	URBAN		ROADWAY	BLACK RD	CATON FARM	SIGNING
			TOTAL QUANTITY	1000-2A				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	226	226				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48	48				
20101000	TEMPORARY FENCE	FOOT	290	290				
20200100	EARTH EXCAVATION	CU YD	15,893	15,893				
20200200	ROCK EXCAVATION	CU YD	873	873				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	13,878	13,878				
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,610	1,610				
20800150	TRENCH BACKFILL	CU YD	5,024	5,024				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	6,680	6,680				
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	2,261	2,261				
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	1,925	1,925				
25000210	SEEDING, CLASS 2A	ACRE	0.47	0.47				
25000310	SEEDING, CLASS 4	ACRE	0.21	0.21				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	42	42				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	42	42				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	42	42				
25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	0.19	0.19				
25100115	MULCH, METHOD 2	ACRE	1.19	1.19				
25100630	EROSION CONTROL BLANKET	SQ YD	3,274	3,274				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100				
28000300	TEMPORARY DITCH CHECKS	EACH	6	6				
28000500	INLET AND PIPE PROTECTION	EACH	2	2				
28000510	INLET FILTERS	EACH	185	185				
28100105	STONE RIPRAP, CLASS A3	SQ YD	33	33				
28100107	STONE RIPRAP, CLASS A4	SQ YD	126	126				
28200200	FILTER FABRIC	SQ YD	126	126				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	68,549	68,549				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	146	146				
40600300	AGGREGATE (PRIME COAT)	TON	39	39				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	41.1	41.1				
40600895	CONSTRUCTING TEST STRIP	EACH	5	5				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	331	331				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,636	1,636				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,016	4,016				
42001300	PROTECTIVE COAT	SQ YD	1,579	1,579				
44000100	PAVEMENT REMOVAL	SQ YD	316	316				
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	93,824	93,824				
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	41,148	41,148				
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	22,618	22,618				
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	8,343	8,343				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	1,131	1,131				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	4,623	4,623				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	563	563				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	148	148				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	104,683	104,683				
50102400	CONCRETE REMOVAL	CU YD	13.7				13.7	

* SPECIALTY ITEMS
 ** URBAN, 90% FEDERAL, 10% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55 (BLACK ROAD TO U.S. 30)
 WIDENING AND RESURFACING

SUMMARY OF QUANTITIES
 I

SCALE: N.T.S.

DATE: 03/22/07

DRAWN BY: AG

CHECKED BY: DDH



TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 CHICAGO, ILLINOIS

DATE = 03/22/07
 FILE NAME = 030814001.DGN
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = MUBEN

DOCUMENT: 02305580\CIVIL\CON\60B46\001.DGN