CONTRACT NO. 60B46

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-2	WILL	228	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

	CODE NO.	ITEM	UNIT	URBAN ** TOTAL QUANTITY	ROADWAY I000-2A	BLACK RD 099-0209 SFTY-2A	CATON FARM 099-0210 X231-2A	SIGNING Y002-1C	
	X0322729	MATERIAL TRANSFER DEVICE	TON	35,210	35,210				
	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	9	9				
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	185	185				
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	139	139				
	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	139	139				
	X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	8	8				
	X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2				
	X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,864	1,864				
	X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1,864	1,864				
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 **INCHES**)	SQ FT	218			218		
	X0484300	MEDIAN INLET BOX REMOVAL	EACH	6	6				
	X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	19,214	19,214				
	X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	15,996	15,996				
	X6330100	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL	EACH	1	1				
	X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	16,432	16,432				
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	18				
	X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	18	18				
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	330	330				
	XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	11,485	11,485				
	XX004592	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2				
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	75,200	75,200				
NP	Z0005305	BOX CULVERTS TO BE CLEANED	FOOT	141	141				
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
NP	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4				
*	Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	9	9				
*	Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	6	6				
	Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	1	1				
@	Z0076600	TRAINEES	HOUR	4,000	4,000				
	35501288	HOT-MIX ASPHALT BASE COURSE, 2 1/2"	SQ YD	68,549	68,549				
	X0325733	TEMPORARY ASPHALT WEDGE	SQ YD	1,422	1,422				

@ Y080
NP= NON-PARTICIPATING
* SPECIALTY ITEMS
** URBAN, 90% FEDERAL, 10% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (BLACK ROAD TO U.S. 30)
WIDENING AND RESURFACING

SUMMARY OF QUANTITIES
IV

SCALE: N.T.S. DRAWN BY AG
DATE 03/22/07 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$

..\ED99\A001.DGN,..\S0081A001.DGN,..\S0081A001.DGN
3-21-2007,15:22:05 GARCIAAZ 5:\DOCUMENT\82385\01\CIVIL\DGN\S0081A0004.SHT