

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) WRS-3	WILL	305	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
		SQQ-01 OF 6		

CODE NO.	ITEM	UNIT	URBAN 90% FED. / 10% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY Sta. 789+00 to Sta. 950+84.47	WEBER Sta. 905+49.48	LIGHTING Sta. 789+00 to Sta. 950+84.47
				1000-2A	SFTY-2A	Y031-1E
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	82	82		
20200100	EARTH EXCAVATION	CU YD	22,570	22,570		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10,675	10,675		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	4,296	4,296		
20800150	TRENCH BACKFILL	CU YD	5,982	5,982		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	12,889	12,889		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	2,285	2,285		
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	390	390		
25000210	SEEDING, CLASS 2A	ACRE	3.75	3.75		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	340	340		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	340	340		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	340	340		
25100115	MULCH, METHOD 2	ACRE	4.25	4.25		
25100630	EROSION CONTROL BLANKET	SQ YD	18,284	18,284		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	410	410		
28000300	TEMPORARY DITCH CHECKS	EACH	3	3		
28000500	INLET AND PIPE PROTECTION	EACH	20	20		
28000510	INLET FILTERS	EACH	140	140		
28100105	STONE RIPRAP, CLASS A3	SQ YD	52	52		
28200200	FILTER FABRIC	SQ YD	52	52		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	151	151		
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	31,397	31,397		
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	67	67		
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	15,142	15,142		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	52,348	52,348		
35501325	HOT-MIX ASPHALT BASE COURSE, 10 1/4"	SQ YD	125	125		
35501330	HOT-MIX ASPHALT BASE COURSE, 11 1/2"	SQ YD	3,435	3,435		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	194.3	194.3		
40600300	AGGREGATE (PRIME COAT)	TON	65.7	65.7		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20.9	20.9		
40600895	CONSTRUCTING TEST STRIP	EACH	5	5		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	790	790		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	869	869		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	4,713	4,713		
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19, N90	TON	9	9		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,504	3,504		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 143RD STREET TO WEBER ROAD
 SUMMARY OF
 QUANTITIES



SCALE: NONE
 DATE: 02-23-07
 DRAWN BY: AR
 CHECKED BY: SV

FINAL