CONTRACT NO. 60B47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	100 (1&2) I-9	WILL	305	150
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		DETLS - 16 OF 30		

SIGN REMOVAL SCHEDULE

SIGN DESIGNAION	STATION	REMOVE SIGN PANEL SIZE (IN X IN)	REMOVE SIGN PANEL AREA (SQ FT))	REMOVE SIGN PANEL TYPE (EACH)	REMOVE SIGN PANEL TYPE ASSEMBLY (EACH)	REMOVE GROUND MOUNTED SIGN SUPPORT (EACH)	REMOVE CONCRETE FOUNDATIONS GROUND MOUNT (EACH)	REMOVE CONCRETE FOUNDATIONS OVER HEAD (EACH)	REMOVE OVERHEAD SIGN STRUCTURE SPAN (EACH)	REMOVE OVERHEAD SIGN STRUCTURE CANTILEVER (EACH)	REMOVE OVERHEAD SIGN STRUCTURE BRIDGE MOUNTED (EACH)
W4-1R	795+61 NB	48 X 48	16.00	2	B						
M1-1	811+04 NB	36 X 36	16.00	2	B						
M3-1	811+04 NB	30 X 15	3.13	1							
R2-4a	817+69 NB	48 X 96	32.00	3		1	1				
R3-4	822+07 NB	24 X 36	6.00	1	B						
R3-I101	822+07 NB	24 X 24	4.00	1							
R3-4	822+07 SB	24 X 36	6.00	1	B						
R3-I101	822+07 SB	24 X 24	4.00	1							
GUIDE SIGN	822+11 SB	150 X 132	137.50	3		2	2				
SL TRUCKS	823+31 NB	48 X 96	32.00	3		1	1				
D10-3	827+51 NB	12 X 48	4.00	1	A						
D10-3	827+52 SB	12 X 48	4.00	1	A						
GUIDE SIGN	837+68 NB	228 X 90	142.50	3		3	3				
GUIDE SIGN	842+67 SB	150 X 132	137.50	3		2	2				
GUIDE SIGN	843+63 NB	162 X 102	114.75	3		2	2				
GUIDE SIGN	850+77 NB	180 X 120	150.00	3		2	2				
GUIDE SIGN	857+76 NB	246 X 120	205.00	3		2	2				
GUIDE SIGN	864+64 NB	162 X 102	114.75	3		2	2				
SL TRUCKS	864+65 SB	48 X 96	32.00	3		1	1				
R2-4a	869+01 SB	48 X 96	32.00	3		1	1				
GUIDE SIGN	872+50 NB	180 X 120	150.00	3		2	2				
M1-1	874+88 SB	36 X 36	16.00	2	B						
M3-3	874+88 SB	30 X 15	3.13	1							
ALCOHOL LIMIT SIGN	877+42 SB	48 X 60	20.00	2	B						
GUIDE SIGN	878+42 NB	96 X 48	32.00	3		1	1				
D10-3	880+33 NB	12 X 48	4.00	1	A						
D10-3	880+34 SB	12 X 48	4.00	1	A						
W13-3	885+00 NB	42 X 48	14.00	2	B						
GUIDE SIGN	887+40 SB	120 X 60	50.00	3		2	2				
E5-1a	892+17 NB	78 X 48	26.00	3		2	2				
W4-1R	896+30 SB	48 X 48	16.00	2	B						
GUIDE SIGN	907+34 SB	228 X 90	142.50	3		3	3				
W4-1R	914+87 NB	48 X 48	16.00	2	B						
E5-1a	917+93 SB	78 X 48	26.00	3		2	2				
GUIDE SIGN	922+41 SB	162 X 120	135.00	3				1		1	
GUIDE SIGN	925+63 NB	48 X 60	20.00	2	B						
GUIDE SIGN	945+75 SB	150 X 102	106.25	3							
GUIDE SIGN	967+90 SB	150 X 102	106.25	3							
TOTAL											
REMOVE SIGN PANEL ASSEMBLY TYPE A					4						
REMOVE SIGN PANEL ASSEMBLY TYPE B					10						
REMOVE SIGN PANEL TYPE 3			1904.00								
REMOVE GROUND MOUNTED SIGN SUPPORT						31					
REMOVE CONCRETE FOUNDATION - GROUND MOUNT							31				
REMOVE CONCRETE FOUNDATION - OVERHEAD								1			
REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER										1	

NOTE:

IT HAS BEEN ESTIMATED THAT 50% OF THE EXISTING TYPE 3 SIGN PANEL POSTS WILL REMAIN IN PLACE AND BE RE-USED TO SUPPORT NEW PROPOSED SIGN PANELS. TYPE 3 SIGN PANEL POSTS THAT ARE IN GOOD CONDITION AND WILL SUPPORT THE PROPOSED SIGN PANELS IN A MANNER THAT MEETS THE APPROPRIATE STANDARDS AND SPECIFICATIONS SHALL BE RE-USED AS DETERMINED BY THE ENGINEER. IF REQUIRED, MODIFICATION OF THE SIGN POST SYSTEMS TO ACCOMMODATE THE PROPOSED SIGNS WILL BE INCLUDED IN THE COST OF THE RESPECTIVE SIGN PANEL.

DAVID MASON & ASSOCIATES
Civil Engineering
Structural Engineering
Surveying
445 E. Illinois, Suite 640
Chicago, IL 60611
(312) 942-9600

PARSONS BRINCKERHOFF

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. I-55
143rd STREET TO WEBER RD.

SIGN REMOVAL SCHEDULE

SCALE:
DATE: FEBRUARY 23, 2007
DRAWN BY: JS, LC
CHECKED BY: SE

FINAL