

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEET NO.	SHEET	SHEET
FAI 55	**	WILL	305	183	7 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT			

\*\* SECTION 99 (1&2) WRS-3  
CONTRACT NO. 60B47

**GENERAL NOTES:**

1. Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work; however, the Contractor will be paid for the quantity actually furnished at the unit price for the work.
2. All Construction joints shall be bonded.
3. Existing reinforcement bars extending into the removal area shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.

**INDEX OF SHEETS**

1. Existing General Plan & Elevation
2. General Notes & Bill of Material
3. Median Removal
4. Median Details
5. Continuous Seal Type Neoprene Expansion Joint
6. Abutment Repair Details
7. Pier Repair Details

**TOTAL BILL OF MATERIAL**

ITEM	UNIT	SUPER	SUB	TOTAL
Concrete Removal	Cu. Yd.	88.6		88.6
Concrete Superstructure	Cu. Yd.	25.4		25.4
Concrete Structures	Cu. Yd.		26.5	26.5
* Reinforcement Bars, Epoxy Coated	Pound	2,170	2,270	4,440
Bridge Deck Grooving	Sq. Yd.	381		381
* Protective Coat	Sq. Yd.	513		513
Neoprene Expansion Joint, 2"	Foot	43.0		43.0
Epoxy Crack Injection	Foot		105	105

\* See Special Provisions

DESIGNED	S.CHELBIAN
CHECKED	J.GRAINAWI
DRAWN	S.CHELBIAN
CHECKED	J.GRAINAWI

Date: 2/23/2007

GENERAL NOTES  
& BILL OF MATERIALS  
WEBER ROAD OVER I-55  
SECTION 99 (1&2) WRS-3  
WILL COUNTY  
STA. 811+86.78  
STRUCTURE NO. 099-0281

