

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 341	32-1VB-I-1	COOK	19	4

CONTRACT 60B65

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE SFTY-2A
 ← BHF → F →

CODE NUMBER	DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE SFTY-2A			
				Location 1	Location 2	Location 1	Location 2
				016-0503	016-2469	016-0502	016-2596
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	1	1	1
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.25	0.25	0.25	0.25
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1918	705	754	231	228
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	14	0	0	0	14
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	0	0	4	4
X0322066	PROTECTIVE SHIELD (PERMANENT)	SQ YD	1672	812	860	0	0
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96	24	24	24	24
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.5	0	0
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	3.7	0	3.7	0	0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	189.2	175.8	13.4	0	0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0	0	0.5	0.5
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	19	17.6	1.4		
* X0325765	ANTI-ICING SURFACE OVERLAY	SQ YD	5868	2030	2170	721	947

* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev .