


F.A.P. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
352	(8 & 9) RS-4	LAKE	31	3
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

ENGLISH	PAY ITEM DESCRIPTION	UNIT	URBAN	
			TOTAL QUANTITY	1000 100% STATE
20200600	EXCAVATING AND GRADING EXISTING SHOULDERS	UNIT	278	278
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	107	107
40600300	AGGREGATE (PRIME COAT)	TON	514	514
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	26	26
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7,192	7,192
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	218	218
40600990	TEMPORARY RAMP	SQ YD	146	146
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	284	284
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10,787	10,787
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	55,892	55,892
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	119	119
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	603	603
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	960	960
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	1,443	1,443
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	563	563
48301000	PROTECTIVE COAT	SQ YD	40	40
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	26	26
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375	375
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	5	5
63200310	GUARDRAIL REMOVAL	FOOT	625	625
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12,555	12,555
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	437	437
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	67,013	67,013
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	987	987
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	9,201	9,201
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,613	1,613
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	77	77
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	5,781	5,781
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	781	781
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	781	781
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	433	433
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	85	85
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	285	285
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	2,535	2,535
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	874	874
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	94,083	94,083
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	8,151	8,151
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,876	1,876
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	14,720	14,720
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,260	2,260
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	324	324

\* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAP 352 (IL 137) GREENWOOD AVE TO GENESEE ST. SUMMARY OF QUANTITIES DRAWN BY: WS CHECKED BY: PJ DATE: 9/14/06
NAME	DATE	
 GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC. CHICAGO, ILLINOIS		

Rev.