

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2006-030 I	COOK	78	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			I000		
CODE NO	ITEM	UNIT		LOC. 1 I-90 016-0977 SFTY-2A	LOC. 2 ILL. 58 016-0980 SFTY-2A	LOC. 3 WOODFIELD 016-0978 SFTY-2A			
28100105	STONE RIPRAP, CLASS A3	SQ YD	24		24				
44000415	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	16,645	9733	5609	1303			
X0325774	RELOCATE TEMPORARY IMPACT ATTENUATOR	EACH	6	3	3				
50102400	CONCRETE REMOVAL	CU YD	148	85	63				
50157300	PROTECTIVE SHIELD	SQ YD	9,875	5,600	3,510	765			
50300100	FLOOR DRAINS	EACH	20		20				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	218	119	90	9			
50300530	FLOOR DRAIN EXTENSION	EACH	8		8				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	47,020	25,690	19,530	1800			
59000200	EPOXY CRACK INJECTION	FOOT	352	211	137	4			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	726	726					
* 63000015	STEEL PLATE BEAM GUARD RAIL, TYPE D	FOOT	623				623		
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	12				12		
63200725	STEEL PLATE BEAM GUARD RAIL REMOVAL, TYPE D	FOOT	2453	1070	683		1200		
<del>63304805</del>	<del>TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 6</del>	<del>EACH</del>	<del>12</del>	<del>6</del>	<del>6</del>				
64200105	SHOULDER RUMBLE STRIP	FOOT	10600	4232	4108	2260			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	5	4	2	1		
67100100	MOBILIZATION	L SUM	1	0.5	0.3	0.2			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		0.5	0.5			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	11	5	4	2			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	87392	43696	26218	17478			
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	62900	31450	18870	12580			
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	11210	5605	3363	2242			
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	510	255	193				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	63079	31540	18924	12615			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3737	2127	1610				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4450	2840	1610				
* 72100100	SIGN PANEL OVERLAY	SQ FT	640	320	320				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,500				14,500		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	6439	3213	2696	530			
78003120	PREFORMED PLASTIC PAVEMENT MARKING, LINE 5" TYPE B	FOOT	16,100				16,100		
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	1588	714	674	200			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	172	80	68	24			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6710				6710		
X0320887	POLYMER CONCRETE	CU FT	45		45				
X0321743	SILICONE JOINT SEALER, 1"	FOOT	1170	714	456				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N70	TON	1552	7	6	2	1537		
40603600	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N70	TON	71				71		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	249	115	98	36			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	18,461				18,461		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	623				623		

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			I000		
CODE NO	ITEM	UNIT		LOC. 1 I-90 016-0977 SFTY-2A	LOC. 2 ILL. 58 016-0980 SFTY-2A	LOC. 3 WOODFIELD 016-0978 SFTY-2A			
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96		48	48			
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	16,645	9733	5609	1303			
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	239		239				
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	315		239	76			
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	590	516		74			
<del>X0325261</del>	<del>SHOULDER RUMBLE STRIP REMOVAL</del>	<del>SQ YD</del>	<del>2,356</del>	<del>941</del>	<del>913</del>	<del>502</del>			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	980	597	290	93			
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	1753	1070	683				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.5	0.3	0.2			
X7012625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	EACH	1			1			
X7012630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	EACH	1		1				
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	204	102	60	42			
Z0006202	BRIDGE DECK HYDRO-SCARIFICATION 3/4"	SQ YD	16,645	9733	5609	1303			
<del>Z0015595</del>	<del>DECK DRAIN EXTENSIONS</del>	<del>EACH</del>	<del>86</del>		<del>60</del>	<del>26</del>			
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	45	30	10	5			
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	441	255	91	95			
Z0065700	SLOPE WALL REPAIR	SQ YD	99		56	43			
X0325042	MODIFY EXISTING CONNECTION TO SIGN STRUCTURE	EACH	8		8				
Z0010605	CLEAN DRAINAGE SYSTEM	L SUM	1	1					
X0322469	PLUG EXISTING FLOOR DRAINS	EACH	12			12			
X7240605	REMOVE AND RE-ERECT BRIDGE MOUNTED SIGN	EACH	1		1				

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev. 6-6-07