

SUMMARY OF QUANTITIES

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	102	6
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
* 991&21AC-R-2		CONTRACT NO. 60B97		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILL COUNTY			CONSTRUCTION TYPE CODE																		
				ROADWAY WESTERN FRONTAGE ROAD	SIGNING	STRUCTURE CULVERT																			
6060605	CONCRETE CURB, TYPE B	FOOT	13.5	13.5																					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	192.0	192.0																					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	160.0	160.0																					
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	387.5	387.5																					
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2																					
63500105	DELINEATORS	EACH	62	62																					
66500105	WOVEN WIRE FENCE, 4'	FOOT	2,368	2,368																					
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	2,306	2,306																					
66502400	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	2,308	2,308																					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9																					
67100100	MOBILIZATION	L SUM	1	1																					
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1																					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1603	1603																					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3100	3100																					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	89	89						89															
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	200	200																					
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	187	187						187															
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	13	13						13															
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	171	171																					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,728	18,728																					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	218	218																					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	107	107																					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	39	39																					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	38	38																					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	166	166																					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6																					
* 78200500	BARRIER WALL MARKERS, TYPE C	EACH	25	25																					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2																					
X0323260	SEDIMENT BASIN	EACH	2	2																					
X0325361	CULVERTS TO BE GROUTED	CU YD	7	7																					
X0712400	TEMPORARY PAVEMENT	SQ YD	3825	3825																					
70166000	CHANGEABLE MESSAGE SIGN	CAL MO	9	9																					
* X7030104	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 4 INCH	FOOT	29,268	29,268																					
XX003669	BITUMINOUS SIDEWALK REMOVAL	SQ YD	88	88																					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1																					
XX005656	INLET FILTER CLEANING	EACH	16	16																					

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 WEST FRONTAGE ROAD AT IL 59
SECTION: 991&21AC-R-2

SUMMARY OF QUANTITIES III

SCALE: _____ DRAWN BY: JB
DATE: 03/22/2007 CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
500 N. MICHIGAN AVE., CHICAGO, IL 60611
TELEPHONE: 312-649-0000

S:\00002940DN...S\00002940DN...TTB00262.DGN
 3-22-2007, 8:56:00
 T:\DOCUMENT\932790\A\CIVIL\DRG\S\00002940DN...TTB00262.DGN
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

Rev.